


## EROSION CONTROL NOTES

- 1. TEMPORARY ROLLED BARRIER SLOPE CHECKS SHALL BE INSTALLED ALONG A SINGLE CONTOUR LINE TO PREVENT EROSION. SEE DETAILS.
- 2. PROVIDE TEMPORARY INLET PROTECTION AT THE FIRST DOWNSTREAM INLET ON EACH MEDIAN CONCRETE DITCH.
- 3. ALL DISTURBED AREAS SHALL BE SEEDED AND HEAVY DUTY EROSION CONTROL BLANKET PLACED PER THE JOB SPECIFICATIONS.
- 4. PROVIDE TEMPORARY SILT FENCE AS DIRECTED BY THE ENGINEER.
- 5. SEE DETAIL SHEETS FOR ADDITIONAL EROSION AND SEDIMENT CONTROL DETAILS AND NOTES.
- 6. TEMPORARY SILT FENCE AND TEMPORARY ROLLED BARRIER SLOPE CHECKS ARE TO BE PAID FOR AS PERIMETER EROSION BARRIER.





ects/0		TERRA
\Proje	I	ENGINEERING LTD.

	USER NAME = WAH	DESIGNED -	REVISED -
١.		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 8/21/2012	DATE -	REVISED -
_			

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

EROSION CONTROL PLAN										
1–57 OVI	R OLD	RO	UTE	45	AND	ILL	.INOIS	CENTRAL	RAILRO	DAD
SCALE:	SHEET	NO.	1 (	OF :	2 SHEI	ETS	STA.	1030+00	TO STA.	1047+00

A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEE NO.
57	(38-2)HBVR, HVBR-1	IROQUOIS	146	28
		CONTRACT	NO. 6	6942
	ILLINOIS FED. A	ID PROJECT		