

0005

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0720D,01	0720D,01	0720D,02	0720D,01	0720D,01	80% FED
				80% FED 20% STATE	80% STATE 20% TOWN	50% STATE 50% TOWN	100% TOWN	100% STATE	80% FED 20% STATE
20200100	EARTH EXCAVATION	CU YD	9	9					
20700220	POROUS GRANULAR EMBANKMENT	CU YD	130	130					
21101600	TOPSOIL FURNISH & PLACE, VARIABLE DEPTH	SO YD	3705	3705					
* 25000110	SEEDING, CLASS 1A	ACRE	0.8	0.8					
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	69	69					
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	69	69					
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	69	69					
25100630	EROSION CONTROL BLANKET	SO YD	3705	3705					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	29	25	2	2			
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	12.2				12.2		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	4704	4544			160		
40600990	TEMPORARY RAMP	SQ YD	649	649					
40603305	HOT - MIX ASPHALT SURFACE COURSE, MIX "C", N30	TON	213	213					
40603335	HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	4,973	4,162	399	412			

FILE NAME = 68982.dgn	USER NAME = aubreygk	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 40,0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 3/21/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.S. RTE. 2361	SECTION 101RS-4;102RS-5	COUNTY MARSHALL	TOTAL SHEETS 51	SHEET NO. 4
CONTRACT NO. 68982				
ILLINOIS FED. AID PROJECT				

15