

0005

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				80% FED 20% STATE	80% STATE 20% TOWN	50% STATE 50% TOWN	100% TOWN	100% STATE	80% FED 20% STATE
40800050	INCIDENTAL HOT - MIX ASPHALT SURFACING	TON	331		331				
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SO YD	37	37					
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	7,488	3,297	4,191				
42400800	DETECTABLE WARNINGS	SO FT	859	859					
44000100	PAVEMENT REMOVAL	SO YD	90	90					
44000152	HOT - MIX ASPHALT SURFACE REMOVAL, 3/4"	SO YD	38197	38197					
44000155	HOT - MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	22442	14142		4744	3556		
44000161	HOT - MIX ASPHALT SURFACE REMOVAL, 3"	SO YD	675				675		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	34	34					
44000600	SIDEWALK REMOVAL	SQ FT	5208	1,761			3,447		
44022033	PARTIAL DEPTH REMOVAL 4"	SO YD	51	51					
48102100	AGGREGATE WEDGE SHOULDERS, TYPE B	TON	2108	2108					
48203029	HOT - MIX ASPHALT SHOULDERS, 8"	SO YD	280	280					
60260500	INLETS TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	4	4					
60603800	COMB. CONC. CURB AND GUTTER, TYPE B-6.12	FOOT	34	34					

15