

LOCATION OF WORK:

FAI 39 SOUTHBOUND URBAN INTERSTATE STA. 77+50 TO STA. 198+62
 FAI 39 SOUTHBOUND RURAL INTERSTATE STA. 198+62 TO STA. 234+91

FUNDING BREAKOUT:
 CONSTRUCTION TYPE CODE:

MCLEAN COUNTY 90% FEDERAL, 10% STATE
 MCLEAN COUNTY 90% FEDERAL, 10% STATE
 0004 0004

CODE NO.	ITEM	UNIT	TOTAL QUANTITY		
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	310.0	220.0	90.0
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	116.0	100.0	16.0
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	50.0	50.0	0.0
44213100	PAVEMENT FABRIC	SQ YD	9,800.0	8,300.0	1,500.0
44213200	SAW CUTS	FOOT	24,310.0	20,730.0	3,580.0
44213204	TIE BARS 3/4"	EACH	5,840.0	5,000.0	840.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	10,050.0	7,520.0	2,530.0
48300300	PORTLAND CEMENT CONCRETE SHOULDERS 8"	SQ YD	2,740.0	2,170.0	570.0
48300515	PORTLAND CEMENT CONCRETE SHOULDERS 10 3/4"	SQ YD	500.0	500.0	0.0
48300700	PORTLAND CEMENT CONCRETE SHOULDERS 12"	SQ YD	540.0	430.0	110.0
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	70.0	50.0	20.0
60100076	SHOULDER REMOVAL AND REPLACEMENT 11"	FOOT	30,510.0	22,990.0	7,520.0
60107600	PIPE UNDERDRAINS 4"	FOOT	30,010.0	22,640.0	7,370.0
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	1,150.0	840.0	310.0
• DENOTES SPECIALTY ITEM					