

SCHEDULE OF QUANTITIES

REMOVAL

PCC SURFACE REMOVAL – BUTT JOINT

	STATION	TO	STATION	THICKNESS (IN)	LENGTH (FOOT)	TOTAL WIDTH (FEET)	AREA (SQ YD)	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT 40600985 (SQ YD)
SB URBAN	126+82.71		127+42.71	2.00	60.00	16.0	106.7	106.7
MEDIAN CROSSOVER			149+04.00	2.00	MEASURED FROM CADD		19.9	19.9
TR 181 RAMP D	8+87.00		9+47.00	2.00	60.00	26.0	173.3	173.3
TR 181 RAMP A	8+01.00		8+61.00	2.00	60.00	26.0	173.3	173.3
							SB URBAN	473.2
							SB RURAL	0.0
							TOTAL	473.2
							ROUNDED	480.0

RAISED REFLECTIVE PAVEMENT MARKERS REMOVAL (SOUTHBOUND)

	STATION	TO	STATION	LENGTH (FOOT)	RAISED PAVEMENT MARKERS REMOVAL 78300200 (EACH)
SB URBAN	92+28.00		116+13.00	2385.00	60.0
SB URBAN	116+13.00		119+27.77	314.77	8.0
SB URBAN	129+22.71		141+40.00	1217.29	61.0
SB URBAN	141+40.00		144+17.00	277.00	7.0
SB URBAN	144+17.00		156+36.57	1219.57	31.0
STA EQ	156+36.57		156+23.97	0.00	
SB URBAN	156+23.97		174+40.00	1816.03	46.0
TR 181 A	0+00.00		3+03.56	303.56	16.0
TR 181 A	3+03.56		6+60.20	356.64	36.0
SB URBAN	182+70.00		198+61.67	1591.67	40.0
SB RURAL	198+61.67		229+25.00	3063.33	77.0
				SB URBAN TOTAL	305.0
				SB URBAN ROUNDED	310.0
				SB RURAL TOTAL	77.0
				SB RURAL ROUNDED	80.0

PCC SHOULDERS

	STA.	INSIDE WIDTH (FOOT)	STA.	OUTSIDE WIDTH (FOOT)	LENGTH (FOOT)	WIDTH (FOOT)	AREA (SQ YD)	PCC SHOULDERS 8" 48300300 (SQ YD)	PCC SHOULDERS 10 3/4" 48300515 (SQ YD)	PCC SHOULDERS 12" 48300700 (SQ YD)
I-55 GORE	84+63.00		89+88.00	MEASURED FROM CADD			492.6		492.6	
SB URBAN	77+50.00	0.0	89+88.00	10.0	1238.00	10.0	1375.6	1,375.6		
SB URBAN	89+88.00	6.0	90+48.00	10.0	60.00	16.0	106.7			106.7
SB URBAN	121+08.00	6.0	121+68.00	10.0	60.00	16.0	106.7			106.7
SB URBAN	121+68.00	0.0	123+22.00	10.0	154.00	10.0	171.1	171.1		
SB URBAN	176+20.00	6.0	176+80.00	10.0	60.00	16.0	106.7			106.7
SB URBAN	176+80.00	6.0	180+30.00	10.0	350.00	16.0	622.2	622.2		
SB URBAN	180+30.00	6.0	180+90.00	10.0	60.00	16.0	106.7			106.7
SB RURAL	231+05.00	6.0	231+65.00	10.0	60.00	16.0	106.7			106.7
SB RURAL	231+65.00	6.0	234+85.00	10.0	320.00	16.0	568.9	568.9		
							SOUTHBOUND URBAN TOTAL	2,168.9	492.6	426.7
							SOUTHBOUND URBAN ROUNDED	2,170.0	500.0	430.0
							SOUTHBOUND RURAL TOTAL	568.9	0.0	106.7
							SOUTHBOUND RURAL ROUNDED	570.0	0.0	110.0

*PCC SHOULDERS 8" SHALL BE 10 3/4" AT EOP TAPERED DOWN TO 6" AT EOS

**PCC SHOULDERS 12" TRANSITION FROM 10 3/4" AT EOP TO 12 3/4" AT EOP

FILE NAME =	USER NAME = hoganbj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pwork\pwork\hoganbj\d0339150\0570634-SHT-SCHEDULE.DGN	DRAWN -	REVISED -	39			57(2,3)RS(SB)	McLean	140	24	
PLOT SCALE = 40.0000' / in.	CHECKED -	REVISED -	CONTRACT NO. 70634							
PLOT DATE = 3/13/2013	DATE -	REVISED -	SCALE: NA			SHEET NO. 6 OF 11 SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT		