

LOCATION: FAI 74 (FAS 1520-CH 50)

URBAN	URBAN	URBAN
CHAMPAIGN CO.	CHAMPAIGN CO.	CHAMPAIGN CO.
STA. 13+75.00 TO	STA. 13+75.00 TO	STA. 19+48.38 TO
STA. 34+50.00	STA. 34+50.00	STA. 23+35.98
ROADWAY	PATH	BRIDGE (SN 010-0289)
FED. -90%, STATE-10%	VILL. OF MAHOMET-100%	FED. -90%, STATE-10%

CONSTRUCTION CODE: 0005 0028 0011

ITEM NO.	DESCRIPTION	UNIT	0005	0028	0011
51200958	FURNISHING METAL SHELL PILES 14" X 0.25"	FOOT	667.0	-	667.0
51202305	DRIVING PILES	FOOT	1935.0	-	1935.0
51203200	TEST PILE METAL SHELLS	EACH	5.0	-	5.0
51204650	PILE SHOES	EACH	67.0	-	67.0
51500100	NAME PLATES	EACH	1.0	-	1.0
52000110	PREFORMED JOINT STRIP SEAL	FOOT	96.0	-	96.0
52100020	ELASTOMETRIC BEARING ASSEMBLY, TYPE II	EACH	16.0	-	16.0
52100520	ANCHOR BOLTS, 1"	EACH	32.0	-	32.0
52100530	ANCHOR BOLTS, 1 1/4"	EACH	16.0	-	16.0
54002020	EXPANSION BOLTS 3/4 INCH	EACH	10.0	10.0	-
54210186	PIPE ELBOW, 18"	EACH	2.0	2.0	-
54213447	END SECTIONS, 12"	EACH	6.0	6.0	-
54213453	END SECTIONS, 18"	EACH	2.0	2.0	-
54213663	PRECAST CONCRETE FLARED END SECTIONS, 18"	EACH	6.0	5.0	1.0

FILE NAME :	USER NAME : cam-lookbm	DESIGNED BMC	REVISED -
c:\pwork\p\idat\cam-lookbm\d0208358\570790-shl-500.dgn		DRAWN BMC	REVISED -
	PLOT SCALE : 40.0000 1/1 in.	CHECKED -	REVISED -
	PLOT DATE : 11/9/2012	DATE 04-24-12	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: - SHEET NO. 5 OF 9 SHEETS STA. - TO STA. -

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	10-4BR	CHAMPAIGN	290	09
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 70700	