LOCATION: FAI 74 (FAS 1520-CH 50)

				URBAN CHAMPAIGN CO. STA. 13+75.00 TO STA. 34+50.00 ROADWAY FED.-90%, STATE-10%	URBAN CHAMPAIGN CO. STA. 13+75.00 TO STA. 18+75.00 PATH VILL. OF MAHOMET-100%	URBAN CHAMPAIGN CO. STA. 19+48.38 TO STA. 23+35.98 BRIDGE (SN 010-0289) FED.-90%, STATE-10%
		CONSTRUCTION CODE:		0005	0028	0011
* A2000192	TREE, ACER X FREEMANII AUTUMN FANTASY (AUTUMN FANTASY FREEMAN MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	6.0	6.0	-	-
* A2005020	TREE, GYMNOCLADUS DIOICUS (KENTUCKY COFFEETREE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2.0	2.0	-	-
* B2001160	TREE, CERCIDIPHYLLYM JAPONICUM (KATSURA TREE), 8' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	3.0	3.0	-	-
* B2005720	TREE, PYRUS CALLERYANA CHANTICLEER (CHANTICLEER CALLERY PEAR), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	5.0	5.0	-	-
* D2001724	EVERGREEN, PICEA ABIES (NORWAY SPRUCE), 2' HEIGHT, BALLED AND BURLAPPED	EACH	6.0	6.0	-	-
* D2001924	EVERGREEN, PICEA GLAUCA DENSATA (BLACK HILLS SPRUCE), 2' HEIGHT, BALLED AND BURLAPPED	EACH	3.0	3.0	-	-
X0327301	RELOCATE EXISTING MAILBOX	EACH	6.0	6.0	-	-
X6430120	REMOVE IMPACT ATTENUATOR, NO SALVAGE	EACH	2.0	2.0	-	-
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	LSUM	1.0	1.0	-	-
X7015005	CHANGEABLE MESSAGE SIGN	CAL. DAY	28.0	28.0	-	-
XZ193300	SURVEY MARKER TYPE 1 (SPECIAL)	EACH	5.0	5.0	-	-
Z0016702	DETOUR SIGNING	L SUM	1.0	1.0	-	-
Z0022800	FENCE REMOVAL	FOOT	390.0	328.0	62.0	-
Z0038700	PERMANENT BENCH MARKS	EACH	1.0	1.0	-	-
# Z0076600	TRAINEES	HOUR	500	500		
# Z0076604	TRAINEES, TRAINING PROGRAM GRADUATE	HOUR	500	500		

#0042 *SPECIALTY ITEM

FILE NAME = c:\pw_work\pwidot\cearlockbm\d0289368\D170700-sht-500.dgn	USER NAME = cearlockbm	DESIGNED BMC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE. 74	SECTION 10-4BR	COUNTY CHAMPAIGN	TOTAL SHEETS 290	SHEET NO. 13
	PLOT SCALE = 40.0000 ' / in.	DRAWN BMC	REVISED -					CONTRACT NO. 70700		
	PLOT DATE = 11/26/2012	CHECKED -	REVISED -		SCALE: - SHEET NO. 9 OF 9 SHEETS STA. - TO STA. -	FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
		DATE 04-24-12	REVISED -							