

50901720 BICYCLE RAILING - VILLAGE OF MAHOMET

STATION TO	STATION	LENGTH
LT. 13+75.00	18+75.00	500.0
Village of Mahomet Total =		500.0

50901720 BICYCLE RAILING - STATE

STATION TO	STATION	LENGTH
LT. 18+75.00	19+48.38	73.4
LT. 23+35.98	27+00.00	364.0
LT. 32+75.00	34+50.00	175.0
State Total =		612.4

PROJECT TOTAL =	1112.4
USE =	1113.0

60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 - VILLAGE OF MAHOMET

STATION TO	STATION	LENGTH
LT. 14+75.00	18+75.00	400.0
Village of Mahomet Sub-Total =		400.0

60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 - STATE

STATION TO	STATION	LENGTH
LT. 18+75.00	19+48.38	73.4
RT. 18+00.00	19+48.38	148.4
LT. 23+35.98	26+62.83	326.9
RT. 23+35.98	30+97.90	761.9
LT. 29+11.28	32+42.15	330.9
State Sub-Total =		1642.0

PROJECT TOTAL =	2042.0
-----------------	--------

66500105 WOVEN WIRE FENCE

STATION	O/S	TO	STATION	O/S	LENGTH (FT.)
18+94.96	80.8 LT.	19+48.38	36.4 LT.		70.0
19+48.38	36.4 LT.	19+48.38	26.4 LT.		10.0
19+48.38	19.6 RT.	19+48.38	29.6 RT.		10.0
19+48.38	29.6 RT.	20+05.00	51.2 RT.		59.0
22+69.00	59.0 LT.	23+35.98	36.4 LT.		75.0
23+35.98	36.4 LT.	23+35.98	26.4 LT.		10.0
23+35.98	19.6 RT.	23+35.98	29.6 RT.		10.0
23+35.98	29.6 RT.	23+97.50	95.6 RT.		87.0

PROJECT TOTAL =	331.0
-----------------	-------

78009004 MODIFIED URETHANE PAVEMENT MARKING - LINE 4" - VILLAGE OF MAHOMET

STATION TO	STATION	LENGTH (FT.)	WHITE EDGELINE (FT.)
13+75	18+00	425.0	850.0
Village of Mahomet Sub-Total =			850.0

78009004 MODIFIED URETHANE PAVEMENT MARKING - LINE 4" - STATE

STATION TO	STATION	LENGTH (FT.)	WHITE EDGELINE (FT.)
18+00	34+50	1650.0	3300.0

STATION TO	STATION	LENGTH (FT.)	DBL YELLOW CENTER LINE SOLID (FT.)
18+00	34+50	1650.0	3300.0
State Sub-Total =			6600.0

PROJECT TOTAL =	7450.0
-----------------	--------

XZ193300 SURVEY MARKER TYPE 1 (SPECIAL)

STATION	DESCRIPTION	EACH
14+23.05	PT	1.0
19+71.60	PC	1.0
26+00.26	PT	1.0
28+97.07	PC	1.0
32+62.61	PT	1.0

PROJECT TOTAL =	5.0
-----------------	-----

Z0038700 PERMANENT BENCH MARKS

LOCATION	EACH
BRIDGE WALL	1.0

PROJECT TOTAL =	1.0
-----------------	-----

NOTE: ACTUAL LOCATION TO BE SELECTED BY RESIDENT ENGINEER.

X0327301 RELOCATE EXISTING MAILBOX

GIRL SCOUT CAMP RD.

STATION	O/S	EACH
99+25.00	13.0 LT.	1.0
99+27.00	13.0 LT.	1.0
99+29.00	13.0 LT.	1.0
99+31.00	13.0 LT.	1.0

Sub-Total =	4.0
-------------	-----

CH 50

STATION	O/S	EACH
RT. 31+66.00	21.8 RT.	1.0
RT. 31+68.00	21.8 RT.	1.0

Sub-Total =	2.0
-------------	-----

PROJECT TOTAL =	6.0
-----------------	-----

72000100 SIGN PANEL TYPE 1

STATION	TYPE	O/S	SQ. FT.
23+40.00	W7-5 & W7-3P	29.5 LT.	5.25

PROJECT TOTAL =	5.25
-----------------	------

ADDITIONAL SCHEDULE NOTES:

- SEE G.N. Z0038 FOR INFORMATION CONCERNING PERMANENT BENCH MARKS.
- SEE SCHEDULES OF TEMPORARY ACCESS ROADWAYS 48
- SEE SCHEDULES OF EROSION CONTROL SHEET 58
- SEE SCHEDULES OF DRAINAGE SHEET(S) 63-64
- SEE SCHEDULES OF REMOVAL SHEET(S) 70-72
- SEE GUARDRAIL DETAILS SHEET 78-81