SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 100% STATE 0014		
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	24	24		
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	1550	1550		
Z0012110	BRIDGE DECK FLY ASH OR GGBF SLAG CONCRETE OVERLAY, 2 1/4"	SQ YD	1550	1550		
Z0012130	BRIDGE DECK SCARIFICATION 3/4"	SQ YD	1550	1550		
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	1	1		
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	67	67		

6

FILE NAME = c:\pw_work\pwidot\teasleyck\d0312934\D774601-sht-soq.dgn	USER NAME = teasleyck	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = 4/8/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
320	*	MACON	29	4
* D7 Bridge Repairs 2014-2		CONTRACT NO. 74601		
		ILLINOIS FED. AID PROJECT		