

PAINT PAVEMENT MARKING - LINE 4"

Stage 1			
Location		Quantity	
Station	to	Station	Foot
416+10	to	418+18	208
418+37	to	425+57	702
425+86	to	429+00	314
426+86	to	429+00	214
Total			1438
Stage 2			
Station	to	Station	
416+81	to	418+55	174
418+75	to	420+00	125
423+38	to	425+03	165
425+30	to	427+27	170
Total			634
Grand Total			2072

PAVEMENT MARKING REMOVAL

Stage 1				
Location		Length	Quantity	
Station	to	Station	Foot	Sq Ft
416+10	to	418+18	208	69
418+37	to	425+57	720	234
425+86	to	429+00	314	105
426+86	to	429+00	214	71
Total				479
Stage 2				
Station	to	Station		
416+81	to	418+55	174	58
418+75	to	420+00	125	42
423+38	to	425+03	165	55
425+30	to	427+27	197	57
Total				212
Grand Total			Grand Total	691

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

Stage 1				
Location		Length	Quantity	
Station	to	Station	Foot	Each
416+10	to	418+18	208	5
418+37	to	425+57	720	18
425+86	to	429+00	314	8
426+86	to	429+00	214	5
Total				36
Stage 2				
Location		Length	Quantity	
Station	to	Station		
416+81	to	418+55	174	4
418+75	to	420+00	125	3
423+38	to	425+03	165	4
425+30	to	427+27	197	4
Total				16
Grand Total			Grand Total	52

REPLACEMENT REFLECTOR

Stage 1				
Location		Length	Quantity	
Station	to	Station	Foot	Each
416+10	to	418+18	208	5
418+37	to	425+57	720	18
425+86	to	429+00	314	8
426+86	to	429+00	214	5
Total				36
Stage 2				
Station	to	Station		
416+81	to	418+55	174	4
418+75	to	420+00	125	3
423+38	to	425+03	165	4
425+30	to	427+27	197	4
Total				15
Grand Total			Grand Total	51

WET REFLECTIVE TEMPORARY TAPE

Stage 1			
Station	to	Station	
408+57	to	429+00	2043
414+15	to	434+47	4064
Total			6107
Stage 2			
Station	to	Station	
413+00	to	434+94	2194
409+60	to	431+00	4280
Total			6474
Grand Total			12581

WORK ZONE PAVEMENT MARKING REMOVAL

Stage 1				
Location		Length	Quantity	
Station	to	Station	Foot	Sq Ft
408+57	to	429+00	2043	681
414+15	to	434+47	4064	1355
Total			6107	2036
Stage 2				
Location		Length	Quantity	
Station	to	Station	Foot	Sq Ft
413+00	to	434+94	2194	731
409+60	to	431+00	4280	1427
Total			6474	2158
Grand Total			Grand Total	4194