

# SUMMARY OF QUANTITIES

| CODE NO  | ITEM                                | UNIT  | TOTAL | M240,01                  | M240,01                              | M240,02                  | CONSTRUCTION CODE     |                                     | M240,01               | 07AQL,01 |
|----------|-------------------------------------|-------|-------|--------------------------|--------------------------------------|--------------------------|-----------------------|-------------------------------------|-----------------------|----------|
|          |                                     |       |       | 80% FEDERAL<br>20% STATE | 80% FEDERAL<br>10% STATE<br>10% CITY | 80% FEDERAL<br>20% STATE | 80% STATE<br>20% CITY | 80% FEDERAL<br>20% STATE            | 100% STATE            |          |
|          |                                     |       |       | ROADWAY<br>0003          | TRAFFIC SIGNALS<br>0021              | TRAFFIC SIGNALS<br>0021  | BICYCLE/PEDS<br>0028  | MINOR STRUCTURES<br>0040            | TRAFFIC SIGNS<br>0021 |          |
|          |                                     |       |       | URBAN                    | ILLINOIS AVE                         | ALL OTHERS               |                       | S.N. 067-2427<br>PEDESTRIAN CULVERT | URBAN                 |          |
| 28000500 | INLET AND PIPE PROTECTION           | EACH  | 266   | 266                      |                                      |                          |                       |                                     |                       |          |
| 28001100 | TEMPORARY EROSION CONTROL BLANKET   | SQ YD | 10471 | 10471                    |                                      |                          |                       |                                     |                       |          |
| 28100205 | STONE RIPRAP, CLASS A3              | TON   | 48    | 48                       |                                      |                          |                       |                                     |                       |          |
| 28100207 | STONE RIPRAP, CLASS A4              | TON   | 1832  | 1832                     |                                      |                          |                       |                                     |                       |          |
| 28100209 | STONE RIPRAP, CLASS A5              | TON   | 544   | 544                      |                                      |                          |                       |                                     |                       |          |
| 28200200 | FILTER FABRIC                       | SQ YD | 6552  | 6552                     |                                      |                          |                       |                                     |                       |          |
| 28300400 | AGGREGATE DITCH                     | TON   | 2040  | 2040                     |                                      |                          |                       |                                     |                       |          |
| 31100100 | SUBBASE GRANULAR MATERIAL, TYPE A   | TON   | 91017 | 84250                    |                                      |                          | 6767                  |                                     |                       |          |
| 35101800 | AGGREGATE BASE COURSE, TYPE B 6"    | SQ YD | 507   | 507                      |                                      |                          |                       |                                     |                       |          |
| 35501306 | HOT-MIX ASPHALT BASE COURSE, 5 1/2" | SQ YD | 7723  | 7723                     |                                      |                          |                       |                                     |                       |          |
| 35501308 | HOT-MIX ASPHALT BASE COURSE, 6"     | SQ YD | 3311  | 3311                     |                                      |                          |                       |                                     |                       |          |
| 35501311 | HOT-MIX ASPHALT BASE COURSE, 6 3/4" | SQ YD | 59516 | 59516                    |                                      |                          |                       |                                     |                       |          |
| 35501316 | HOT-MIX ASPHALT BASE COURSE, 8"     | SQ YD | 920   | 920                      |                                      |                          |                       |                                     |                       |          |
| 35501324 | HOT-MIX ASPHALT BASE COURSE, 10"    | SQ YD | 234   | 234                      |                                      |                          |                       |                                     |                       |          |

• SPECIALTY ITEM

LAST SAVED = 1/25/2013  
 PEN TABLE = VB-HAIF-101  
 PLOT DRIVER = PLOTDRIVER\$=pltf9

|  |                      |            |           |
|--|----------------------|------------|-----------|
| FILE NAME =  | USER NAME = bschmidt | DESIGNED - | REVISED - |
| 1:\10011001\Phase II - 76017\Cad\1\Plans\003_0876017-shr-500.dgn |                      | DRAWN -    | REVISED - |
|  |                      | CHECKED -  | REVISED - |
|  |                      | DATE -     | REVISED - |

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**



**SUMMARY OF QUANTITIES**

SCALE: NONE      SHEET NO. 2 OF 25 SHEETS      STA.      TO STA.

| F.A.P. RTE.        | SECTION  | COUNTY | TOTAL SHEETS | SHEET NO. |
|--------------------|----------|--------|--------------|-----------|
| 312                | 68-WRS-1 | MONROE | 760          | 5         |
| CONTRACT NO. 76817 |          |        |              |           |

ILLINOIS FED. AID PROJECT