

SUMMARY OF QUANTITIES

M240,01 M240,01 M240,02 07CDL,01 M240,01 07A06,01

CODE NO	ITEM	UNIT	TOTAL	CONSTRUCTION CODE						
				80% FEDERAL 20% STATE	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 20% STATE	80% STATE 20% CITY	80% FEDERAL 20% STATE	100% STATE	
				ROADWAY 0003	TRAFFIC SIGNALS 0021	TRAFFIC SIGNALS 0021	BICYCLE/PEDS 0028	MINOR STRUCTURES 0040	TRAFFIC SIGNS 0021	
				URBAN	ILLINOIS AVE	ALL OTHERS		S. N. 067-2427 PEDESTRIAN CULVERT	URBAN	
55100500	STORM SEWER REMOVAL 12"	FOOT	749	749						
55100700	STORM SEWER REMOVAL 15"	FOOT	332	332						
55101200	STORM SEWER REMOVAL 24"	FOOT	181	181						
55101400	STORM SEWER REMOVAL 30"	FOOT	176	176						
55101600	STORM SEWER REMOVAL 36"	FOOT	209	209						
55200200	STORM SEWERS JACKED IN PLACE, 12"	FOOT	168	168						
55200400	STORM SEWERS JACKED IN PLACE, 15"	FOOT	83	83						
55200600	STORM SEWERS JACKED IN PLACE, 18"	FOOT	117	117						
55200900	STORM SEWERS JACKED IN PLACE, 24"	FOOT	131	131						
58000100	MEMBRANE WATERPROOFING	SQ FT	4344					4344		
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	319					319		
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	52	52						
60107600	PIPE UNDERDRAINS 4"	FOOT	31430	31430						
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	1216	1216						

* SPECIALTY ITEM

LAST SAVED * 1/25/2013
 PEN TABLE * Y8:Msif.tbl
 PLOT DRIVER * pdfplotter.exe

FILE NAME * H:\1001100\Phase II - 76817\Cad\T\Plans\003_0876817-sht-S00.dgn	USER NAME * bschmidt	DESIGNED -	REVISED -
PLOT SCALE * 2.0000 / 1 in.	PLOT DATE * 1/25/2013 3:20:24 PM	DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**



SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 12 OF 25 SHEETS STA. TO STA.

F.A.P. RTE. 312	SECTION 68-WRS-1	COUNTY MONROE	TOTAL SHEETS 760	SHEET NO. 15
CONTRACT NO. 76817				
ILLINOIS FED. AID PROJECT				