

# SUMMARY OF QUANTITIES

M240,01 M240,01 M240,02 07CDL,01 M240,01 07A0L,01

CODE NO	ITEM	UNIT	TOTAL	CONSTRUCTION CODE						
				80% FEDERAL 20% STATE	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 20% STATE	80% STATE 20% CITY	80% FEDERAL 20% STATE	100% STATE	
				ROADWAY 0003 URBAN	TRAFFIC SIGNALS 0021 ILLINOIS AVE	TRAFFIC SIGNALS 0021 ALL OTHERS	BICYCLE/PEDS 0028	MINOR STRUCTURES 0040 S. N. 067-2427 PEDESTRIAN CULVERT	TRAFFIC SIGNS 0021 URBAN	
Z0022800	FENCE REMOVAL	FOOT	3698	3698						
Z0023500	FILLING EXISTING CULVERTS	CU YD	37	37						
Z0026407	TEMPORARY SHEET PILING	SQ FT	1518					1518		
Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	1661					1661		
* Z0036200	PAINT CURB	FOOT	1834	1834						
Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	30439	30439						
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	236					236		
Z0055400	RUMBLE STRIP	FOOT	2763	2763						
* Z0056608	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	591	591						
* Z0056610	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	343	343						
* Z0056612	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	275	275						
* Z0056616	STORM SEWER (WATER MAIN REQUIREMENTS) 24 INCH	FOOT	128	128						
* Z0056620	STORM SEWER (WATER MAIN REQUIREMENTS) 30 INCH	FOOT	63	63						

\* SPECIALTY ITEM

13

LAST SAVED = 1/25/2013 3:28:30 PM  
 PEN TABLE = 1/25/2013 3:28:30 PM  
 PLOT DRIVER = 1/25/2013 3:28:30 PM

FILE NAME = I:\1001100\Phase II - 76817\Cad\1\Plans\003_0076817-sht-500.dgn	USER NAME = bschmidt	DESIGNED -	REVISED -
PLOT SCALE = 2.0000' = 1"	PLOT DATE = 1/25/2013 3:28:30 PM	DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**



## SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 24 OF 25 SHEETS STA. TO STA.

F.A.P. RTE. = 312	SECTION = 68-WRS-1	COUNTY = MONROE	TOTAL SHEETS = 760	SHEET NO. = 27
CONTRACT NO. 76817			ILLINOIS FED. AID PROJECT	