CURB & GUTTER / MEDIAN

LOCATION	STATION	CONCRETE CURB, TYPE B	COMBINATION CURB & GUTTER, TYPE B-6.06	COMBINATION CURB & GUTTER, TYPE B-6.12	COMBINATION CURB & GUTTER, TYPE B-6.12 (SPECIAL)	COMBINATION CURB & GUTTER, TYPE B-6.24	COMBINATION CURB & GUTTER, TYPE B-9.12 (SPECIAL)	COMBINATION CURB & GUTTER, TYPE B-9.24	COMBINATION CURB & GUTTER, TYPE M-2.12	COMBINATION CURB & GUTTER, TYPE M-2.12 (SPECIAL)	CONCRETE MEDIAN SURFACE, 4"	CONCRETE MEDIAN, TYPE SB (SPECIAL)	PROTECTIVE COAT	PAINT CURB	PRISMATIC CURB REFLECTOR
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	SQ FT	SQ YD	FOOT	EACH
GALL ROAD / N MOORE ST	500+51.00 123.34 RT TO 500+69.88 111.82 RT					22.5							8		
MARKETPLACE DRIVE	40+53.35 54.96 RT TO 41+20.00 21.81 RT					76.5							26		
	40+55.36 31.55 LT TO 41+20.00 18.47 LT					68.0							23		
N MARKET STREET	196+99.76 31.97 LT TO 197+14.81 21.19 LT	19.0											2		
	198+00.16 20.35 LT TO 199+09.69 60.19 LT					121.0							51		
	198+00.15 32.00 RT TO 199+49.59 49.40 RT					154.0							40		
	199+18.86 29.43 LT TO 199+36.35 53.93 LT		30.5										5		
	199+18.25 28.00 LT TO 199+48.18 29.97 LT					65.5					332		59	77	14
	200+37.06 23.95 LT TO 200+88.13 24.07 LT					186.0					998		173	146	22
	200+53.52 46.93 RT TO 200+83.81 45.00 RT					67.5					352		62	77	14
	200+53.56 83.02 LT TO 201+24.15 40.02 LT					84.0							28		
	200+65.55 72.51 RT TO 200+83.26 46.38 RT			31.5									7		
	200+95.29 74.41 RT TO 207+38.38 19.21 RT					701.5							234		
	SUBTOTAL	19.0	30.5	31.5	0.0	1546.5	0.0	0.0	0.0	0.0	1682	0	718	300	50
	TOTAL	208.0	89.5	117.5	803.0	10894.5	169.5	10487.5	362.0	123.5	5833	7712	9242	1834	291

CURB / MEDIAN / SIDEWALK REMOVAL

STATION	COMBINATION CURB & GUTTER REMOVAL	MEDIAN REMOVAL	SIDEWALK REMOVAL
	FOOT	SQ YD	SQ YD
IL ROUTE 3			
2047+70.95 TO 2050+00.00 RIGHT	229		
2050+00.00 TO 2056+14.29 RIGHT	614		
2056+48.15 TO 2058+20.00 RIGHT	172		
2059+20.00 TO 2065+00.00 RIGHT	580		
2065+00.00 TO 2067+76.46 RIGHT	276		
2059+70.00 TO 2062+87.95 LEFT	318		
2063+22.98 TO 2065+00.00 LEFT	177		
2065+00.00 TO 2067+77.70 LEFT	278		
2082+76.65 TO 2083+05.00 RIGHT	28		
2082+97.22 TO 2083+35.00 LEFT	38		
2083+60.00 TO 2084+06.52 RIGHT	47		
2084+00.00 TO 2084+24.81 LEFT	25		
2151+36.50 TO 2151+57.00 34.00 RIGHT		270	
2152+15.00 TO 2152+80.85 RIGHT	66		
2158+05.00 TO 2158+38.00 37.00 RIGHT		628	
2158+75.50 TO 2159+59.00 37.00 RIGHT		1561	
2159+35.00 TO 2163+64.41 LEFT	429		
2160+13.00 TO 2169+39.66 RIGHT	927		
2165+24.73 TO 2167+10.40 LEFT	186		
2167+29.23 TO 2167+40.29 LEFT	23		
2167+54.92 TO 2170+00.00 LEFT	245		
2170+00.00 TO 2170+68.98 LEFT	69		
SOUTHVIEW DRIVE			
50+49.40 TO 50+74.94 RIGHT	26		
50+49.40 TO 50+74.94 LEFT	26		
IL ROUTE 156			
5+23.44 TO 5+50.08 RIGHT			163
5+37.49 TO 6+47.65 LEFT	110		
6+20.00 TO 7+36.55 RIGHT	117		
6+30.64 TO 7+38.17 RIGHT			538
7+22.03 TO 7+94.01 LEFT	72		
8+48.55 TO 9+14.88 LEFT	66		
7+93.69 TO 8+70.91 RIGHT			463
7+94.91 TO 10+12.08 RIGHT	217		
10+34.77 TO 12+70.50 LEFT	236		
10+71.24 TO 12+70.50 RIGHT	199		
LAKEVIEW DRIVE			
90+33.61 TO 91+36.63 RIGHT	103		
90+64.00 TO 92+53.11 LEFT	189		
ILLINOIS AVENUE			
17+17.67 TO 19+56.95 LEFT	239		
18+50.60 TO 19+48.11 RIGHT	98		
20+23.41 TO 23+82.91 LEFT	360		
20+50.81 TO 23+82.91 RIGHT	332		
COLUMBIA AVENUE			
30+33.55 TO 31+95.30 RIGHT	162		
30+39.84 TO 31+13.50 LEFT	74		
MARKETPLACE DRIVE			
40+32.89 TO 40+87.73 RIGHT	55		
40+37.39 TO 40+87.73 LEFT	50		
N MARKET STREET			
198+00.00 TO 199+72.96 RIGHT	173		
198+00.00 TO 199+30.34 LEFT	130		
TOTAL	7761	2459	1164

SIDEWALK

LOCATION	STATION	PORTLAND CEMENT CONCRETE SIDEWALK, 4"	PORTLAND CEMENT CONCRETE SIDEWALK, 8"	DETECTABLE WARNINGS	PROTECTIVE COAT
		SQ FT	SQ FT	SQ FT	SQ YD
IL ROUTE 3	2014+48.36 LT			12	
	2014+75.59 TO 2015+04.23 LT		192	23	21
	2015+50.27 LT			12	
	2054+61.66 TO 2054+79.28 RT	155		20	17
	2055+20.97 TO 2058+11.91 RT	1865		36	207
	2057+97.96 TO 2058+50.81 LT	277		12	31
	2058+91.29 TO 2059+07.48 RT		93	24	10
	2082+94.14 TO 2083+06.39 RT		75	24	8
	2083+44.10 TO 2084+10.77 RT	378		24	42
	2083+93.80 TO 2084+11.50 LT		149	36	17
	2100+23.66 TO 2100+36.70 RT		86	24	10
	2100+76.67 TO 2100+94.08 RT		108	23	12
	2101+16.32 TO 2101+68.07 RT	444			49
	2118+67.85 TO 2118+82.17 RT	71		12	8
	2119+80.98 RT			10	
	2151+18.43 TO 2151+31.87 RT	57		24	6
	2152+07.38 TO 2152+17.54 RT	48			5
	2157+94.29 TO 2158+11.03 RT		105	24	12
	2158+77.97 TO 2159+04.20 RT		216	24	24
	2159+21.05 TO 2159+31.56 LT		96	24	11
IL 156	6+23.36 TO 7+41.75 RT	598		8	66
	7+84.82 TO 9+58.54 RT	882		8	98
	10+41.13 TO 11+70.84 LT	683		12	76
	10+77.19 TO 11+94.34 RT	605			67
	11+89.65 TO 12+70.50 LT	397			44
	12+31.91 TO 12+72.41 RT	192			21
LAKEVIEW AVENUE	90+76.77 TO 92+29.93 LT	754		10	84
ILLINOIS AVENUE	17+22.61 TO 19+09.40 LT	940		22	104
	19+00.00 TO 19+42.15 RT	222		12	25
	20+82.70 TO 23+89.41 RT	1577		12	175
COLUMBIA AVENUE	30+63.64 TO 31+83.45 LT	623		12	69
	30+66.82 TO 31+83.55 RT	944		12	105
N MARKET STREET	197+01.15 TO 199+09.20 LT	1074		22	119
	200+95.77 TO 201+77.05 RT	480		22	53
	TOTAL	13266	1120	540	1596

LAST SAVED = 1/25/2013
PEN TABLE = VB:-Half.tbl
PLOT DRIVER = pdfNOLAYERSbw.pltcfg

FILE NAME = I:\1001100_Phase II - 76817\Cad\T_Plans\005_D876817-sht-schedule.dgn
PLOT SCALE = 100.0000 ' / in.
PLOT DATE = 1/25/2013 3:28:50 PM

USER NAME = beriechmann
DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

HORNER & SHIFRIN, INC. ENGINEERS
SCALE: NONE

SCHEDULES OF QUANTITIES
CURB & GUTTER / MEDIAN,
CURB / MEDIAN, SIDEWALK REMOVAL, SIDEWALK

SHEET NO. 10 OF 32 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
312	68-WRS-1	MONROE	760	58

CONTRACT NO. 76817

ILLINOIS FED. AID PROJECT