MANHOLES

LOCATION	STATION	MANHOLE ID	TYPE A 4' - DIAMETER TYPE 1 FRAME, OPEN LID	4' - DIAMETER TYPE 1 FRAME, CLOSED LID	4' - DIAMETER TYPE 3 FRAME & GRATE	4' - DIAMETER TYPE 3V FRAME & GRATE	4' - DIAMETER TYPE 8 GRATE	WITH MEDIAN INLET (604101)	5' - DIAMETER TYPE 1 FRAME, CLOSED LID	5' - DIAMETER TYPE 3V FRAME & GRATE	5' - DIAMETER TYPE 8 GRATE	6' - DIAMETER TYPE 1 FRAME, CLOSED LID	6' - DIAMETER TYPE 3V FRAME & GRATE	6' - DIAMETER TYPE 24 FRAME & GRATE	7' - DIAMETER TYPE 1 FRAME, CLOSED LID	8' - DIAMETER TYPE 3V FRAME & GRATE	9' - DIAMETER TYPE 1 FRAME, CLOSED LID
			EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH
IL ROUTE 3	2160+00.00 54.00 LT	JJ5.1				1											
	2161+83.62 77.59 LT	JJ6										1					
	2162+00.00 54.00 LT	JJ7											1				
	2162+19.25 54.00 LT	JJ7.1											1				
	2162+50.00 54.00 LT	JJ8											1				
	2163+31.34 65.48 LT	JJ8.1											1				
	2163+50.00 58.21 LT	JJ9											1				
	2164+00.00 54.00 LT	JJ10											1				
	2164+59.52 66.80 LT	JJ11										1					
	2166+03.02 62.51 LT	JJ12									1						
	2166+66.11 60.67 LT	JJ12.1					1										
IL ROUTE 156	3+76.77 25.12 LT	M1.1					1										
	4+50.46 24.91 LT	M1.2					1										
	4+67.00 21.69 LT	M2				1											
	6+63.50 46.76 RT	L3				1											
	8+08.00 24.00 LT	L4.1				1											
	8+11.00 41.95 RT	L4				1											
	11+00.00 32.23 LT	Q14											1				
	11+05.00 32.26 RT	Q14.1				1											
	11+32.00 25.40 LT	Q15				1											
	12+57.31 24.73 LT	Q16		1													
LAKEVIEW	90+87.76 25.99 LT	L2				1											
ILLINOIS	20+97.00 39.05 RT	T9.1				1											
	21+20.00 20.00 LT	T9.2				1											
	22+70.74 20.00 LT	T9.4												1			
COLUMBIA	31+41.37 25.14 RT	SS1				1											
N MARKET ST	199+04.69 22.75 LT	JJ4.2	1														
	199+23.57 34.08 RT	II1				1											
	201+56.81 37.26 RT	DD2.1				1											
	201+61.27 78.92 RT	DD2													1		
	204+50.00 28.00 RT	GG2				1											
		SUBTOTAL	1	1	0	14	3	0	0	0	1	2	7	1	1	0	0
		TOTAL	1	4	3	55	5	1	3	9	2	3	13	1	1	1	1

SURVEY MARKERS

LOCATION	STATION	PERMANENT SURVEY MARKERS, TYPE I	LOCATION	STATION	PERMANENT SURVEY MARKERS, TYPE I
		EACH			EACH
IL ROUTE 3	1993+71.63	1	PT		
	2001+10.26	1		2161+67.90	1
	2012+37.69	1		2165+58.21	1
	2024+00.00	1	S LIBRARY STREET	17+91.57	1
	2032+73.70	1		21+00.18	1
	2040+23.36	1	SOUTHVIEW DRIVE	50+51.93	1
	2050+44.73	1	GALL RD / N MOORE ST	494+99.95	1
	2054+89.07	1		497+58.80	1
	2058+96.06	1		502+95.26	1
	2068+33.67	1		504+54.44	1
	2076+96.18	1	N MOORE STREET	604+17.16	1
	2079+00.00	1		606+83.72	1
	2092+08.22	1	BASEBALL FIELDS ACCESS ROAD	400+11.99	1
	2103+00.00	1		401+13.57	1
	2112+97.72	1		402+21.22	1
	2122+00.00	1		403+16.46	1
	2132+00.00	1		404+16.19	1
	2140+95.16	1		406+02.84	1
	2146+06.53	1	N MARKET STREET	202+68.32	1
	2154+00.00	1		204+94.42	1
	SUBTOTAL	20		SUBTOTAL	19
				TOTAL	39

BOLLARDS

LOCATION		BOLLARDS	FOLD DOWN BOLLARDS
		EACH	EACH
IL ROUTE 3			
2054+49.40	LT	1	
2054+49.40	-		1
2054+49.40	RT	1	
2055+29.29 TO 2057+80.37	RT	40	
SHARED USE PATH			
12015+85.13	LT	1	
12015+85.13	-		1
12015+85.13	RT	1	
12120+11.00	LT	1	
12120+11.00	-		1
12120+11.00	RT	1	
12123+95.38	LT	1	
12123+95.38	-		1
12123+95.38	RT	1	
SHARED USE PATH CONNECTOR			
1+58.00	LT	1	
1+58.00	-		1
1+58.00	RT	1	
BASEBALL ROAD SHARED USE PATH CONNECTOR			
81+33.83	LT	1	
81+33.83	-		1
81+33.83	RT	1	
	TOTAL	52	6

FENCE

STATION		CHAIN LINK FENCE, 5' (SPECIAL)	FENCE REMOVAL
IL ROUTE 3		FOOT	FOOT
2030+00.00 TO 2048+85.50	RT	1986	
2030+04.91 TO 2035+00.00	RT		503
2030+07.44 TO 2034+88.13	LT	481	
2030+07.97 TO 2035+00.00	LT		528
2035+00.00 TO 2036+19.13	LT		115
2035+00.00 TO 2050+00.00	RT		1554
2050+00.00 TO 2054+23.80	RT	418	
2050+00.00 TO 2055+79.94	RT		569
2083+51.99 TO 2085+18.83	RT	169	
2083+67.85 TO 2087+95.83	LT		429
2085+14.00 TO 2087+90.72	RT	282	
	TOTAL	3336	3698

TEMPORARY SOIL RETENTION SYSTEM

STATION	LT/RT	SQ FT
IL ROUTE 3		
2042+25.02	RIGHT	308
2074+48.31	RIGHT	386
2089+50.12	RIGHT	184
2115+79.04	LEFT	220
2130+98.50	RIGHT	327
	TOTAL	1425

LAST SAVED = 1/25/2013
PEN TABLE = VB-Half.tbl
PLOT DRIVER = pdfNOLAYERSbw.pltcfg

FILE NAME = I:\1001100_Phase II - 76817\Cad\T_Plans\005_D876817-sht-schedule.dgn
USER NAME = beriechmann
PLOT SCALE = 100.0000 ' / in.
PLOT DATE = 1/25/2013 3:28:53 PM

DESIGNED - | REVISED -
DRAWN - | REVISED -
CHECKED - | REVISED -
DATE - | REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

HORNER & SHIFRIN, INC. ENGINEERS

SCALE: NONE

SCHEDULES OF QUANTITIES
MAHOLES, SURVEY MARKERS, BOLLARDS, FENCE

SHEET NO. 15 OF 32 SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
312	68-WRS-1	MONROE	760	63

CONTRACT NO. 76817
ILLINOIS FED. AID PROJECT