STORM SEWERS

STATION	STORM SEWER ID	STORM SEWERS																																		SLOTTED DRAIN, 12" WITH 2-1/2" SLOT	TRENCH BACKFILL
		CLASS A																	CLASS B						JACKED IN PLACE				(WATER MAIN REQUIREMENTS)						
		TYPE 1							TYPE 2								TYPE 3		TYPE 1			TYPE 2														
		12"	15"	18"	24"	30"	42"	ERS 30"	12"	15"	18"	24"	30"	36"	42"	48"	24"	36"	12"	15"	24"	12"	24"	30"	12"	15"	18"	24"	12"	15"	18"	24"	30"		
		FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	CU YD
LAKEVIEW DRIVE																																					
90+87.76 25.99 LT TO 91+09.11 61.42 RT	L2-L1																									83											
91+12.71 45.49 LT TO 91+30.58 33.47 LT	O1.2-O1.1																		15																		
91+19.63 60.71 RT TO 91+30.26 51.57 RT	N3-N2																					7															
91+30.26 51.57 RT TO 92+00.00 58.67 RT	N2-N1																					64															
91+75.00 16.46 LT TO 91+94.00 16.65 LT	O3-O2																																			20	
91+94.00 16.65 LT TO 91+94.25 29.37 LT	O2-O1	12																																			
92+41.08 29.28 RT TO 92+57.64 55.94 RT	P2-P1																				24																
ILLINOIS AVENUE																																					
18+74.06 31.38 LT TO 2084+39.00 56.32 LT	U6.1-U6	47																																			4
20+97.00 39.05 RT TO 2082+66.00 50.72 RT	T9.1-T9												24																								11
21+20.00 20.00 LT TO 20+97.00 39.05 RT	T9.2-T9.1																																63				43
22+12.82 19.79 LT TO 21+20.00 20.00 LT	T9.3-T9.2												92																								37
22+70.74 20.00 RT TO 22+70.74 20.00 LT	T9.5-T9.4																												40								3
COLUMBIA AVENUE																																					
31+03.84 34.94 RT TO 31+41.37 25.14 RT	SS2-SS1																												38								1
N MARKET STREET																																					
198+65.33 45.54 LT TO 2159+53.80 89.43 LT	JJ4.1-JJ4													29																							
199+04.69 22.75 LT TO 2159+53.80 89.43 LT	JJ4.2-JJ4											37																									15
199+23.25 26.00 LT TO 199+04.69 22.75 LT	JJ4.3-JJ4.2								18																												3
199+23.57 34.08 RT TO 199+04.69 22.75 LT	II1-JJ4.2																											59									
200+80.00 21.82 LT TO 201+00.00 48.44 LT	LL3-LL2																								33												
201+00.00 48.44 LT TO 201+08.69 59.45 LT	LL2-LL1								7																												
201+25.00 49.55 RT TO 201+56.81 37.26 RT	DD2.2-DD2.1	33																																			3
201+56.81 37.26 RT TO 201+61.27 78.92 RT	DD2.1-DD2	40																																			
201+61.27 78.92 RT TO 202+57.50 60.51 RT	DD2-DD1												91																								
203+25.00 31.80 RT TO 203+30.08 45.41 RT	FF2-FF1	8																																			
204+50.00 28.00 RT TO 204+52.94 40.31 RT	GG2-GG1	6																																			
204+71.00 27.36 RT TO 204+50.00 28.00 RT	GG3-GG2	19																																			0
206+00.00 23.42 RT TO 204+93.40 46.01 RT	HH2-HH1	102																																			
206+50.00 21.90 RT TO 206+00.00 23.42 RT	HH3-HH2	50																																			1
SUBTOTAL		317	0	0	0	0	0	0	25	0	0	37	207	29	0	0	0	0	15	0	24	71	0	0	33	83	0	59	78	0	0	0	63	20	121
TOTAL		1153	734	477	292	83	397	20	3393	1896	1405	676	881	1751	101	26	126	44	46	35	101	112	152	134	168	83	117	131	591	343	275	128	63	20	4755

GUARDRAIL

LOCATION	STATION	STEEL PLATE BEAM GUARDRAIL, TYPE A 9' POSTS	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	TRAFFIC BARRIER TERMINAL, TYPE 2	GUARDRAIL MARKERS, TYPE A	TERMINAL MARKER - DIRECT APPLIED
		FOOT	EACH	EACH	EACH	EACH
IL ROUTE 3	2017+84.16 41.50 TO 2018+34.16 40.50 RT		1			1
	2018+34.16 40.50 TO 2020+09.16 40.50 RT	175.0			4	
	2018+34.43 40.50 TO 2018+46.93 40.50 LT			1		
	2018+46.93 40.50 TO 2020+21.93 40.50 LT	175.0			4	
	2020+09.16 40.50 TO 2020+21.66 40.50 RT			1		
	2020+21.93 40.50 TO 2020+71.93 41.64 LT		1			1
	TOTAL	350.0	2	2	8	2

LAST SAVED = 1/25/2013
PEN TABLE = V8-Half.tbl
PLOT DRIVER = pdfNOLAYERSbw.pltcfg

FILE NAME = I:\1001100_Phase II - 76817\Cad\T_Plans\005_DB76817-sht-schedule.dgn
USER NAME = beriechmann
PLOT SCALE = 100.0000 ' / in.
PLOT DATE = 1/25/2013 3:28:56 PM

DESIGNED - | REVISED -
DRAWN - | REVISED -
CHECKED - | REVISED -
DATE - | REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

HORNER & SHIFRIN, INC. ENGINEERS

SCHEDULES OF QUANTITIES
STORM SEWERS, GUARDRAIL

SCALE: NONE | SHEET NO. 21 OF 32 SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
312	68-WRS-1	MONROE	760	69

CONTRACT NO. 76817

ILLINOIS FED. AID PROJECT