


PLANTING NOTES:

1. TREE SHALL BE PLANTED SO ROOT FLARE IS 2" ABOVE ADJACENT FINISH GRADE.
2. ESTABLISHMENT AND PLANT MAINTENANCE SHALL BE PERFORMED PER THE STANDARD SPECIFICATIONS, ARTICLE 253.14 AND 253.15.
3. PLANTING SOIL SHALL BE ASTM D 5268 TOPSOIL, WITH PH RANGE OF 5.5 TO 7, A MINIMUM OF 4 PERCENT ORGANIC MATERIAL CONTENT; FREE OF STONES 1 INCH (25 MM) OR LARGER IN ANY DIMENSION AND OTHER EXTRANEIOUS MATERIALS HARMFUL TO PLANT GROWTH. MIX THE TOPSOIL WITH AMENDMENTS AND FERTILIZERS IN A RATIO OF LOOSE COMPOST TO TOPSOIL BY VOLUME OF 1:4 AND WEIGHT OF COMMERCIAL FERTILIZER PER 1000 SQ. FT., AS RECOMMENDED BY MANUFACTURER.
4. MULCH FOR ALL PLANTING BEDS SHALL BE HARDWARE BARK MULCH, DERIVED FROM DECIDUOUS HARDWOOD TREES FREE OF DISEASE AND INSECTS. PARTICLE SIZES SHALL BE NO LONGER THAN 3" IN LENGTH. THE MULCH SHALL BE MECHANICALLY SCREENED AND/OR SHREDDED FOR UNIFORM SIZE. SUBMIT A SAMPLE FOR REVIEW AND WRITTEN APPROVAL BY THE RESIDENT ENGINEER A MINIMUM OF 14 DAYS PRIOR TO DELIVERY.

NOTES:

1. THERE ARE SEVERAL FIBER OPTICS LINES IN THE AREA. THE CONTRACTOR SHALL HAND LOCATE AND EXPOSE THESE PRIOR TO EXCAVATING FOR THE PROJECT PARTICULARLY ALONG MISSOURI AVE. THIS WORK SHALL BE PAID FOR UNDER ARTICLE 109.04.
2. CAUTION, EXISTING UTILITIES, INCLUDING FIBER OPTIC, ELECTRICAL, TELEPHONE, WATER, AERIAL LINES AND OTHER FACILITIES, ARE LOCATED WITHIN THE LIMITS OF CONSTRUCTION. THE CONTRACTOR SHALL VERIFY THE UTILITY LOCATIONS PRIOR TO CONSTRUCTION. SEE SUBSURFACE UNDERGROUND ENGINEERING PLANS FOR ADDITIONAL INFORMATION.



USER NAME = dmeyer	DESIGNED - JJ0	REVISED -
PLOT SCALE = 100.0000' / 1" =	DRAWN - JJ0	REVISED -
PLOT DATE = 3/21/2013	CHECKED - PJM	REVISED -
	DATE - 03/20/13	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

LANDSCAPING PLAN

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
788	520-1-2	ST. CLAIR	142	71
CONTRACT NO. 76850				
ILLINOIS FED. AID PROJECT				