## PAVEMENT MARKING SCHEDULE

| LOCATION STATION TO STATION | LENGTH | PAINT PAVEMENT MARKING LINE 4" YELLOW DBL SOLID | PAINT PAVEMENT MARKING LINE 4" YELLOW SOLID | PAINT PAVEMENT MARKING LINE 4" YELLOW SKIP DASH | PAINT PAVEMENT MARKING LINE 4" WHITE SOLID | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | | FOOT | FOOT | FOOT | FOOT | FOOT | FOOT | |
| IL 14 (FAP 855) | | | | | | | | |
| | | | | | | | | |
| RURAL | | | | | | | | |
| 77+32 TO 80+91 | 359 | | | 90 | 718 | | | |
| 80+91 TO 91+47 | 1056 | | 1056 | 264 | 2112 | | | |
| 91+47 TO 115+76 | 2429 | 4858 | | | 4858 | | | |
| 115+76 TO 125+26 | 950 | | 950 | 238 | 1900 | | | |
| 125+26 TO 126+32 | 106 | | | 27 | 212 | | | |
| 126+32 TO 136+88 | 1056 | | 1056 | 264 | 2112 | | | |
| 136+88 TO 140+04 | 316 | 632 | | | 632 | | | |
| 140+04 TO 150+60 | 1056 | | 1056 | 264 | 2112 | | | |
| 150+60 TO 158+00 | 740 | | | 185 | 1480 | | | |
| 158+00 TO 164+86 | 686 | | 686 | 172 | 1372 | | | |
| 164+86 TO 167+50 | 264 | | | 66 | 528 | | | |
| 167+50 TO 172+78 | 528 | | 528 | 132 | 1056 | | | |
| 172+78 TO 174+89 | 211 | 422 | | | 422 | | | |
| 174+89 TO 181+76 | 687 | | 687 | 172 | 1374 | | | |
| 181+76 TO 183+87 | 211 | | | 53 | 422 | | | |
| 183+87 TO 192+84 | 897 | | 897 | 224 | 1794 | | | |
| 192+84 TO 193+90 | 106 | | | 27 | 212 | | | |
| 193+90 TO 204+46 | 1056 | | 1056 | 264 | 2112 | | | |
| 204+46 TO 213+96 | 950 | 1900 | | | 1900 | | | |
| 213+96 TO 224+52 | 1056 | | 1056 | 264 | 2112 | | | |
| 224+52 TO 229+80 | 528 | | | 132 | 1056 | | | |
| 229+80 TO 237+20 | 740 | | 740 | 185 | 1480 | | | |
| 237+20 TO 239+31 | 211 | | | 53 | 422 | | | |
| 239+31 TO 246+70 | 739 | | 739 | 185 | 1478 | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| SUB-TOTAL | | 7812 | 10507 | 3258 | 33876 | 0 | 0 | |
| RURAL SHEET TOTAL | | 55453 | | | | 0 | 0 | |

## PAVEMENT MARKING SCHEDULE

| LOCATION STATION TO STATION | LENGTH | PAINT PAVEMENT MARKING LINE 4" YELLOW DBL SOLID | PAINT PAVEMENT MARKING LINE 4" YELLOW SOLID | PAINT PAVEMENT MARKING LINE 4" YELLOW SKIP DASH | PAINT PAVEMENT MARKING LINE 4" WHITE SOLID | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | REMARKS |
|---|---|---|---|---|---|---|---|---|
| | | FOOT | FOOT | FOOT | FOOT | FOOT | FOOT | |
| IL 14 (FAP 855) | | | | | | | | |
| | | | | | | | | |
| RURAL (CONTINUED) | | | | | | | | |
| 246+70 TO 251+98 | 528 | | | 132 | 1056 | | | |
| 251+98 TO 256+20 | 422 | | 422 | 106 | 844 | | | |
| 256+20 TO 261+48 | 528 | | | 132 | 1056 | | | |
| 261+48 TO 266+76 | 528 | | 528 | 132 | 1056 | | | |
| 266+76 TO 348+41.58 BK | 8166 | | | 2041 | 16331 | | | |
| 348+41.7 AH TO 421+94 | 7352 | | | 1838 | 14705 | | | |
| 421+94 TO 433+56 | 1162 | | 1162 | 291 | 2324 | | | |
| 433+56 TO 437+78 | 422 | 844 | | | 844 | | | |
| 437+78 TO 445+16.65 BK | 739 | | 739 | 185 | 1477 | | | |
| 445+18.7 AH TO 447+29 | 210 | | 210 | 53 | 421 | | | |
| 447+29 TO 454+68 | 739 | | 739 | 185 | 1478 | | | |
| 454+68 TO 493+44 | 3876 | 7752 | | | 7752 | | | |
| 493+44 RT | | | | | | | 12 | |
| 493+95 | WHITE SKIP DASH (100') = | | | | 25 | | 12 | US 45 |
| 494+10 | WHITE SKIP DASH (100') = | | | | 25 | | 12 | US 45 |
| 494+60 LT | | | | | | | 12 | |
| 494+60 TO 521+73 | 2713 | | | 678 | 5426 | | | |
| 521+73 TO 525+96 | 423 | | 423 | 106 | 846 | | | |
| 525+96 TO 531+24 | 528 | | | 132 | 1056 | | | |
| 531+24 TO 536+52 | 528 | | 528 | 132 | 1056 | | | |
| 536+52 TO 540+74 | 422 | | | 106 | 844 | | | |
| 540+74 TO 548+13 | 739 | | 739 | 185 | 1478 | | | |
| 548+13 TO 553+41 | 528 | 1056 | | | 1056 | | | |
| 553+41 TO 562+92 | 951 | | 951 | 238 | 1902 | | | |
| 562+92 TO 572+42 | 950 | | | 238 | 1900 | | | |
| 572+42 TO 582+98 | 1056 | | 1056 | 264 | 2112 | | | |
| 582+98 TO 597+06 | 1408 | 2816 | | | 2816 | | | |
| | | | | | | | | |
| SUB-TOTAL | | 12468 | 7497 | 7171 | 69886 | 0 | 48 | |
| RURAL SHEET TOTAL | | 97022 | | | | 0 | 48 | |

| | | | | | |
|---|---|---|---|---|---|
| URBAN TOTAL | | 7398 | 100 | 0 | |
| RURAL TOTAL | | 152475 | 0 | 48 | |
| JOB TOTAL | | 159873 | 100 | 48 | |