

CONSTRUCTION JOINT &

**EXPANSION JOINT** 

DETAIL

CITY OF MOLINE

STANDARD

EXPANSION JOINT

DOWEL BARS SHALL BE GREASED TO THE SATISFACTION OF THE ENGINEER.

HOLES SHALL BE DRILLED IN PREFORMED

NO SLOTS OR GAPS WILL BE ALLOWED.

EXPANSION JOINT FILLER.

#6 x 24" EPOXY COATED DEFORMED BARS DRILLED & EPOXIED 9" INTO EXISTING CURB.

SAWED JOINT

SEE NOTE

LONGITUDINAL JOINT &

TRANSVERSE JOINT

DETAIL

#7

CITY OF MOLINE

STANDARD

NOTE:

COMBINATION CURB & GUTTER, B6.18 (MODIFIED)

A MINIMUM OF 6" BASE OF CA-6 EXTENDING I' BEHIND THE BACK OF CURB SHALL BE INCLUDED

CITY O MOLINE

I. AFTER SAWING, FLUSH JOINT WITH WATER OR AIR.

2. CLEAN BY SAND BLASTING UNTIL SURFACES ARE

3. JUST PRIOR TO INSTALLATION OF BACKER ROPE,

BLOW WITH OIL AND WATER FREE COMPRESSED

AIR TO ELIMINATE SAND AND WATER.

FREE OF SAWCUTTING FINES

CITY OF MOLINE DEPARTMENT OF PUBLIC WORKS - ENGINEERING DIVISION 3635 4TH AVENUE, MOLINE, IL 61265 (309) 524-2350 CITY ENGINEER - SCOTT HINTON, P.E.

NOTES:

12TH AVENUE OVERLAY 19TH STREET TO 34TH STREET DETAILS

| 3-21-13 | IDOT COMMENTS |
|---------|---------------|
| Date    | Revision      |

| 8-20-12                | sheet 39           |
|------------------------|--------------------|
| Scole NTS              | <b>4</b> 0         |
| Design Engineer<br>JWC | Project<br>MFT 254 |