

SUMMARY OF QUANTITIES

CONSTRUCTION TYPE CODE: 0011

PAY CODE	QUANTITY	UNIT	ITEM
20300100	210	CU. YD.	CHANNEL EXCAVATION
20400800	7	CU. YD.	FURNISHED EXCAVATION
25100630	4,030	SG. YD.	EROSION CONTROL BLANKET
28000250	83	POUND	TEMPORARY EROSION CONTROL SEEDING
28000305	58	FOOT	TEMPORARY DITCH CHECKS
28000400	300	FOOT	PERIMETER EROSION BARRIER
*40200100	613	TCN	AGGREGATE SURFACE COURSE, TYPE A
*50100100	1	EACH	REMOVAL OF EXISTING STRUCTURES
*50300225	28.8	CU. YD.	CONCRETE STRUCTURES
50400605	1,864	SO. FT.	PRECAST PRESTRESSED CONCRETE DECK BEAMS (33" DEPTH)
50800105	3,660	POUND	REINFORCEMENT BARS
+ *50900205	158	FOOT	STEEL RAILING, TYPE S1
51200957	412	FOOT	FURNISHING METAL SHELL PILES 12" X 0.250"
51202305	412	FOOT	DRIVING PILES
51203200	2	EACH	TEST PILE METAL SHELLS
51500100	1	EACH	NAME PLATES
67100100	1	L. SUM	MOBILIZATION
*X2020410	735	CU. YD.	EARTH EXCAVATION (SPECIAL)
*X2070302	150	TON	POROUS GRANULAR EMBANKMENT, SPECIAL
*X2501100	0.83	ACRE	SEEDING, CLASS 3 (SPECIAL)
*X2810210	1,068	TON	STONE RIPRAP, CLASS A5 (SPECIAL)
*X7010716	1	L. SUM	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)
70013798	1	L. SUM	CONSTRUCTION LAYOUT

*See B.L.R. 11310 in the contract documents for Special Provisions.

+Specialty Item



WILLETT HOFMANN
ASSOCIATES, INC.
ENGINEERING ARCHITECTURE LAND SURVEYING
809 EAST 2ND STREET, DIXON, IL 61021-0367
TEL: 815-284-3301 DESIGN FROM: #185-000518

DESIGNED -	IPN	REVISED -	-
CHECKED -	BKC	REVISED -	-
DRAWN -	FDL	REVISED -	-
CHECKED -	BKC	REVISED -	-

BUREAU COUNTY
T.R. 46 (350 E. ST.) OVER W. FORK SPOON RIVER
STATION 20+00

SUMMARY OF QUANTITIES
STRUCTURE NO. 006-4263

TWP. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
46	11-18103-00-BR	BUREAU	19	2
WHA* 1003012		CONTRACT NO. 87531		