

All elevations shown on the plans are established from U.S.G.S. mean sea level datum.

The Contractor shall seed all disturbed areas within the project limits.

No overhaul has been computed and none shall be paid for from any source.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications.

The location and elevation of the various underground utilities as shown on the plans are not to be taken as exact. The Contractor shall use special care when conducting construction operations near them to prevent damage.

AMEREN ILLINOIS
Attn: Bob Torres
P.O. Box 1428
340 Raccuglia Dr.
LaSalle, IL 61301
815-224-6275

FRONTIER COMMUNICATIONS
Attn: Carroll Burt
112 Elm Street
Sycamore, IL 60178
(815) 895-1538

CITY OF SPRINGFIELD, ILL.

COMCAST
Attn: Donna Zies
4450 Kishwaukee St.
Rockford, IL 61109
815-395-8977

A minimum of 48 hours advance notice is required for non-emergency work.

Where section or subsection monuments are encountered, the Engineer shall be notified before such monuments are removed. The Contractor shall protect and carefully preserve all property markers, monuments and right-of-way pins until the Owner, an Authorized Surveyor, or Agent has witnessed or otherwise referenced their location.

Where the proposed construction meets an existing bituminous surface, or where sawing is stated on the plans, the existing shall be sawed in a neat, straight line. Cost of sawing to be included in the contract unit price bid per Cubic Yard for Earth Excavation (Special).

All borrow/waste/use sites must be approved by the Illinois Department of Transportation prior to removing any material from the project site or initiating any earthmoving activities, including temporary stockpiling outside the limits of construction.

Tree clearing is prohibited between April 1st and September 30th.

EROSION CONTROL BLANKET

LOCATION	SG.	YD.	REMARKS
LT. STA. 18-SG. 00 - 21+20.00	357		
RT. STA. 18-SG. 00 - 21+20.00	375		
TOTAL	732	SG. YD.	25100630

LOCATION			POUND	REMARKS
LT.	STA.	18+90.00 - 21+20.00	8	100 LB./ACRE
RT.	STA.	18+90.00 - 21+20.00	8	100 LB./ACRE
TOTAL			16 POUND	28000250



DESIGNED	-	IAN NILAUSEN
CHECKED	-	BRAD KLEINMAIER
DRAWN	-	RON ALLEN
CHECKED	-	BRAD KLEINMAIER

PERIMETER EROSION BARRIER

LOCATION	FOOT	REMARKS
LT. STA. 18+90 - 19+02	12	
RT. STA. 18+90 - 19+69	99	
LT. STA. 19+05 - 19+10	5	
LT. STA. 19+21 - 19+28	7	
LT. STA. 19+31 - 19+69	57	
STA. 19+83 - 21+20	333	
TOTAL	513	FOOT
		28000400

LOCATION	TON	REMARKS
STA. 18+90.00 - 19+55.50	128	12"
STA. 20+44.50 - 21+20.00	132	12"
TOTAL	260 TON	*31100100

LOCATION	TON	REMARKS
P.E.L. STA. 19+16	17	8"
TOTAL	17 TON	*40200800

LOCATION	GALLON	REMARKS
STA. 18+90.00 - 19+55.50	17	0.10 GAL/SQ. YD. ON BIT.
STA. 20+44.50 - 21+20.00	18	0.10 GAL/SQ. YD. ON BIT.
STA. 18+90.00 - 19+55.50	75	0.40 GAL/SQ. YD. ON AGG.
STA. 20+44.50 - 21+20.00	77	0.40 GAL/SQ. YD. ON AGG.
TOTAL	187 GALLON	*40600100

LOCATION	TON	REMARKS
STA. 18+90.00 - 19+55.50	19	2"
STA. 20+44.50 - 21+20.00	20	2"
TOTAL	39 TON	40603305

LOCATION	TON	REMARKS
LT. STA. 18+80.00 - 19+03.07	2	6"
RT. STA. 18+80.00 - 19+55.50	7	6"
LT. STA. 19+27.50 - 19+55.50	4	6"
LT. STA. 20+44.50 - 21+20.00	12	6"
RT. STA. 20+44.50 - 21+20.00	11	6"
TOTAL	36	TON 48100.00

LOCATION	UNIT	REMARKS
36' LT. OF STA. 19+36	10	
31' LT. OF STA. 19+39	10	
32' LT. OF STA. 19+41	14	
33' LT. OF STA. 19+41	7	
34' LT. OF STA. 19+43	12	
34' RT. OF STA. 20+10	14	
28' LT. OF STA. 20+26	7	
33' RT. OF STA. 20+27	12	
25' RT. OF STA. 20+75	6	
28' RT. OF STA. 20+77	10	
24' RT. OF STA. 20+77	12	
22' LT. OF STA. 21+16	7	
24' LT. OF STA. 18+97	44	
32' LT. OF STA. 19+58	20	2 @ 22"
36' LT. OF STA. 19+60	20	
25' LT. OF STA. 20+66	18	
TOTAL 223	UNIT	*X2010400

LOCATION	ACRE	REMARKS
LT. STA. 18+90.00 - 21+20.00	0.08	
RT. STA. 18+90.00 - 21+20.00	0.08	
TOTAL	0.16 ACRE	*X2501100

LOCATION	TON	REMARKS
STA. 18+96.00 - 19+55.50	27	2 3/4"
STA. 20+44.50 - 21+20.00	27	2 3/4"
TOTAL	54 TON	*XX000001

* See Special Provisions.

BUREAU COUNTY
T.R. 398 OVER SPRING CREEK
STATION 20+00

GENERAL NOTES, COMMITMENTS & SCHEDULE OF QUANTITIES
STRUCTURE NO. 006-4143

TWP. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
398	09-1C113-00-BR	BUREAU	19	3
WIA* 1004012		CONTRACT NO. 87551		
ILLINOIS FED. AID PROJECT BR05-001(C54)				