INDEX TO SHEETS						
SHEET NO.	DESCRIPTION					
1	COVER SHEET					
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS					
3	PROPOSED SCOPE OF WORK PLAN					
4	SURVEY BASE SHEET					
5	PROPOSED SAFETY AND PHASING PLAN — WORK AREA 1					
6	PROPOSED SAFETY AND PHASING PLAN — WORK AREA 2					
7	PROPOSED SAFETY AND PHASING PLAN — WORK AREA 3					
8	CONSTRUCTION SAFETY AND PHASING DETAILS AND NOTES					
9	EXISTING SITE AND DEMOLITION PLAN					
10	PROPOSED TYPICAL SECTIONS					
11	PROPOSED CONSTRUCTION PLAN					
12	TAXILANE PLAN AND PROFILE					
13	TAXILANE CONNECTOR PLAN AND PROFILE					
14	PROPOSED JOINTING PLAN AND SPOT ELEVATION PLAN					
15	PAVEMENT JOINTING DETAILS					
16	PROPOSED MARKING PLAN					
17	STORMWATER POLLUTION PREVENTION DETAILS					
18	CONSTRUCTION PLAN — ADDITIVE ALTERNATE					

SUMMARY OF QUANTITIES - BASE BID							
ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES			
AR150510	FIELD OFFICE	LS	1				
AR150520	MOBILIZATION	LS	1				
AR150540	HAUL ROUTE	LS	1				
AR152410	UNCLASSIFIED EXCAVATION	CY	1,590				
AR156510	SILT FENCE	LF	325				
AR156520	INLET PROTECTION	EA	4				
AR162900	REMOVE CLASS E FENCE	LF	30				
AR162630	CLASS E GATE-30'	EA	1				
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	4,150				
AR401613	BIT. SURF. CSE METHOD I, SUPERPAVE	TON	665				
AR401650	BITUMINOUS PAVEMENT MILLING	SY	506				
AR403613	BIT. BASE CSE METHOD I, SUPERPAVE	TON	1,195				
AR501508	8" PCC PAVEMENT	SY	815				
AR501530	PCC TEST BATCH	EA	1				
AR602510	BITUMINOUS PRIME COAT	GAL	1,815				
AR603510	BITUMINOUS TACK COAT	GAL	1,088				
AR620520	PAVEMENT MARKING-WATERBORNE	SF	1,320				
AR620525	PAVEMENT MARKING-BLACK BORDER	SF	1,320				
AR701512	12" RCP, CLASS IV	LF	42				
AR752412	PRECAST REINFORCED CONC. FES 12"	EA	2				
AR800372	BITUMINOUS & PCC PAVEMENT REMOVAL	SY	5,806				
AR803015	TEMPORARY PAVEMENT	SY	370				
AR904510	SODDING	SY	160				

EARTHWORK QUANTITY SUMMARY (BASE BID):

CUT1,590	CY
FILL 120	CY
FILL + 15% 138	CY

SUMMARY OF QUANTITIES - ADDITIVE ALTERNATE 1						
ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES		
AS150530	TRAFFIC MAINTENANCE	LS	1			
AS610510	STRUCTURAL PC CONCRETE	CY	8.5			
AS620520	PAVEMENT MARKING-WATERBORNE	SF	30			
AS620525	PAVEMENT MARKING-BLACK BORDER	SF	30			
AS800372	BITUMINOUS & PCC PAVEMENT REMOVAL	SY	41			

GENERAL NOTES:

QUANTITIES

PAYMENT WILL BE MADE UNDER THE ITEM NUMBERS, DESCRIPTIONS AND UNITS NOTED IN THE ABOVE TABLE IN ACCORDANCE WITH THE BASIS OF PAYMENT FOR EACH RESPECTIVE WORK ITEM COMPLETED AND ACCEPTED BY THE ENGINEER.

CERTIFIED PAYROLLS
THE RESIDENT ENGINEER CANNOT FORWARD CONSTRUCTION REPORTS TO THE ILLINOIS DIVISION OF AERONAUTICS FOR PROCESSING UNTIL ALL CERTIFIED PAYROLLS FOR THE PERIOD HAVE BEEN RECEIVED.

MATERIAL CERTIFICATIONS

COMPLETED WORK CANNOT BE PLACED ON A CONSTRUCTION REPORT UNTIL ALL MATERIAL CERTIFICATIONS FOR THAT PAY ITEM HAVE BEEN RECEIVED, REVIEWED AND ACCEPTED BY THE RESIDENT ENGINEER.

SAINT LOUIS
DOWNTOWN
AIRPORT
A Puvision of Bi-State Development Agen

RECONSTRUCT TAXILANE IN NORTHWEST QUADRANT