



Illinois Department of Transportation

Division of Aeronautics

1 Langhorne Bond Drive / Capital Airport / Springfield, Illinois / 62707-8415

June 7, 2013

SUBJECT: Sparta Community Airport
Sparta, Illinois
Randolph County
Illinois Project Number: SAR-4224
SBG Project Number: 3-17-0094-B11
Contract No. SP023
Item No. 4A, June 14, 2013 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

Reason for Addendum:

Revised Plan Sheets No. 1 and 6
Revised Schedule of Prices
Revised page 21 of the Special Provisions

To All Plan Holders:

Replace Plan Sheet 1 with Revised Plan Sheet 1

- Pay Item number changed in Schedule of Quantities from AR801246 Tied Concrete Block Mat to AR801248 Tied Concrete Block Mat.

Replace Plan Sheet 6 with Revised Plan Sheet 6

- Additional barricades added and barricade locations changed.

Replace Plan Schedule of Prices dated 04/30/13 with Revised Schedule of Prices dated 06/06/13

- Pay Item number changed from AR801246 Tied Concrete Block Mat to AR801248 Tied Concrete Block Mat.

Replace Special Provision page 21 with Revised Special Provision page 21

- Pay Item number changed from AR801246 Tied Concrete Block Mat to AR801248 Tied Concrete Block Mat.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Questions on this addendum may be directed to Christopher Groth, P.E. of Crawford, Murphy & Tilly, Inc. at 217-572-1101.

STATE JOB #- - - -

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - SP023

ECMS002 DTGECM03 ECMR003 PAGE 1
 RUN DATE - 06/06/13
 RUN TIME - 183108

COUNTY NAME	CODE	DIST	AIRPORT NAME	FED PROJECT	ILL PROJECT
RANDOLPH	157	08	SPARTA COMMUNITY	3-17-0094-B11	SA-R -4224

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	3,975.000 X		=		
AR110102	DUCT MARKER - IN PAVEMENT	EACH	2.000 X		=		
AR110504	4-WAY CONCRETE ENCASED DUCT	L.F.	45.000 X		=		
AR125415	MITL-BASE MOUNTED	EACH	33.000 X		=		
AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EACH	2.000 X		=		
AR125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EACH	2.000 X		=		
AR125447	TAXI GUIDANCE SIGN, 7 CHARACTER	EACH	2.000 X		=		
AR125565	SPLICE CAN	EACH	1.000 X		=		
AR125610	REILS	PAIR	1.000 X		=		
AR125901	REMOVE STAKE MOUNTED LIGHT	EACH	3.000 X		=		
AR125904	REMOVE TAXI GUIDANCE SIGN	EACH	4.000 X		=		
AR125907	REMOVE REILS	PAIR	1.000 X		=		
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1.000 X		=		
AR150520	MOBILIZATION	L.S.	1.000 X		=		
AR151450	CLEARING AND GRUBBING	ACRE	0.250 X		=		

SPARTA COMMUNITY
 RANDOLPH

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - SP023

ECMS002 DTGECM03 ECMR003 PAGE 2
 RUN DATE - 06/06/13
 RUN TIME - 183108

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	7,000.000	X	=		
AR156510	SILT FENCE	L.F.	650.000	X	=		
AR156515	STRAW WATTLE	L.F.	270.000	X	=		
AR156520	INLET PROTECTION	EACH	1.000	X	=		
AR156530	TEMPORARY SEEDING	ACRE	3.500	X	=		
AR208540	OVERSIZE AGGREGATE	TON	1,800.000	X	=		
AR209600	GEOTEXTILE FABRIC	S.Y.	3,250.000	X	=		
AR209606	CRUSHED AGG. BASE COURSE - 6"	S.Y.	3,150.000	X	=		
AR401610	BITUMINOUS SURFACE COURSE	TON	325.000	X	=		
AR401655	BUTT JOINT CONSTRUCTION	S.Y.	234.000	X	=		
AR401921	REMOVE PAVEMENT	S.Y.	785.000	X	=		
AR403610	BITUMINOUS BASE COURSE	TON	455.000	X	=		
AR602510	BITUMINOUS PRIME COAT	GAL.	1,600.000	X	=		
AR603510	BITUMINOUS TACK COAT	GAL.	850.000	X	=		
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	3,000.000	X	=		

SPARTA COMMUNITY
 RANDOLPH

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT NUMBER - SP023

ECMS002 DTGECM03 ECMR003 PAGE 3
 RUN DATE - 06/06/13
 RUN TIME - 183108

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT OF MEASURE	QUANTITY	UNIT PRICE		TOTAL PRICE	
				DOLLARS	CENTS	DOLLARS	CTS
AR620525	PAVEMENT MARKING-BLACK BORDER	S.F.	1,960.000	X	=		
AR620900	PAVEMENT MARKING REMOVAL	S.F.	1,210.000	X	=		
AR625511	SEAL COAT	S.Y.	2,250.000	X	=		
AR701530	30" RCP, CLASS IV	L.F.	192.000	X	=		
AR701900	REMOVE PIPE	L.F.	140.000	X	=		
AR751410	INLET	EACH	1.000	X	=		
AR752430	PRECAST REINFORCED CONC. FES 30"	EACH	1.000	X	=		
AR752900	REMOVE END SECTION	EACH	1.000	X	=		
AR801248	TIED CONCRETE BLOCK MAT	S.F.	1,600.000	X	=		
AR901510	SEEDING	ACRE	3.500	X	=		
AR908510	MULCHING	ACRE	3.500	X	=		
AR908520	EXCELSIOR BLANKET	S.Y.	500.000	X	=		
AR908525	KNITTED STRAW MAT	S.Y.	2,050.000	X	=		

TOTAL \$

--	--

NOTE:
 *** PLEASE TURN PAGE FOR IMPORTANT NOTES ***

SPARTA COMMUNITY
RANDOLPH

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF PRICES
CONTRACT NUMBER - SP023

ECMS002 DTGECM03 ECMR003 PAGE 4
RUN DATE - 06/06/13
RUN TIME - 183108

NOTE:

1. EACH PAY ITEM SHOULD HAVE A UNIT PRICE AND A TOTAL PRICE.
2. THE UNIT PRICE SHALL GOVERN IF NO TOTAL PRICE IS SHOWN OR IF THERE IS A DISCREPANCY BETWEEN THE PRODUCT OF THE UNIT PRICE MULTIPLIED BY THE QUANTITY.
3. IF A UNIT PRICE IS OMITTED, THE TOTAL PRICE WILL BE DIVIDED BY THE QUANTITY IN ORDER TO ESTABLISH A UNIT PRICE.
4. A BID MAY BE DECLARED UNACCEPTABLE IF NEITHER A UNIT PRICE NOR A TOTAL PRICE IS SHOWN.

The installation and maintenance of the inlet protection shall be at the locations shown on the plans or as directed by the Engineer.

The Contractor shall maintain the inlet protection throughout the duration of the project. Efforts to maintain inlet protection shall include but not be limited to replacing installed inlet protection devices that are not functioning properly with new devices. The cost of maintaining the inlet protection throughout the project shall be considered incidental to the inlet protection pay item.

Upon completion or as directed, the Contractor shall remove the inlet protection and restore the area as needed.

156-3.8 TIED CONCRETE BLOCK MAT

Prior to placing the tied concrete block mats, prepare the subgrade to the slopes shown in the plans. All subgrade surfaces prepared for placement of mats shall be smooth and free of all rocks, stones, sticks, roots other protrusions or debris of any kind.

The prepared surface shall provide a firm unyielding foundation for the mats with no sharp or abrupt changes or breaks in the grade.

Apply seed directly to the prepared soil prior to installation of the Tied Concrete Block Mat. Use seed mix per Item 901.

Install mats to the line and grade shown on the plans and according to the manufacturer's installation guidelines. The manufacturer shall provide technical assistance during the slope preparation and installation of the tied concrete block mats as needed.

METHOD OF MEASUREMENT

156-4.4 ADD: The number of inlet protection structures to be paid for shall be the number satisfactorily installed, maintained and accepted by the Engineer.

156-4.5 ADD: The area of tied concrete block mat shall be the square feet of tied concrete block mat placed and accepted by the Engineer.

BASIS OF PAYMENT

156-5.1 ADD: Payment will be made at the Contract Unit Price for each Inlet Protection installed. Payment shall be made at the contract unit price for tied concrete block mat installed on the project.

Payment will be made under:

Item AR156510 – Silt Fence – per linear foot.

Item AR156514 – Straw Wattle – per each.

Item AR156520 – Inlet Protection – per each.

Item AR156530 – Temporary Seeding – per acre.

Item AR801248 – Tied Concrete Block Mat – per square foot.