VILLAGE NOTES

- 1) THE VILLAGE OF LIBERTYVILLE ENGINEERING DIVISION (847-918-2105) SHALL BE CONTACTED A MINIMUM OF 48 HOURS PRIOR TO THE COMMENCEMENT OF WORK, AND SHALL BE KEPT APPRISED OF THE PROJECT SCHEDULE THROUGHOUT THE DURATION OF CONSTRUCTION.
- 2) THE CONTRACTOR WILL BE RESPONSIBLE FOR ALL NECESSARY PRECAUTIONS TO ENSURE PROTECTION OF EXISTING BRICK PAVERS. ANY BRICK PAVERS THAT ARE REMOVED AND ARE NOT INTENDED TO BE REPLACED UPON COMPLETION OF THE IMPROVEMENTS SHALL BE RETURNED TO THE VILLAGE OF LIBERTYVILLE.
- 3) ALL EXISTING BRICK PAVER CROSSWALKS ARE TO REMAIN AND SHALL BE PROTECTED AS NECESSARY TO AVOID DAMAGE DURING CONSTRUCTION.
- 4) VILLAGE-OWNED IRRIGATION LINES ARE COMMONLY LOCATED IN CLOSE PROXIMITY OR BENEATH CURB LINES AND ROADWAYS ALONG MILWAUKEE AVE. BETWEEN CHURCH ST. AND JOHNSON AVE. ANY IRRIGATION LINES DAMAGED DURING CONSTRUCTION SHALL BE REPAIRED BY THE CONTRACTOR USING PVC GLUE FITTINGS AND WATERPROOF UNDERGROUND WIRE CONNECTIONS AFTER THE PIPE INTERIOR AND EXTERIOR AND WIRING ARE CLEANED AND PREPPED PER MANUFACTURER'S RECOMMENDATIONS.
- 5) THERE ARE DECORATIVE FENCING AND PLANTING AREAS LOCATED WITHIN THE BRICK PAVERS THROUGHOUT THE DOWNTOWN AREA THAT WILL NEED TO BE MAINTAINED AND PROTECTED DURING CONSTRUCTION.
- 6) THE CONTRACTOR SHALL COORDINATE WITH THE VILLAGE OF LIBERTYVILLE PARKS
 DIVISION (847) 918-2074 REGARDING IRRIGATION LINES. THE VILLAGE WILL REMOVE
 EXISTING IRRIGATION PIPING AND INSTALL NEW IRRIGATION PIPING FOR THE PLANTING
 BEDS. THE CONTRACTOR SHALL ALLOW THE VILLAGE ACCESS TO THE CONSTRUCTION SITE
 WHILE PAVERS ARE REMOVED TO COMPLETE THE NECESSARY IRRIGATION IMPROVEMENTS.



REVISED SHEET 5/29/2024

	USER NAME = Jammal.Alramahi	DESIGNED -	REVISED - JA 5/23/2024
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 5/23/2024	DATE -	REVISED -