

SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PARK ROADS	LASALLE	38	2
STA.	TO STA.			
IDNR PROJECT NO. 02-03-020			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	

CODE NO.	ITEM	UNIT	TOTAL	1000 100% STATE			1000 100% IDNR
20100110	TREE REMOVAL, (6 TO 15 UNITS, DIAMETER)	UNIT	402	402			
20100210	TREE REMOVAL, (OVER 15 UNITS, DIAMETER)	UNIT	210	210			
20100500	TREE REMOVAL, ACRE	ACRE	0.1	0.1			
20200100	EARTH EXCAVATION	CU YD	177	134			43
20800150	TRENCH BACKFILL	CU YD	60	57	3		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	580	580			
21101600	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	SQ YD	1,100	125	900		75
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,131	1,131			
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	200	200			
* 25000100	SEEDING, CLASS 1	ACRE	0.32	0.1	0.2		0.02
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	32	10	20		2
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	32	10	20		2
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	32	10	20		2
* 25100110	MULCH, METHOD 1	TON	1.1	0.5	0.5		0.1
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	32	10	20		2
28000400	PERIMETER EROSION BARRIER	FOOT	475	475			
28000500	INLET AND PIPE PROTECTION	EACH	8	7	1		
28100725	STONE DUMPED RIPRAP, CLASS B3	SQ YD	7	7			
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	TON	405	405			
35101400	AGGREGATE BASE COURSE, TYPE B	TON	281	196	5		80
40300700	PREPARATION OF BASE	TON	5,790	5,790			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL-BUTT JOINT	SQ YD	75				75
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	3,471	2,480	816		175
40603080	HOT-MIX ASPHALT, BINDER COURSE, IL-19.0, N50	TON	765	745			20

CODE NO.	ITEM	UNIT	TOTAL	1000 100% STATE			1000 100% IDNR
40603310	HOT-MIX ASPHALT, SURFACE COURSE, MIX "C", N50	TON	1,575	575	925		75
42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4"	SQ FT	1,195		1,195		
44000100	PAVEMENT REMOVAL	SQ YD	125				125
44000157	HOT-MIX ASPHALT SURFACE REMOVAL 2"	SQ YD	5,740	5,740			
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	200		200		
44000400	GUTTER REMOVAL	FOOT	327	327			
44000600	SIDEWALK REMOVAL	SQ FT	1,195		1,195		
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	14,310	5,790	7,875		645
48101200	AGGREGATE SHOULDERS, TYPE B	TON	70	60	10		
50105210	REMOVE EXISTING CULVERTS	FOOT	291	267	24		
54200427	PIPE CULVERT, TYPE 1 RCCP, 12"	FOOT	98	82	16		
54200430	PIPE CULVERT, TYPE 1 RCCP, 15"	FOOT	45	45			
54201279	PIPE CULVERT, TYPE 2 RCCP, 24"	FOOT	100	100			
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 12"	EACH	8	6	2		
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 15"	EACH	4	4			
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 24"	EACH	2	2			
60220230	MANHOLES, TYPE A, 4'-DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	1	1			
60238700	INLETS, TYPE A, WITH SPECIAL FRAME AND GRATE	EACH	1	1			
60500060	REMOVING INLETS	EACH	1	1			
60600095	CLASS S1 CONCRETE (OUTLET)	CU YD	44.4	44.4			
60602500	CONCRETE GUTTER, TYPE A	FOOT	1,341	1,341			
* 63300540	REMOVAL AND REPLACEMENT OF STEEL PLATE BEAM GUARDRAIL, SINGLE RAIL	FOOT	75	75			
* 63300905	VERTICAL ADJUSTMENT OF GUARDRAIL, TYPE A	FOOT	895				895

* SPECIALTY ITEM

- NOTES:
- ① BASE BID INCLUDES THE ENTRANCE ROAD UP TO THE PARKING AREAS.
 - ② ADDITIVE ALTERNATE NO. 1 INCLUDES RESURFACING THE ROADS AND PARKING AREAS WEST OF THE SERVICE DRIVE.
 - ③ ADDITIVE ALTERNATE NO. 2 INCLUDES VERTICALLY ADJUSTING THE GUARDRAIL.
 - ④ ADDITIVE ALTERNATE NO. 3 INCLUDES THE SERVICE DRIVE.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 IDOT / IDNR
 BUFFALO ROCK STATE PARK

SCALE: VERT.
 HORIZ.
 DATE: 12/12/06

DRAWN BY: JJ
 CHECKED BY: PJM