

SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PARK ROADS	LASALLE	38	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
IDNR PROJECT NO. 02-03-020				

CODE NO.	ITEM	UNIT	TOTAL	1000 100% STATE		1000 100% IDNR
67100100	MOBILIZATION	L SUM	1	1		
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	1		
* 72000100	SIGN PANEL- TYPE 1	SQ FT	45	29	16	
* 72900100	METAL POST, TYPE A	FOOT	70		70	
* 73000100	WOOD SIGN SUPPORT	FOOT	120	120		
* 78000100	THERMOPLASTIC PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	40		40	
* 78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FOOT	15,310	9,750	5,560	
* 78000400	THERMOPLASTIC PAVEMENT MARKING-LINE 6"	FOOT	230		230	
* 78000650	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	FOOT	15	15		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
X0325796	GATES TO BE REMOVED AND RE-ERECTED	EACH	1	1		
X0325797	REMOVE AND REINSTALL PARKING BLOCKS	EACH	89		89	
* X0325798	WOODEN PARKING BLOCKS	EACH	25		25	
* A2002916	TREE, CELTIS OCCIDENTIALIS (COMMON HACKBERRY), 2" CALIPER, BALLED AND BURLAPPED	EACH	6	6		
* A2005614	TREE, OSTRYA VIRGINIANA (AMERICAN HOPHORNBEAM/IRONWOOD), 1.75" CALIPER, BALLED AND BURLAPPED	EACH	5	5		
* A2006416	TREE, QUERCUS ALBA (WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	3	3		
* A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	7	7		
* A2006716	TREE, QUERCUS MACROCARPA (BUR OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	10	10		
* A2006816	TREE, QUERCUS MUEHLENBERGII (CHINKAPIN OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	7	7		
* A2007816	TREE, TILIA AMERICANA (AMERICAN LINDEN/BASSWOOD), 2" CALIPER, BALLED AND BURLAPPED	EACH	7	7		
* B2001116	TREE EASTERN CERCIS CANADENSIS (REBUD), 2" CALIPER, BALLED AND BURLAPPED	EACH	5	5		
* D2001980	EVERGREEN PINUS STROBUS (EASTERN WHITE PINE), 8' HEIGHT, BALLED AND BURLAPPED	EACH	5	5		

* SPECIALTY ITEM

* SPECIAL PROVISION

- NOTES:
- ① BASE BID INCLUDES THE ENTRANCE ROAD UP TO THE PARKING AREAS.
 - ② ADDITIVE ALTERNATE NO. 1 INCLUDES RESURFACING THE ROADS AND PARKING AREAS WEST OF THE SERVICE DRIVE.
 - ③ ADDITIVE ALTERNATE NO. 2 INCLUDES VERTICALLY ADJUSTING THE GUARDRAIL.
 - ④ ADDITIVE ALTERNATE NO. 3 INCLUDES THE SERVICE DRIVE.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
IDOT / IDNR
BUFFALO ROCK STATE PARK

SCALE: VERT.
HORIZ.
DATE: 12/12/06

DRAWN BY: JJ
CHECKED BY: PJM