COOK

COUNTY TOTAL SHEET SHEETS NO.

## STATE OF ILLINOIS

# DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS

FOR INDEX OF SHEETS, SEE SHEET NO. 2

# PROPOSED HIGHWAY PLANS

F.A.U. 2592: HICKS ROAD & FAP 305: US 14 SECTION: 531 RS-1

HICKS RD. - KIRCHOFF RD. TO FIRST BANK DR. US 14 - HICKS RD. TO E/O PLUM GROVE RD. RESURFACING (MAINTENANCE)

COOK COUNTY

C-91-246-98


THE IMPROVEMENT IS LOCATED IN THE VILLAGE OF PALATINE AND THE CITY OF ROLLING MEADOWS

TRAFFIC DATA
SPEED LIMIT: 35-40 MPH
2005 ADT: 33,300

FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

J.U.L.I.E.
JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION
1-800-892-0123

CONTRACT NO. 60620




GROSS LENGTH OF IMPROVEMENT = 15,829 FEET (3.00 MILES)
NET LENGTH OF IMPROVEMENT = 14,998 FEET (2.84 MILES)

D-91-246-98



\* SECTION \* 531 RS-1

\*FAU 2592 & FAP 305



PRINTED BY THE AUTHORITY
OF THE STATE OF ILLINOIS

DISTRICT 1 - PLAN PREPARATION ENGINEER: KEN ENG / LONG TRAN (8

705-4240

1

#### CONTRACT #60620

			.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	30020				
F.A.U. RTE.	SECTION	COUNT	TOTAL SHEETS	SHEET NO.				
*	531 RS-1	COOR	34	2				
STA. TO STA.								
FED. ROAD DIST. NO. 1 ILLINOIS HIGHWAY PROJECT								

\* FAU 2592 & FAP 305

#### INDEX OF SHEETS

scts\d32465fhsh\_rdwy.den 4/24/2007 [ 55: 18 PM liser dran]:

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4-5	TYPICAL SECTIONS AND HMA MIXTURE REQUIREMENTS
6-12	PROPOSED ROADWAY AND PAVEMENT MARKING PLANS
13-22	DETECTOR LOOP REPLACEMENT
23	DETAILS FOR FRAMES AND LIDS ADJUSTMENT WITH MILLING
24	PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT
25	CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT
26	BUTT JOINT AND HMA TAPER DETAILS
27	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS
28	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)
29	DISTRICT ONE TYPICAL PAVEMENT MARKINGS
30	TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC)
31	PAVEMENT MARKING LETTERS AND SYMBOLS FOR TRAFFIC STAGING
32	ARTERIAL ROAD INFORMATION SIGN
33	TYPICAL SUPPLEMENTAL SIGNING AND PAVEMENT MARKING TREATMENT FOR RAILROAD CROSSINGS
34	DISTRICT ONE DETECTOR LOOP INSTALLATION DETAIL FOR ROADWAY RESURFACING

#### STATE STANDARDS

000001-04	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
442201-02	CLASS C AND D PATCHES
604001-02	FRAME AND LIDS, TYPE 1
604086-01	FRAME AND GRATE, TYPE 23
606001-03	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
701601-04	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W, WITH NON-TRAVERSABLE MEDIAN
701602-02	URBAN LANE CLOSURE, MULTILANE, 2W WITH BIDIRECTIONAL LEFT TURN LANE
701606-04	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701701-04	URBAN LANE CLOSURE, MULTILANE INTERSECTION
702001-06	TRAFFIC CONTROL DEVICES

#### GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 FOR FIELD LOCATIONS OR BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES. (48 HOUR NOTIFICATION REQUIRED)

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES AND THE CITY OF ROLLING MEADOWS & THE VILLAGE OF PALATINE.

THE CONTRACTOR WILL NOT BE ABLE TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT THE WRITTEN PERMISSION OF THE DEPARTMENT.

ALL HOT-MIX ASPHALT PAVEMENT PATCHING SHALL BE CLASS D.

BUTT JOINTS WILL BE INSTALLED AT THE ENDS OF RESURFACING (WHERE RESURFACING MEETS EXISTING PAVEMENT). IN ACCORDANCE WITH THE "BUTT JOINT AND HOT MIX ASPHALT TAPER DETAILS" SHEET INCLUDED IN THE PLANS UNLESS OTHERWISE SPECIFIED.

THE RESIDENT ENGINEER SHALL CONTACT MS. PATRICE HARRIS, AT (708) 597-9800 A MINIMUM OF 72 HOURS PRIOR TO PLACEMENT OF PERMANENT PAVEMENT MARKINGS.

3 METER (10 FEET) TRANSITION SHALL BE USED TO MATCH PROPOSED CURB AND GUTTER TO EXISTING CURB AND GUTTERS IN THE FIELD, UNLESS OTHERWISE SHOWN. THE TRANSITION SHALL BE PAID FOR AT THE CONTRACT UNTI PRICE FOR THE PROPOSED ITEMS OF WORK SPECIFIED.

WHEN MILLED PAVEMENT IS OPEN TO TRAFFIC, THE MAXIMUM GRADE DIFFERENTIAL BETWEEN PASSES OF THE MILLING MACHINE SHALL NOT EXCEED 1 1/2 INCHES WHERE THE SPEED LIMIT IS 45 MPH OR LESS, AND 1 INCH WHERE THE SPEED LIMIT IS GREATER THAN 45 MPH. WITH WRITTEN APPROVAL FROM THE RESIDENT ENGINEER. A MAXIMUM GRADE DIFFERENTIAL OF 3 INCHES MAY BE ALLOWED IF THE EDGE OF THE MILLING IS SLOPED A MINIMUM OF 1:3 (V:H).

THE UNIT WEIGHT (CONVERSION FACTOR) QUOTED IS FOR THE ESTIMATING PLAN QUANTITIES ONLY. ACTUAL QUANTITIES TO FULFILL CONTRACT REQUIREMENTS WILL BE DETERMINED BASED ON UNIT WEIGHT OF APPROVED MIX DESIGN, PLAN DIMENSIONS, AND DENSITY LIMITATIONS. MAXIMUM PAYMENT WILL BE COMPUTED BASED ON WEIGHT AVERAGE DENSITIES OF THE IN-PLACE MIXTURE.

THE RESIDENT ENGINEER SHALL VERIFY THE LOCATIONS OF ALL EXISTING PAVEMENT MARKINGS PRIOR TO MILLING OR RESURFACING.

LIMIT OF RESURFACING ON SIDE-STREETS THROUGH OUT THE IMPROVEMENT SHALL BE TO THE RADIUS OF RETURN OR AS DIRECTED BY THE ENGINEER.

ALL FINAL PAVEMENT MARKINGS SHALL BE THERMOPLASTIC (OF THE EXTRUDED TYPE) AND SHOULD BE PLACED IN ACCORDANCE WITH "DISTRICT ONE TYPICAL PAVEMENT MARKINGS" DETAIL (TC-13).

ALL RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED IN ACCORDANCE WITH THE DISTRICT ONE "TYPICAL APLLICATIONS RAISED REFLECTIVE PAVEMENT MARKER DETAIL" (TC-11).

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE ARTERIAL TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

REVISIONS	T	THE THOSE OFFICE	IT OF TRANSPORT
NAME	DATE	ILLINOIS DEPARTMEN	IT OF TRANSPORTATION
		HTCK	(S ROAD
		11201	io mone
		INDEX OF SHEETS	, STATE STANDARDS,
			ERAL NOTES
			ENAL NOTES
		SCALE: VERT. NONE HORIZ. NONE	DRAWN BY
		DATE HORIZ. NONE	CHECKED BY

| CONTRACT COG20
RTE.	SECTION	COUNTY	TOTAL	SHEET	NO.
# 531 RS-1	COOK	3.4	3		
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT			
# FAU 2592 & FAP 305					


	SUMMARY OF QUANTITIES			1	CONSTRUCTION TYPE CODE						¥ FAU 2592 & FAF	305		
	JOMMAN OF QUANTITIES				CONSTRUCTION TIPE CODE		SUMMARY OF QUANTITIES				CONSTRUCT	ION TYPE	CODE	
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN IOOO 100% STATE		CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN IOOO 100% STATE				
40 <b>6</b> 00200	BITUMINOUS MATERIALS (PRIME COAT)	TON	50	50		70102632	TRAFFIC CONTROL AND PROTECTION,	L SUM	1					
40600300	AGGREGATE (PRIME COAT)	TON	225	225			STANDARD 701602	L JOW	1	1				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	40	40		70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11515	11515				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	755	755		70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2060	2060				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	490	490		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	41855	41855				·
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	11105	11105		70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	5795	5795	·			
42001300	PROTECTIVE COAT	SQ YD	850	850		70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	325	325				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	110000	110000		70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1091	1091				
14001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3820	3820		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1461	1461				
14002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	2120	2120	i	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	11780	11780				
14201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	1520	1520		* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	2060	2060				
	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	350	350		* 78000200	THERMOPLASTIC PAVEMENT MARKING	FOOT	41855	41855				
	CLASS D PATCHES, TYPE IV, 10 INCH STORM SEWERS TO BE CLEANED	SQ YD	250	250		* 78000400	- LINE 4"							
		FOOT	500	500		7 10000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	5795	5795				
	CATCH BASINS TO BE ADJUSTED  CATCH BASINS TO BE ADJUSTED WITH NEW	EACH EACH	30	30 40	-	* 78000500	THERMOPLASTIC PAVEMENT MARKING	FOOT	325	325				
	TYPE 24 FRAME AND GRATE FRAMES AND GRATES TO BE ADJUSTED	EACH				* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1091	1091				
1	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	90	90		* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1461	1461			To the second se	
0406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	25	25		* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1910	1910				
0406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	65	65		78300200	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1585	1585				
7000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6		* 88600600	REMOVAL							
7100100	MOBILIZATION	L SUM	1	1		X0322256	DETECTOR LOOP REPLACEMENT	F00T	3966	3966				
0102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1			TEMPORARY INFORMATION SIGNING POLYMERIZED LEVELING BINDER (MACHINE	SQ FT TON	78	78				
0102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1			METHOD), IL-4.75, N50		4760	4760				
`							DRAINAGE STRUCTURES TO BE CLEANED	EACH	150	150				
						Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				

Tprojects/o124699/sh\_noky.age 4/24/2007 2:10:07 PM User-tranit

\* SPECIALTY ITEM

REVISIONS

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
HICKS RD. & US 14



\* FAU 2592 & FAP 305

#### LEGEND


- 1) EXISTING P.C.C. PAVEMENT, 8" (±)
- 2) EXISTING P.C.C. PAVEMENT, 9 1/2" (±)
- (3) EXISTING CONCRETE PAVEMENT, 7 1/2" (±)
- (4) EXISTING HMA PAVEMENT, 10" (±)
- 5) EXISTING BARRIER MEDIAN
- (6) EXISTING HMA SHOULDER
- 7) EXISTING HMA OVERLAY, 4" (±)
- (8) EXISTING HMA BASE COURSE WIDENING, 8" (±)
- (9) EXISTING COMBINATION CONCRETE CURB & GUTTER TYPE B-6.24 (MOD.)
- (10) EXISTING COMBINATION CONCRETE CURB & GUTTER TYPE M-2.12
- (11) EXISTING STABILIZED MEDIAN, 12"
- (12) EXISTING AGGREGATE SUBBASE, TYPE B
- (13) EXISTING STABILIZED SUBBASE
- (14) PROPOSED HMA SURFACE REMOVAL, 2 1/2"
- (15) PROPOSED POLYMERIZED HMA SURFACE COURSE, MIX "F", N90, 1 3/4"
- (16) PROPOSED POLYMERIZED LEVELING BINDER (MM), IL-4.75, N50, 3/4"

#### HOT-MIX ASPHALT MIXTURE REQUIREMENTS

MIXTURE TYPE	AC TYPE	AIR VOIDS
PAVEMENT RESURFACING:		
POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	SBS/SBR PG 76-28/-22	4.0% @ 50 GYR
POLYMERIZED HMA SURFACE COURSE, MIX "F", N90 (IL-9.5MM)	SBS/SBR PG 70-22	4.0% @ 90 GYR
PAVEMENT PATCHING:		
CLASS D PATCHES (HMA BINDER IL-19.0 MM)	PG 64-22 / 58-22*	4.0% @ 70 GYR
HMA REPLACEMENT OVER PATCHES (HMA BINDER IL-19.0 MM)	PG 64-22 / 58-22*	4.0% @ 70 GYR

THE UNIT WEIGHT USED TO CALCULATE ALL HMA SURFACE MIX QUANTITIES IS 112 LBS / SQ YD / IN \*\* WHEN RAP EXCEEDS 20% THE NEW ASPHALT BINDER IN THE MIX SHALL BE PG 58-22

# REVISIONS NAME DATE HICKS ROAD EXISTING AND PROPOSED TYPICAL SECTIONS SCALES VERT. NONE HORIZ, NONE DATE CHECKED BY



#### EXISTING TYPICAL SECTION

KIRCHOFF RD. TO EUCLID AVE. STATION 80+57 TO 95+07


\*BARRIER MEDIAN FROM STA. 80+57 TO 83+07 TO REMAIN (SEE ROADWAY PLAN)



#### PROPOSED TYPICAL SECTION

KIRCHOFF RD. TO EUCLID AVE. STATION 80+57 TO 95+07


#### ¢ HICKS ROAD



#### EXISTING TYPICAL SECTION

EUCLID AVE. TO US 14 STATION 95+07 TO 164+40

#### ¢ HICKS ROAD




#### PROPOSED TYPICAL SECTION

EUCLID AVE. TO US 14 STATION 95+07 TO 164+40

\*\*\*\* BARRIER MEDIAN FROM STA. 160+71 TO 163+55 TO REMAIN (SEE ROADWAY PLAN)

anni ecta/uti24i99/sh inten.du1 4/24/2007 2:00:37 PN (ben-tron)



CONTRACT #60620

F.A.U. RTE.	SECTION	COUNTY		COUNTY		COUNTY		TOTAL SHEETS	SHEET NO.
*	531 RS-1	COOK		34	5				
STA. TO STA.									
FED. ROAD DIST. NO. 1 THENOIS HIGHWAY PROJECT									

\* FAU 2592 & FAP 305

#### LEGEND

- 1) EXISTING P.C.C. PAVEMENT, 8" (±)
- 2) EXISTING P.C.C. PAVEMENT, 9 1/2" (±)
- (3) EXISTING CONCRETE PAVEMENT, 7 1/2" (±)
- 4) EXISTING HMA PAVEMENT, 10" (±)
- 5 EXISTING BARRIER MEDIAN
- (6) EXISTING HMA SHOULDER
- 7 EXISTING HMA OVERLAY, 4" (±)
- 8 EXISTING HMA BASE COURSE WIDENING, 8" (±)
- (9) EXISTING COMBINATION CONCRETE CURB & GUTTER TYPE B-6.24 (MOD.)
- (10) EXISTING COMBINATION CONCRETE CURB & GUTTER TYPE M-2.12
- (11) EXISTING STABILIZED MEDIAN, 12"
- (12) EXISTING AGGREGATE SUBBASE, TYPE B
- (13) EXISTING STABILIZED SUBBASE
- (14) PROPOSED HMA SURFACE REMOVAL, 2 1/2"
- (15) PROPOSED POLYMERIZED HMA SURFACE COURSE, MIX "F", N90, 1 3/4"
- (16) PROPOSED POLYMERIZED LEVELING BINDER (MM), IL-4.75, N50, 3/4"

REVISIONS
NAME
DATE


HICKS ROAD

EXISTING AND PROPOSED
TYPICAL SECTIONS

SCALE: VERT. NONE
HORIZ. NONE
DATE

CHECKED BY

Complete of 24999 on Index dgn 4/24/2007 3.02 20 PM (ben-trans)t




CONTRACT #60620


CONTRACT #60620

COUNTY TOTAL SHEETS NO.

COOK 34 7 F.A.U. SECTION \* 531 RS-1 STA. 100+00 TO STA. 130+00 FED. ROAD DIST. NO. 1 ILLINOIS HIGHWAY PROJECT \* FAU 2592 & FAP 305 LINCOLN AVE. ---LETTERS AND SYMBOLS (TYP.) HMA SURFACE REMOVAL 2 1/2"  $\rightarrow \oplus \rightarrow Z$ POLY. LEVEL BINDER (MM), IL-4.75, N50, 3/4" 29.0′ 24" WHITE STOP BAR (TYP) POLY. HMA SURFACE COURSE, MIX "F", N90, 1 3/4" ---12" YELLOW DIAGONALS (TYP.) & 45° 115+00 100+00 HICKS ROAD STA. 105+00 . MATCH -4" YELLOW SKIP DASH LANE LINE (10' DASH - 30' SKIP) (TYP.) -4" WHITE SKIP DASH LANE LINE (10' DASH - 30' SKIP) (TYP.) -4" DOUBLE YELLOW (TYP.) --- 6" WHITE LANE LINE (TYP.) " YELLOW LINES (TYP.) (TYP.)
(SEE NOTE 1) WILMETTE AVE. HICKS ROAD ILLINOIS AVE. -4" DOUBLE YELLOW (TYP.) -4" WHITE SKIP DASH LANE LINE (10' DASH - 30' SKIP) (TYP.) - RAISED REFLECTIVE PAVT MKR SEE TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKER DETAIL **Z**→**Û**→ Z STA. STA. 12' 120+00 MATCH LINE MATCH HMA SURFACE REMOVAL 2 1/2"
POLY. LEVEL BINDER (MM), IL-4,75, N50, 3/4" 6" WHITE CROSSWALK LINES (TYP.) 38.0' LETTERS AND SYMBOLS (TYP.)-POLY. HMA SURFACE COURSE, MIX "F", N90, 1 3/4" 24" WHITE STOP BAR (TYP.) WINNETKA AVE. 66.0' ∠6" WHITE LANE LINE (TYP.) ILLINOIS DEPARTMENT OF TRANSPORTATION INDUSTRIAL AVE. HICKS ROAD PROPOSED ROADWAY AND PAVEMENT MARKING PLAN SCALE: VERT. NONE HORIZ.1" = 50' DRAWN BY CHECKED BY


\projects\dd24598\shirdwy.dgn 4/24/2007 2 57:03 PM Ukerstranit







CONTRACT #60620 COUNTY TOTAL SHEET SHEETS NO. F.A.U. SECTION \* 531 RS-1 COOK COOK 10 STA. 30+00 TO STA. 55+00 FED. ROAD DIST. NO. 1 ILLINOIS | HIGHWAY PROJECT \* FAU 2592 & FAP 305 U.S. RTE. 14 (NORTHWEST HWY. - HICKS RD.) WOOD STREET **D**-Û→Z 30+00 COLFAX STREET 4" SOLID DOUBLE YELLOW (TYP.) - EXIST. SW 4" SOLID DOUBLE YELLOW CENTERLINE (TYP.) 4" SOLID DOUBLE YELLOW (TYP.) 4" SOLID DOUBLE YELLOW (TYP.) — B-6.12 C&G STA. INE. - . . MATCHHLI 4" SOLID DOUBLE YELLOW (TYP.) LETTERS & SYMBOLS (TYP.) -4" WHITE SKIP-DASH 4" WHITE SKIP-DASH LANE LINE (TYP.) OMISSION ENDS 6" WHITE LANE LINE (TYP.) ---LANE LINE (TYP.) LINCOLN STREET STATION 31+44 WILSON STREET 24" WHITE STOP BAR (TYP.)-HMA SURFACE REMOVAL 2 1/2"
POLY. LEVEL BINDER (MM), IL-4.75, N50, 3/4"
POLY. HMA SURFACE COURSE, MIX "F", N90, 1 3/4" ROBERTSON AVENUE  $\Rightarrow \ominus > Z$ U.S. RTE. 14 (NORTHWEST HWY.!- HICKS RD.) LETTERS & SYMBOLS (TYP.) - 4" SOLID DOUBLE YELLOW (TYP.) MATCHHLINE ILLINOIS DEPARTMENT OF TRANSPORTATION 4" WHITE SKIP-DASH LANE LINE (TYP.) U.S. RTE. 14 PROPOSED ROADWAY AND HMA SURFACE REMOVAL 2 1/2"
POLY. LEVEL BINDER (MM), IL-4.75, N50, 3/4"
POLY. HMA SURFACE COURSE, MIX "F", N90, 1 3/4" PAVEMENT MARKING PLAN ROBERTSON STREET SCALE: VERT. 1"= 50" DATE 4/24/2007 DRAWN BY CHECKED BY


: \projects\d124996\sh risw.gen 4/24/2007 2:56:27 9M Exaretranit





CONTRACT #60620 COUNTY TOTAL SHEET SHEETS NO. SECTION \* 531 RS-1 COOK STA. 500+00 TO STA. 510+80 FED. ROAD DIST. NO. 1 ILLINOIS HIGHWAY PROJECT \* FAU 2592 & FAP 305 8" WHITE EDGE LINE (TYP.) IMPROVEMENT ENDS STATION 510+80 6" WHITE LANE LINE (TYP.) HICKS RD FIRST BANK DRIVE 50<sub>1</sub>0′ 6" WHITE CROSSWALK LINES (TYP.) CONC. PAV'T. PALATINE MALL ENT. 6" WHITE CROSSWALK LINES (TYP.) ---4" WHITE SKIP DASH LANE LINE (10' DASH - 30' SKIP) (TYP.) - 24" WHITE STOP BAR (TYP.) HMA SURFACE REMOVAL 2 1/2"
POLY. LEVEL BINDER (MM), IL-4.75, N50, 3/4"
POLY. HMA SURFACE COURSE, MIX "F", N90, 1 3/4" ILLINOIS DEPARTMENT OF TRANSPORTATION HICKS RD. & US 14 PROPOSED ROADWAY AND PAVEMENT MARKING PLAN SCALE: VERT. NONE HORIZ.1" = 50" DRAWN BY.... CHECKED BY





























## 12 (300) MIN. 9 8 -6 · · : • 6 PROPOSED PROPOSED SAND FILL BRICK, MORTAR, OR CONC. ADJUSTING RINGS

#### NOTES:

EXISTING BROKEN FRAMES AND LIDS SHALL BE REMOVED AND DISPOSED OF BY THE CONTRACTOR AND SHALL BE REPLACED AS DIRECTED BY THE ENGINEER. REPLACEMENT FRAMES AND LIDS WILL BE PAID FOR IN ACCORDANCE WITH ARTICLE 109.40 OF THE STANDARD SPECIFICATIONS UNLESS A SEPARATE PAY ITEM HAS BEEN PROVIDED.

SAND FILL

IF THE EXISTING LIDS ARE OPEN, THE FRAME WILL BE ADJUSTED TO THE ELEVATION OF THE MILLED PAVEMENT SURFACE PRIOR TO THE MILLING OPERATION. THE FRAME WILL NOT BE REMOVED AND COVERED BY THE METAL PLATE.

CITY OF CHICAGO CASTINGS ARE THE PROPERTY OF THE CITY AND THE CONTRACTOR SHALL NOTIFY THE CITY FOR REMOVAL AND DISPOSITION OF THE CASTINGS.

THE METAL PLATE USED TO COVER THE STRUCTURE SHALL REMAIN THE PROPERTY OF THE CONTRACTOR.

WHEN STRUCTURES ARE TO BE ADJUSTED OR RECONSTRUCTED, THE LOWERING AND RAISING OF THE FRAMES AND LIDS WILL NOT BE PAID FOR SEPARATELY, BUT WILL BE INCLUDED IN THE COST OF THE CORRESPONDING PAY ITEM.

#### CONSTRUCTION PROCEDURES

#### STAGE 1 (BEFORE PAVEMENT MILLING)

- A) REMOVE A MINIMUM OF 12 (300) OF THE PAVEMENT FROM AROUND THE STRUCTURE.
- B) REMOVE THE EXISTING FRAME AND LID FROM THE STRUCTURE.
- C) COVER THE STRUCTURE OPENING WITH A 36 (900) DIAMETER METAL PLATE.
- D) BACKFILL WITH CRUSHED STONE AND A MINIMUM  $1\frac{1}{2}$  (40) THICK HMA SURFACE MIX APPROVED BY THE ENGINEER.

#### STAGE 2 (AFTER PAVEMENT MILLING)

- A) REMOVE THE HMA SURFACE MIX AND CRUSHED STONE.
- B) INSTALL THE FRAME AND LID; ADJUST THE FRAME TO ITS FINAL SURFACE ELEVATION.
- C) THE SURROUNDING SPACE SHALL BE FILLED WITH CLASS SI CONCRETE, OR HMA SURFACE COURSE OR HMA BINDER COURSE TO THE LEVATION OF THE SURFACE OF THE EXISTING BASE COURSE OR THE BINDER COURSE,

THE PROCEDURE EXPLAINED ABOVE SHALL CONFORM TO THE APPLICABLE PORTIONS OF SECTIONS 353, 406, 602, AND 603 OF THE STANDARD SPECIFICATIONS.

#### LEGEND

- SUB-BASE GRANULAR MATERIAL
- 2 EXISTING PAVEMENT
- 3 36 (900) DIAMETER METAL PLATE
- PROPOSED CRUSHED STONE AND HMA SURFACE MIX
- 5 EXISTING STRUCTURE
- 6 FRAME AND LID (SEE NOTES)
- CLASS SI CONCRETE, HMA SURFACE COURSE OR HMA BINDER COURSE
- 8 PROPOSED HMA SURFACE COURSE
- 9 PROPOSED HMA BINDER COURSE

#### LOCATION OF STRUCTURES:

R. SHAH

ABBAS

R. WIEDEMAN R. BORO

THE CONTRACTOR WILL BE REQUIRED TO KEEP A RECORD OF THE LOCATIONS OF THE BURIED STRUCTURES ACCORDING TO THE STATION AND DISTANCE LEFT OR RIGHT OF THE CENTERLINE OF PAVEMENT. UPON COMPLETION OF THE WORK, THE CONTRACTOR WILL DELIVER THE RECORD TO THE ENGINEER.

BASIS OF PAYMENT: THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER EACH FOR "FRAMES AND LIDS TO BE ADJUSTED, SPECIAL"

01/01/0

NEW FRAMES AND LIDS, WHEN SPECIFIED, WILL BE PAID FOR SEPARATELY.

DETAILS FOR FRAMES AND LIDS ADJUSTMENT

WITH MILLING

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN

ILLINOIS DEPARTMENT OF TRANSPORTATION DETAILS FOR

FRAMES AND LIDS ADJUSTMENT WITH MILLING

SCALE: VERT. NONE


DRAWN BY CHECKED BY

BD600-03 (BD-8)

DATE = 4/23/2007
NAME = 5:\NP\PLANPREP\,
SCALE = 50.0000 '/ IN,
NAME = obreuch

PLOT FILE 1 PLOT USER

F.A.U. RTE. 2592 STA. COUNTY TOTAL SHEET NO. SECTION 531 RS-1 TO STA. FED. ROAD DIST. NO. 1 | ILLINOIS | HIGHWAY PROJECT



#### NOTES:

- 1. THE WIDTH OF THE FULL DEPTH PATCH OVER A TRENCH SHALL BE 12 (300) WIDER ON EACH SIDE OF THE TRENCH.
- 2. FOR METHOD OF MEASUREMENT AND BASIS OF PAYMENT, SEE RECURRING SPECIAL PROVISION "PATCHING WITH HOT-MIX ASPHALT OVERLAY REMOVAL".

#### SEQUENCE OF CONSTRUCTION

- 1. REMOVE THE EXISTING HMA MATERIAL OVER THE AREA TO BE PATCHED.
- 2. REMOVE AND REPLACE FULL DEPTH PATCHES
- 3. REPLACE HMA MATERIAL OVER THE AREA TO BE PATCHED.

A. HOUSEH A. ABBAS

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.


ILLINOIS DEPARTMENT OF TRANSPORTATION

PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT

SCALE: VERT. NONE

DRAWN BY CHECKED BY

BD400-04 (BD-22)



BE DONE IN ACCORDANCE WITH THE APPLICABLE PORTIONS OF SECTION 440 AND 606

7) THE LOCATIONS OF REMOVAL AND REPLACEMENT OF EXISTING CURB OR CURB AND GUTTER SHALL BE DETERMINED BY THE RESIDENT ENGINEER AT THE TIME OF CONSTRUCTION.

OF THE STANDARD SPECIFICATIONS.

CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT

FOOT (METER) FOR "CURB REMOVAL AND REPLACEMENT" OR

"COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT".

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS)

REVISIO	ONS
NAME	DATE
A. HOUSEH	03/11/94
R. SHAH	02/24/95
R. SHAH	03/02/95
R. SHAH	08/19/96
R. SHAH	09/12/96
R. SHAH	09/19/96
R. SHAH	10/03/96
A. ABBAS	03/21/97
M. GOMEZ	01/22/01
R. BORO	01/01/07

ILLINOIS DEPARTMENT OF TRANSPORTATION


CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT

SCALE: VERT. NONE

DRAWN BY BD600-06 (BD-24)


MILLED TEMPORARY RAMP (FOR BUTT JOINT AND HMA TAPER SEE DETAIL BELOW)

#### OPTION 1



OPTION 2


#### TYPICAL TEMPORARY RAMP




TYPICAL BUTT JOINT AND HMA TAPER

CONTRACT NO. 60620

COUNTY TOTAL SHEET NO. SECTION 2592 COOK 34 26 531 RS-1 TO STA. FED. ROAD DIST. NO. 1 ILLINOIS HIGHWAY PROJECT





### TYPICAL BUTT JOINT AND HMA TAPER FOR RESURFACING ONLY

\* \* PC CONCRETE, HMA OR HMA RESURFACED PAVEMENT.

#### NOTES

- A: MAINLINE ROADWAYS AND MAJOR SIDE ROADS.
- B: MINOR SIDE ROADS.

THE BUTT JOINT WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER SQUARE YARD (SQUARE METER) FOR "HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT" OR FOR "PORTLAND CEMENT CONCRETE SURFACE REMOVAL- BUTT JOINT".

BASIS OF PAYMENT:

- C: THE TEMP. RAMP SHALL BE CONSTRUCTED IMMEDIATELY UPON REMOVAL OF THE EXISTING HMA SURFACE.
- D: THE BUTT JOINT SHALL BE CONSTRUCTED IMMEDIATELY PRIOR TO PLACING THE PROPOSED HMA COURSES.
- E: TAPER THE TEMP. RAMP AT A RATE OF 3'-0" (900 mm) PER 1 INCH (25 mm) OF MILLING THICKNESS.
- F: INSTALLATION AND REMOVAL OF THE 4'-6" (1.35 m) TEMP. RAMP IS INCLUDED IN COST OF HMA SURFACE REMOVAL - BUTT JOINT
- G: SEE ARTICLE 406.08 AND 406.14 OF THE STANDARD SPECIFICATIONS FOR "HMA AND/OR PCC SURFACE REMOVAL, BUTT JOINT".
- \* SEE TYPICAL SECTIONS FOR MILLING THICKNESS.
- \* \*\* \* 20'-0" (6.1 m) PER 1 (25) RESURFACING (NOTE "A") 10'-0" (3.0 m) PER 1 (25) RESURFACING (NOTE "B")

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

REVISIONS M. DE YONG R. SHAH A. ABBAS M. GOMEZ R. BORO 04/06/0

ILLINOIS DEPARTMENT OF TRANSPORTATION

BUTT JOINT AND HMA TAPER DETAILS


SCALE: VERT. NONE.

DRAWN BY CHECKED BY

BD400-05 (VI=BD32)

FOR MILLING AND RESURFACING

SECTION



ROAD TYPE III BARRICADES WITH TWO FLASHING AMBER LIGHTS ON EACH. AHEAD TYPE I OR TYPE II BARRICADES WITH ONE FLASHING AMBER LIGHT ON EACH, OR TYPE III BARRICADES WITH TWO FLASHING 15 (380) 200'± (60 m±)-AMBER LIGHTS ON EACH. 21 (530) DRIVEWAY 200'± (60 m±) 09) STREET; COLLECTOR LIMIT> 40 MPH ( ROAD CONSTRUCTION W20-1(0) M6-4(0)-2115 M6-1(0)-2115 **4=>** 

TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS

#### NOTES:

- A. FOR NO LANE RESTRICTION ON THE SIDE ROAD OR DRIVEWAYS
- 1. SIDE ROAD WITH A SPEED LIMIT OF 40 MPH (60 km/h) OR LESS AS SHOWN ON THE DRAWING AND AS DIRECTED BY THE ENGINEER:
- d) ONE ROAD CONSTRUCTION AHEAD SIGN 36 x 36 (900x900) WITH A FLASHER AND FLAG MOUNTED ON IT APPROXIMATELY 200' (60 m) IN ADVANCE OF THE MAIN ROUTE.
- b) THE CLOSED PORTION OF THE MAIN ROUTE SHALL BE PROTECTED BY BLOCKING WITH TYPE I, TYPE II OR TYPE III BARRICADES, 1/3 OF THE CROSS SECTION OF THE CLOSED PORTION.
- 2. SIDE ROAD WITH A SPEED LIMIT GREATER THAN 40 MPH (60 km/h) AS SHOWN ON THE DRAWING AND AS DIRECTED BY THE ENGINEER:
- a) ONE ROAD CONSTRUCTION AHEAD SIGN 48 x 48 (1.2 m x 1.2 m) WITH A FLASHER MOUNTED ON IT APPROXIMATELY 500' (150 m) IN ADVANCE OF THE MAIN ROUTE.
- b) THE CLOSED PORTION OF THE MAIN ROUTE SHALL BE PROTECTED BY BLOCKING WITH TYPE III BARRICADES, 1/2 OF THE CROSS SECTION OF THE CLOSED PORTION.
- 3. WHEN THE SIDE ROAD LIES BETWEEN THE BEGINNING OF THE MAINLINE SIGNING AND THE WORK ZONE, A SINGLE HEADED ARROW (M6-1) SHALL BE USED IN LIEU OF THE DOUBLE HEADED ARROW (M6-4).

- B. FOR A LANE CLOSURE ON A SIDE ROAD OR DRIVEWAY:
- USE APPLICABLE PORTIONS OF THE TYPICAL APPLICATION OF TRAFFIC CONTROL DEVICES (STD. 701501, STD. 701606 OR THE APPROPRIATE STANDARD). THE SPACING OF SIGNS AND BARRICADES SHALL BE ADJUSTED FOR FIELD CONDITIONS AS DIRECTED BY THE ENGINEER. THE DIRECTIONAL ARROW SHALL BE COVERED OR REMOVED WHEN NO LONGER CONSISTENT WITH THE SIDE ROAD LANE CLOSURE.
- C. ADVANCE WARNING SIGNS ARE TO BE OMITTED ON DRIVEWAY UNLESS
- D. THE TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS SHALL BE INCIDENTAL TO THE COST OF SPECIFIED TRAFFIC CONTROL STANDARDS OR ITEMS.

All dimensions are in millimeters (inches) unless otherwise shown.

REVISION	VS	THE TRICTS DEPARTME	ENT OF TRANSPORTATION
NAME	DATE	ILLINOIS DELAKTIME	INT OF TRANSFORTATION
LHA	6/89	TRAFFIC CONTRA	OL AND PROTECTION
T. RAMMACHER	09/08/94		
J. OBERLE	10/18/95		FOR
A. HOUSEH	03/06/96	CIDE DOADS IN	NTERSECTIONS, AND
A. HOUSEH	10/15/96		
T. RAMMACHER	01/06/00	DRI	VEWAYS
		SCALE: NONE	DRAWN BY
			CHECKED BY
			TC-10


CONTRACT NO. 60620


F.A.U RTE	SEC	TION	COUNTY	TOTAL SHEETS	SHEET NO.
2592	531	RS-1	СООК	34	28
STA.		TO STA.			
FED. R	OAD DIST. NO. 1	ILLINOIS	HIGHWAY	PROJECT	

80' (24 m) O.C. **⟨**== ⇔


\*\*\* REDUCE TO 40' (12 m) O.C. ON CURVES WITH POSTED OR ADVISORY SPEED 45 M.P.H. (70 km/h) OR LESS.

TWO-LANE/TWO-WAY






TWO-WAY LEFT TURN



MULTI-LANE/UNDIVIDED



MULTI-LANE/DIVIDED

#### GENERAL NOTES

- MARKERS USED WITH DASHED LINES SHALL BE CENTERED IN THE GAP BETWEEN SEGMENTS.
- 2. MARKERS USED ADJACENT TO SOLID LINES SHALL BE OFFSET 2 TO 3 (50 TO 75) TOWARD TRAFFIC AS SHOWN.
- 3. MARKERS THROUGH TANGENTS LESS THAN 500' (150 m) IN LENGTH BETWEEN CURVES SHALL BE INSTALLED AT THE LESSER OF THE TWO CURVE SPACINGS.

#### LANE MARKER NOTES

B. REDUCE TO 40' (12 m) O.C. ON CURVES WHERE ADVISORY SPEEDS ARE 10 M.P.H (20 km/h) LOWER THAN POSTED SPEEDS.

A. USE DOUBLE LANE LINE MARKERS SPACED AS SHOWN.

#### SYMBOLS

YELLOW STRIPE

WHITE STRIPE

- ONE-WAY AMBER MARKER
- ONE-WAY CRYSTAL MARKER (W/O)
- → TWO-WAY AMBER MARKER

#### DESIGN NOTES

- 1. DOUBLE LANE LINE MARKERS SHALL BE USED UNLESS SPECIFIED OTHERWISE.
- 2. EXCEPT AS SHOWN ON THE LANE REDUCTION TRANSITION AND FREEWAY EXIT RAMP DETAIL, MARKERS ARE NOT TO BE SPECIFIED ON RIGHT EDGE
- 3. THE EXACT MARKER LIMITS, SPACING, AND COLOR SHOULD BE INCLUDED IN THE PLANS.
- 4. MARKERS SHOULD NOT BE USED ALONGSIDE CURBS EXCEPT FOR EXTREMELY SHORT SECTIONS OF CURBS WHERE NOT MORE THAN TWO MARKERS WOULD BE

All dimensions are in inches (millimeters) unless otherwise shown.


REVISIO NAME	DATE
T. RAMMACHER	09-19-94
T. RAMMACHER	03-12-99
T. RAMMACHER	01-06-00

ILLINOIS DEPARTMENT OF TRANSPORTATION


TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)


SCALE: NONE


DRAWN BY CADD CHECKED BY



LEFT TURN








6'-4" (2 m) 8' 8' 8' 8' 8' (2.4 m)

MEDIAN WITH TWO-WAY LEFT TURN LANE

### TYPICAL PAINTED MEDIAN MARKING




FULL SIZE LETTERS 8' (2.4 m) AND ARROWS SHALL BE USED.  $\P_1$  AREA = 15.6 SQ. FT. (1.5 m² ) (III) AREA = 20.8 SQ. FT. (1.9 m²)

\* TURN LANES IN EXCESS OF 400' (120 m) IN LENGTH MAY HAVE AN ADDITIONAL SET OF ARROW - "ONLY" INSTALLED MIDWAY BETWEEN THE OTHER TWO SETS OF ARROW - "ONLY".

TYPICAL LEFT (OR RIGHT) TURN LANE

#### TYPICAL TURN LANE MARKING



#### TYPICAL ISLAND MARKING

TYPE OF MARKING	WIDTH OF LINE	PATTERN	COLOR	SPACING / REMARKS
CENTERLINE ON 2 LANE PAVEMENT	4 (100)	SKIP-DASH	YELLOW	10' (3 m) LINE WITH 30' (9 m) SPACE
CENTERLINE ON MULTI-LANE UNDIVEDED PAVEMENT	2 & 4 (100)	SOLID	YELLOW	11 (280) C-C
NO PASSING ZONE LINES: FOR ONE DIRECTION FOR BOTH DIRECTIONS	4 (100) 2 <b>0</b> 4 (100)	SOLID SOLID	YELLOW YELLOW	5½ (140) C-C FROM SKIP-DASH CENTERLINE 11 (280) C-C OMIT SKIP-DASH CENTERLINE BETWEEN
LANE LINES	4 (100) 5 (125) ON FREEWAYS	SKIP-DASH SKIP-DASH	WHITE WHITE	10' (3 m) LINE WITH 30' (9 m) SPACE
DOTTED LINES (EXTENSIONS OF CENTER, LANE OR TURN LANE MARKINGS)	SAME AS LINE BEING EXTENDED	SKIP-DASH	SAME AS LINE BEING EXTENDED	2' (600) LINE WITH 6' (1.8 m) SPACE
EDGE LINES	4 (100)	SOLID	YELLOW-LEFT WHITE-RIGHT	OUTLINE MOUNTABLE MEDIANS IN YELLOW; EDGE LINES ARE NOT USED NEXT TO BARRIER CURB
TURN LANE MARKINGS	6 (150) LINE; FULL SIZE LETTERS & SYMBOLS (8' (2.4m))	SOLID	WHITE	SEE TYPICAL TURN LANE MARKING DETAIL
TWO WAY LEFT TURN MARKING	2 @ 4 (100) EACH DIRECTION	SKIP-DASH AND SOLID	YELLOW	10' (3 m) LINE WITH 30' (9 m) SPACE FOR SKIP-DASH; 5½ (140) C-C BETWEEN SOLID LINE AND SKIP-DASH LINE
	8' (2.4m) LEFT ARROW	IN PAIRS	WHITE	SEE TYPICAL TWO-WAY LEFT TURN MARKING DETAIL
CROSSWALK LINES (PEDESTRIAN) A. DIAGONALS (BIKE & EQUESTRIAN) B. LONGITUDINAL BARS (SCHOOL)	2 @ 6 (150) 12 (300) @ 45° 12 (300) @ 90°	SOLID SOLID SOLID	WHITE WHITE WHITE	NOT LESS THAN 6' (1.8 m) APART 2' (500) APART 2' (500) APART SEE TYPICAL CROSSWALK MARKING DETAILS.
STOP LINES	24 (600)	SOLID	WHITE	PLACE 4' (1.2 m) IN ADVANCE OF AND PARALLEL TO CROSSWALK, IF PRESENT. OTHERNISE, PLACE AT DESIRED STOPPING POINT. PARALLEL TO CROSSROAD CENTERLINE, WHERE POSSIBLE
PAINTED MEDIANS	2 & 4 (100) WITH 12 (300) DIAGONALS	SOLID	YELLOW: TWO WAY TRAFFIC	11 (280) C-C FOR THE DOUBLE LINE
	& 45°  NO DIAGONALS USED FOR 4' (1.2 m) WIDE MEDIANS		WHITE: ONE WAY TRAFFIC	SEE TYPICAL PAINTED MEDIAN MARKING.
GORE MARKING AND CHANNELIZING LINES	8 (200) WITH 12 (300) DIAGONALS @ 45°	SOLID	WHITE	DIAGONALS: 15' (4.5 m) C-C (LESS THAN 30MPH (50 km/h)) 20' (6 m) C-C 30MPH (50 km/h) TO 45MPH (70 km/h) 30' (9 m) C-C (OVER 45MPH (70 km/h))
RAILROAD CROSSING	24 (600) TRANSVERSE LINES; "RR" IS 6' (1.8 m) LETTERS; 16 (400) LINE FOR "X"	SOLID	WHITE	SEE STATE STANDARD 780001 AREA OF: "M"-3.6 SO. FT. (0.33 m <sup>2</sup> ) EACH "X"-54.0 SQ. FT. (5.0 m <sup>2</sup> )
SHOULDER DIAGONALS	12 (300) <b>c</b> 45°	SOLID	WHITE - RIGHT	50' (15 m) C-C (LESS THAN 30MPH (50 km/h)) 75' (25 m) C-C (30 MPH (50 km/h) TO 45MPH (70 km/h) 150' (45 m) C-C (0VER 45MPH (70 km/h))

FOR FURTHER DETAILS ON PAVEMENT MARKING REFER TO STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION AND STATE STANDARD 780001.

All dimensions are in inches (millimeters) unless otherwise shown.

REVISIONS
NAME DATE
EVERS 03-19-90
T. RAMMACHER 10-27-94
ALEX HOUSEH 10-09-96
ALEX HOUSEH 10-17-96
T. RAMMACHER 01-06-00

ILLINOIS DEPARTMENT OF TRANSPORTATION


DISTRICT ONE TYPICAL PAVEMENT MARKINGS

SCALE: NONE

DRAWN BY CADD CHECKED BY

TC-13

ATE = 4/23/2007 HME = S.V.WPY-PLANPREP\SQUAD\_I\Des\_DW\cadd standards\to13.dgn >> T = ### mma \* Thi





CHECKED BY LHA

TC-14


F.A.U. SEC 2592 531 RS-1 STA. TO STA.

FED. ROAD DIST. NO. 1 | ILLINOIS HIGHWAY PROJECT





QUANTITY 4 (100) LINE = 45.5 ft. (13.9 m) 15.2 sq. ft. (1.39 sq. m)



QUANTITY 4 (100) LINE = 82.5 ft. (25.3 m) 27.5 sq. ft. (2.53 sq. m)

All dimensions are in inches (millimeters) unless otherwise shown.


NAME	DATE
T. RAMMACHER	09/18/94
J. OBERLE	06/01/96
T. RAMMACHER	06/05/96
T. RAMMACHER	11/04/97
T. RAMMACHER	03/02/98
E. GOMEZ	08/28/00

ILLINOIS DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING LETTERS AND SYMBOLS FOR TRAFFIC STAGING

SCALE: NONE

DRAWN BY CADD CHECKED BY




DATE = 4/23/2807 NAME = SLYMP/RIANMER/SQUAD\_I\Des\_DW\cadd standards SCALE = 50.080 / IN.

 F.A.U. RTE.	SECTION	۱ C	ראטס	ſ	TOTAL SHEETS	SHEE
2592	531 RS	-1	COOL	<	34	33
STA.		TO	STA.			
FFO. ROAL	DIST. NO.	ILI INOIS	FED.	AID	PROJECT	

WITH INTERSECTION TRAFFIC SIGNALS


WITH NEAR-SIDE TRAFFIC SIGNALS



- PAVEMENT MARKINGS TO BE INSTALLED ONLY ON APPROACHES TO INTERSECTIONS CONTROLLED BY TRAFFIC SIGNALS
  WHICH ARE INTERCONNECTED WITH THE RAILROAD WARNING SIGNALS.
- 2. WHERE NEAR-SIDE TRAFFIC SIGNALS ARE USED, THE PAVEMENT MARKINGS EXTENDS TO THE INTERSECTION.
- 3. WHERE THE ANGLE BETWEEN THE DIAGONAL STRIPES AND THE TRACK (Ø) WOULD BE LESS THAN APPROXIMATELY 20°, THE STRIPES SHOULD BE SLOPED IN THE OPPOSITE DIRECTION FROM THAT SHOWN.

#### WITH NONSIGNALIZED INTERSECTION

81' (25 m) OR LESS TO CLOSEST RAIL




- 1. DISTANCE TO BE SHOWN ON SIGN MEASURED FROM A POINT 6 FEET (1.8 m) FROM THE RAIL CLOSEST TO THE INTERSECTION TO THE STOP LINE OR CROSSWALK, WHICKEVER IS CLOSEST, ROUNDED DOWN TO THE MEAREST 5 FEET (1.5 m). WHERE THERE IS NO STOP LINE, MEASURE TO POINT WHERE THE DRIVER HAS A VIEW OF APPROACHING TRAFFIC.
- 2. THE CLEARANCE SIGN IS ALSO TO BE USED AS AN INTERIM MEASURE AT LOCATIONS WITH INTERCONNECTED INTERSECTION TRAFFIC SIGNALS WHERE IT IS PLANNED TO CHANGE THEM TO NEAR-SIDE SIGNALS AT A FUTURE TIME. IN THIS CASE, THE DISTANCE TO BE SHOWN ON THE SIGN IS MEASURED FROM THE EDGE OF THE STRIPED-OUT AREA INSTEAD OF 6-FECT FROM THE RAIL. THE SIGN IS TO BE REMOVED WHEN THE NEAR-SIDE SIGNALS ARE INSTALLED AND THE PAVEMENT MARKINGS EXTEND TO THE INTERSECTION.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

TC23


REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	ILLINOIS DEPARTMENT OF TRANSFORTATION
	01/01/07	
		TYPICAL SUPPLEMENTAL
		SIGNING AND PAVEMENT MARKING
		310NING AND PAVEMENT MARKING
		ITREATMENT FOR RAILROAD CROSSING
		SCALE: NONE DRAWN BY
	1	OUEOVED DV
	1	L CHECKED BY



#### <u>LEFT TURN LANES WITH MEDIANS</u> VOLUME DENSITY ("FAR OUT" DETECTION) ON SAME APPROACH

(PROTECTED / PERMITTED LEFT TURN PHASING)


HANDHOLE LOCATION MAY VARY DEPENDING ON GEOMETRICS AND DESIGN OF TRAFFIC SIGNALS. HEAVY-DUTY HANDHOLES TO BE USED WHEN THE MEDIAN IS MOUNTABLE. REFER TO STANDARD BIADOI TO ENSURE THAT HANDHOLE FITS IN MEDIAN.



\*\* UNIT DUCT IS TO BE SHOWN ON PLAN SHEETS BUT SHALL NOT BE INCLUDED IN THE PAY ITEMS. PLAN SHEET FOR DETECTOR LOOP REPLACEMENT


LEFT TURN LANES WITHOUT MEDIANS VOLUME DENSITY ("FAR OUT" DETECTION) ON SAME APPROACH

(PROTECTED / PERMITTED LEFT TURN PHASING)




NOTE: DUAL LEFT TURNS NOT SHOWN REFER TO

ARTERIAL-VOLUME DENSITY ("FAR OUT" DETECTION) CROSS STREET-VOLUME DENSITY ("FAR OUT" DETECTION)



ARTERIAL-VOLUME DENSITY ("FAR OUT" DETECTION) CROSS STREET-NON VOLUME DENSITY ("UPTIGHT" PRESENCE DETECTION)



CONTRACT NO. 60620 COUNTY TOTAL SHEET NO. SECTION 2592 COOK 34 531 RS-1 34 STA. TO STA. FED. ROAD DIST. NO. 1 | ILLINOIS | HIGHWAY PROJECT

#### NOTES:

#### VEHICLES LOOP DETECTORS

- \* ALL LEAD IN CABLE SHALL BE TWO CONDUCTOR NO. 14 TWISTED. SHIELDED.
- \* EACH DETECTOR LOOP SHALL HAVE ITS OWN SAW CUT FROM THE LOOP TO THE EDGE OF PAVEMENT OR TO A HANDHOLE IN THE PAVEMENT.
- \* EACH DETECTOR LOOP SHALL HAVE ITS OWN ONE INCH (25 mm) UNIT DUCT BETWEEN THE EDGE OF PAVEMENT AND THE FIRST HANDHOLE OR JUNCTION BOX, EACH UNIT DUCT RUN SHALL BE SHOWN ON THE PLANS BY THE DESIGNER, BUT SHALL NOT BE PAID FOR SEPARATLY. THIS ITEM IS INCIDENTAL TO THE PAY ITEM FOR DETECTOR LOOPS.
- \* ONE DIMENSION OF ALL DETECTOR LOOPS SHALL BE SIX FEET
- \* EACH LANE OF NON-LOCKING, PRESENCE DETECTION AND EACH LANE OF A DOUBLE LEFT TURN LANE REQUIRES A SEPARATE INDUCTIVE LOOP DETECTOR AND LEAD IN CABLE.
- \* WHEN NON-LOCKING, PRESENCE DETECTION IS USED, MORE THAN ONE LOOP PER LANE IS REQUIRED BEHIND THE STOP BAR (i.e. 1-1/2, 1-3/4, 2).
- \* WHEN SYSTEM LOOPS ARE REQUIRED ON AN APPROACH OF AN INTERSECTION, THE LOOPS USED FOR VOLUME DENSITY AND INTERSECTION TIMING SHALL ALSO BE USED AS SYSTEM DETECTORS. EACH ONE OF THESE TYPE OF LOOPS REQUIRES A SEPARATE TWO CONDUCTOR NO. 14 TWISTED SHIELDED CABLE AND A SEPARATE INDUCTIVE LOOP DETECTOR WHEN NEW CONTROLLERS ARE UTILIZED. THE DESIGNER SHALL LABEL THESE TYPES OF LOOPS AS "INTERSECTION AND SAMPLING (SYSTEM) DETECTORS" ON THE SIGNAL LAYOUT, THE INTERCONNECT PLAN AND THE SYSTEM CABLE PLAN. WHEN AN EXISTING CONTROLLER IS UTILIZED FOR THIS TYPE OF DETECTION, THE PAY ITEM "INDUCTIVE LOOP DETECTOR WITH SYSTEM OUTPUT" SHOULD BE USED.

#### PLACEMENT OF DETECTORS

THE FOLLOWING FIGURES REPRESENT THE MOST COMMON DETECTOR LOOP LOCATIONS AND SIZES. ADJUSTMENTS WILL BE NECESSARY FOR SPECIFIC GEOMETRIC CONSIDERATIONS.

LOCATIONS AND DEMENSIONS OF DETECTOR LOOPS ARE REQUIRED ON ALL SIGNAL LAYOUT PLAN SHEETS.

"FAR OUT" DETECTION REFERS TO LOCKING, PRESENCE TYPE DETECTION LOCATED IN THRU LANES, RIGHT TURN LANES, AND RIGHT TURN LANE TAPER AREAS (IF APPLICABLE), USUALLY 250' (75 m) IN ADVANCE OF STOP BARS. "UPTIGHT" DETECTION REFERS TO NON-LOCKING PRESENCE TYPE DETECTION LOCATED IN ALL LANES AND 10'-15' (3.0 m-4.5 m) BEHIND THE CROSSING STREET'S EDGE OF PAVEMENT EXTENDED.

ALL DETAILS AND NOTES SHOWN ARE FROM THE I.D.O.T. DISTRICT 1 TRAFFIC SIGNAL DESIGN GUIDELINES DATED JANUARY 1995

THIS DRAWING HAS BEEN PREPARED TO ASSIST THE RESIDENT ENGINEER FOR ALL ROADWAY RESURFACING OR S.M.A.R.T. PROJECTS WHERE THE DIMENSIONS ARE NOT SHOWN ON THE PLANS AND THE FINAL LOCATIONS FOR CROSSWALKS OR STOP BARS ARE NOT DETERMINED.

ILLINOIS DEPAR	REVISIONS		
ILLINOIS DEPAR	DATE	NAME	
(			
DE <sup>-</sup>			
INSTAL			
FOR ROA			
SCALE: NONE			
SCALE: NUME			

RTMENT OF TRANSPORTATION DISTRICT 1 ETECTOR LOOP LLATION DETAILS ADWAY RESURFACING DESIGNED BY

> DRAWN BY CADD CHECKED BY R.K.F.

PLOT FILE PLOT USER