

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2688	3178 G-RS-2	COOK	24	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 1000				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	203	203				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	23	23				
40600300	AGGREGATE (PRIME COAT)	TON	113	113				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	17	17				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	201	201				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	432	432				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4873	4873				
42001300	PROTECTIVE COAT	SQ YD	15	15				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	56316	56316				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	50	50				
44002215	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 3/4"	SQ YD	366	366				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	75	75				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	47	47				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	244	244				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	812	812				
67000200	ENGINEER'S FIELD OFFICE, TYPE A	EACH	6	6				
67100100	MOBILIZATION	L SUM	1	1				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6471	6471				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	596	596				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	42905	42905				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN 1000				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1110	1110				
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	135	135				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	600	600				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	16624	16624				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	596	596				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	42905	42905				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1110	1110				
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	135	135				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	600	600				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	252	252				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	462	462				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	430	430				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	730	730				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2437	2437				
20018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	7	7				

* SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 US ROUTE 6
 FROM 159TH STREET TO COOK-WILL COUNTY LINE

3/16/2007 10:41:00 AM C:\Users\jgordon\Documents\60A84\60A84.dwg