

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	WEBER	LIGHTING
				Sta. 789+00 to Sta. 950+84.47	Sta. 905+49.48	Sta. 789+00 to Sta. 950+84.47
				I000-2A	SFTY-2A	Y031-1E
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	51,919	51,919		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	798	798		
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	13,019	13,019		
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,690	1,690		
78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	5,915	5,915		
78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	60,202	60,202		
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	15,540	15,540		
78005120	EPOXY PAVEMENT MARKING - LINE 5"	FOOT	1,943	1,943		
78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	341	341		
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,590	1,590		
78100300	REPLACEMENT REFLECTOR	EACH	624	624		
78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	5,400	5,400		
78200410	GUARDRAIL MARKERS, TYPE A	EACH	38	38		
78200530	BARRIER WALL MARKERS, TYPE C	EACH	449	449		
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2		
* 78300100	PAVEMENT MARKING REMOVAL	SQ FT	64,220	64,220		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,590	1,590		
81603210	UNIT DUCT, 600V, 3-1/C NO.4, 1/C NO.6 GROUND, (EPR-TYPE RHW), 1 1/4" DIA. POLYETHYLENE	FOOT	5,029			5,029
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	4,609			4,609
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	243			243
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	27			27
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	2			2
84200700	LIGHTING FOUNDATION REMOVAL	EACH	27			27
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	27			27
X0322054	REMOVAL OF PRECAST FLARED END SECTION	EACH	5	5		0
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	1,622	1,622		
X0322323	WEED CONTROL, TEASEL	GALLON	3	3		
X0322729	MATERIAL TRANSFER DEVICE	TON	20,583	20,583		
X0323574	MAINTENANCE OF LIGHTING SYSTEM	CALMO	18			18
X0323973	SEDIMENT CONTROL, SILT FENCE	FOOT	1,800	1,800		
X0323974	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	FOOT	429	429		
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	8	8		
X0324114	DRAINAGE STRUCTURES, TYPE 8'X3' WITH TWO TYPE 20 FRAME AND GRATES	EACH	2	2		

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI ROUTE 55
143RD STREET TO WEBER ROAD

SUMMARY OF QUANTITIES

SCALE: NONE
DATE: 02-23-07

DRAWN BY AR
CHECKED BY SJV



Rev. 10-4-07

FINAL