



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 7, 2007

SUBJECT: FAP Route 846  
Section (4, 4R & 5) RS-7  
Will County  
Contract No. 62364  
Item No. 100, June 15, 2007 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 1 of the Schedule of Prices.
2. Revised page i of the Table of Contents to the Special Provision.
3. Revised page 10 of the Special Provisions.
4. Revised sheet 3 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric E. Harm  
Interim Bureau Chief  
Bureau of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger P.E.'.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Roger Driskell; R. E. Anderson;  
Estimates; Design & Environment File

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 62364

State Job # - C-91-002-02  
 PPS NBR - 1-74893-0000  
 County Name - WILL--  
 Code - 197- -  
 District - 1- -  
 Section Number - (4,4R,&5)RS-7

Project Number

Route  
FAP 846

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0301424	SILICONE JOINT SEALER	FOOT	172.000				
X0322256	TEMP INFO SIGNING	SQ FT	51.400				
X0325303	STR REP CON DP OVER 5	SQ FT	75.000				
X0325305	STR REP CON DP = < 5	SQ FT	40.000				
* DELETED							
X4067107	POL LB MM IL4.75 N50	TON	6,154.000				
Z0001800	APPROACH SL REP (PD)	SQ YD	2.000				
20201006	GRADING & SHAP SHLDS	UNIT	471.000				
* DELETED							
40600200	BIT MATLS PR CT	TON	63.000				
40600300	AGG PR CT	TON	313.000				
40600400	MIX CR JTS FLANGWYS	TON	47.000				
40600895	CONSTRUC TEST STRIP	EACH	1.000				
40600982	HMA SURF REM BUTT JT	SQ YD	635.000				
40600990	TEMPORARY RAMP	SQ YD	635.000				
							* REVISED : JUNE 8, 2007

## TABLE OF CONTENTS

LOCATION OF IMPROVEMENT .....	1
DESCRIPTION OF IMPROVEMENT.....	1
MAINTENANCE OF ROADWAYS.....	1
STATUS OF UTILITIES TO BE ADJUSTED .....	2
START OF WORK .....	2
WEEKEND WORK RESTRICTION .....	2
COMPLETION DATE PLUS WORKING DAYS.....	2
RESTRICTION ON WORKING DAYS AFTER A COMPLETION DATE .....	3
HOT MIX ASPHALT MIXTURE IL-4.75 (DISTRICT ONE) .....	3
ALKALI - SILICA REACTION FOR CAST-IN-PLACE CONCRETE (BMPR) .....	7
EPOXY COATING ON REINFORCEMENT (DISTRICT ONE) .....	9
DECK SLAB REPAIR.....	10
SILICONE BRIDGE JOINT SEALER.....	16
STRUCTURAL REPAIR OF CONCRETE .....	19
APPROACH SLAB REPAIR .....	27
FRAMES AND LIDS TO BE ADJUSTED (SPECIAL).....	32
TRAFFIC CONTROL PLAN.....	32
TEMPORARY INFORMATION SIGNING.....	33
TRAFFIC SIGNAL SPECIFICATIONS FOR DETECTOR REPLACEMENT AND/OR INSTALLATION ON ROADWAY GRINDING, RESURFACING, & PATCHING OPERATIONS .....	34
CEMENT (BDE) .....	37
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) .....	39
ENGINEER'S FIELD OFFICE TYPE A (BDE).....	47
ERRATA FOR THE 2007 STANDARD SPECIFICATIONS (BDE).....	48
HOT-MIX ASPHALT EQUIPMENT, SPREADING AND FINISHING MACHINE (BDE) .....	50
HOT-MIX ASPHALT - FIELD VOIDS IN THE MINERAL AGGREGATE (BDE).....	50
PAYMENTS TO SUBCONTRACTORS (BDE) .....	51
PORTLAND CEMENT CONCRETE PLANTS (BDE) .....	52
RECLAIMED ASPHALT PAVEMENT (RAP) (BDE) .....	54
REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE) .....	59
REINFORCEMENT BARS (BDE) .....	60
SELF-CONSOLIDATING CONCRETE FOR CAST-IN-PLACE CONSTRUCTION (BDE).....	62
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) .....	66
THERMOPLASTIC PAVEMENT MARKINGS (BDE) .....	66
WATER BLASTER WITH VACUUM RECOVERY (BDE).....	67
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID).....	68

Revised 06/07/2007

**DECK SLAB REPAIR**

Effective: May 15, 1995

Revised: February 2, 2007

This work shall consist of hot-mix asphalt surface removal, when required, the removal and disposal of all loose and deteriorated concrete from bridge deck and the replacement with new concrete to the original top of deck. The work shall be done according to the applicable requirements of Sections 501, 503 and 1020 of the Standard Specifications and this Special Provision.

Deck slab repairs will be classified as follows:

- (a) Partial-Depth. Partial-depth repairs shall consist of removing the loose and unsound deck concrete, disposing of the concrete removed and replacing with new concrete. The removal may be performed by chipping with power driven hand tools or by hydro-scarification equipment. The depth shall be measured from the top of the concrete deck surface, at least 3/4 in. (20 mm) but not more than 1/2 the concrete deck thickness.

Revised 06/07/2007