

| CONTRACT NO. 6270|
F.A.U.	SECTION	COUNTY	TOTAL	SHEET	NO.
5565	(B&U-1) RS-6	COOK	27	6	
STA.	TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID	PROJECT

LEGEND

- 1) EXISTING HOT-MIX ASHPALT SURFACE, 6" +/-
- (2) EXISTING P.C.C. PAVEMENT, 9" +/-
- (3) EXISTING AGGREGATE SHOULDER
- (4) EXISTING CONCRETE CURB AND GUTTER, TYPE B-6.24
- 5 EXISTING RAISED CONCRETE MEDIAN
- (6) PROPOSED HOT MIX ASPHALT SURFACE REMOVAL, 2 1/4"
- 7) PROPOSED HOT MIX ASPHALT CONCRETE SURFACE COURSE, MIX "D", N70, 1 1/2"
- PROPOSED POLYMERIZED LEVELING BINDER, (MACHINE METHOD), IL 4.75, N50, 3/4"
- 9 PROPOSED AGGREGATE WEDGE SHOULDERS, TYPE B
- (10) PROPOSED HOT MIX ASPHALT SURFACE REMOVAL, 2 1/2"
- 11) PROPOSED HMA SURFACE COURSE, MIX "F", N90, 1 3/4"
- 12 PROPOSED GRADING & SHAPING SHOULDER



EXISTING TYPICAL CROSS SECTION STATION 455+80 TO STATION 477+70



PROPOSED TYPICAL CROSS SECTION STATION 455+80 TO STATION 477+70

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	ILLINOIS DEFARTMENT OF TRANSFORTATION	
		ILLINO	IS ROUTE 171
		ROBERTS ROAD TO	SOUTH OF 63RD STREET
		EXISTING AND PROPOSED TYPICAL SECTIONS	
		SCALE: VERT.	DRAWN BY
		DATE 3/28/2007	CHECKED BY

with the first the second of t