

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	COOK COUNTY 1000-1A 90% FED 10% STATE	DUPAGE COUNTY 1000-1A 90% FED 10% STATE		
20200100	EARTH EXCAVATION	CU YD	467	87	380		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	282	111	171		
20800150	TRENCH BACKFILL	CU YD	66	66			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	920	260	660		
25200110	SODDING, SALT TOLERANT	SQ YD	920	260	660		
25200200	SUPPLEMENTAL WATERING	UNIT	8	3	5		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	20	6	14		
28000400	PERIMETER EROSION BARRIER	FOOT	469	469			
28000510	INLET FILTERS	EACH	10	3	7		
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	292		292		
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	1515	593	922		
35300410	PORTLAND CEMENT CONCRETE BASE COURSE 9 1/2"	SQ YD	999	442	557		
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	413		413		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6	3	3		
40600300	AGGREGATE (PRIME COAT)	TON	22	11	11		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	4	2	2		
40600895	CONSTRUCTING TEST STRIP	EACH	2	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	106	59	47		
40600990	TEMPORARY RAMP	SQ YD	106	59	47		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	47		47		
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1065	534	531		
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	44		44		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2230		2230		
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	10134	5275	4859		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	481	20	461		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1850	518	1332		
44000600	SIDEWALK REMOVAL	SQ FT	2547		2547		

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	COOK COUNTY 1000-1A 90% FED 10% STATE	DUPAGE COUNTY 1000-1A 90% FED 10% STATE		
44003100	MEDIAN REMOVAL	SQ FT	2647	2447	200		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	82	82			
50300300	PROTECTIVE COAT	SQ YD	1917	618	1299		
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	107		107		
550A0030	STORM SEWERS, CLASS A, TYPE 1 8"	FOOT	14	14			
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	425	425			
55100300	STORM SEWER REMOVAL 8"	FOOT	14		14		
55100500	STORM SEWER REMOVAL 12"	FOOT	70		70		
60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	7	1	6		
60208240	CATCH BASINS, TYPE C, TYPE 24 FRAME AND GRATE	EACH	2	2			
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3	1	2		
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	3	1	2		
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	13	1	12		
60500050	REMOVING CATCH BASINS	EACH	5		5		
60624600	CORRUGATED MEDIAN	SQ FT	60	60			
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	193		193		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1330	176	1154		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	245		245		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	12.5	12.5			
63200310	GUARDRAIL REMOVAL	FOOT	75	75			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	3	3		
67100100	MOBILIZATION	L SUM	1	0.5	0.5		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.5	0.5		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	0.5	0.5		
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.5	0.5		
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1		1		
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1			

NP - NON-PARTICIPATING

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

Rev. R1

PLOT DATE: 3/2/2007

* SPECIALTY ITEM

3/2/2007 11:46:26 AM