

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	CARROLL	548	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* ROUTE 17 (US 52 / IL 64)
 ** (1,2)RS & (3,1)RS-1

SUMMARY OF QUANTITIES

Code No.	Item	Units	Total Quantity	← F →		
				80 % Fed. 20 % State 1 000-2A	100 % CITY Y060 UTILITIES	80 % Fed. 20 % State Y030-1E LIGHTING
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	747	747		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	423	423		
20100500	TREE REMOVAL, ACRES	ACRE	7	7		
20101000	TEMPORARY FENCE	FOOT	627	627		
20200100	EARTH EXCAVATION	CU YD	113,482	113,482		
20200200	ROCK EXCAVATION	CU YD	9,035	9,035		
20400800	FURNISHED EXCAVATION	CU YD	11,915	11,915		
20600300	QUARRY RUN GRANULAR EMBANKMENT	TON	7,643	7,643		
20800150	TRENCH BACKFILL	CU YD	307	307		
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	22,570	22,570		
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	59,050	59,050		
* 25000210	SEEDING, CLASS 2A	ACRE	40	40		
* 25000310	SEEDING, CLASS 4	ACRE	10	10		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4,533	4,533		
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4,533	4,533		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4,533	4,533		
* 25100115	MULCH, METHOD 2	ACRE	40	40		
* 25100125	MULCH, METHOD 3	ACRE	11	11		
* 25100630	EROSION CONTROL BLANKET	SQ YD	42,002	42,002		
* 25000750	MOWING	ACRE	50	50		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	20,147	20,147		
28000300	TEMPORARY DITCH CHECKS	EACH	273	273		
28000400	PERIMETER EROSION BARRIER	FOOT	10,509	10,509		
28000500	INLET AND PIPE PROTECTION	EACH	106	106		
28100107	STONE RIPRAP, CLASS A4	SO YD	62	62		
28100109	STONE RIPRAP, CLASS A5	SO YD	879	689		189
28100111	STONE RIPRAP, CLASS A6	SO YD	126	126		
28100113	STONE RIPRAP, CLASS A7	SO YD	40	40		
28200200	FILTER FABRIC	SQ YD	7,935	7,746		189
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	75			75
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SO YD	31,180	31,180		
31100920	SUB-BASE GRANULAR MATERIAL, TYPE A 15"	SO YD	9,768	9,768		
31100935	SUB-BASE GRANULAR MATERIAL, TYPE A 18"	SO YD	1,776	1,776		
31100965	SUB-BASE GRANULAR MATERIAL, TYPE A 24"	SO YD	11,254	11,254		
31103000	SUB-BASE GRANULAR MATERIAL (SPECIAL)	SO YD	2,371	2,371		
35101400	AGGREGATE BASE COURSE, TYPE B	TON	14,016	14,016		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	257.4	257.4		
40600300	AGGREGATE (PRIME COAT)	TON	229.4	229.4		

*SPECIALTY ITEM

© NON-PARTICIPATING

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE DRAWN BY CHECKED BY

SUMMARY OF QUANTITIES

PLT DATE = Thu, Mar 22 15:42:56 2007
 FILE NAME = C:\projects\127488\127488-vr.dgn
 PLOT SCALE = 50.0000 / 1 IN.
 USER NAME = eudmanle