

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	CARROLL	548	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

* ROUTE 17 (US 52 / IL 64)
 ** 1,2,1RS & 13,11RS-1

SUMMARY OF QUANTITIES

Code No.	Item	Units	Total Quantity	← F →		
				80 % Fed. 20 % State 1 000-2A	100 % CITY Y060 UTILITIES	80 % Fed. 20 % State Y030-1E LIGHTING
X0325304	MANHOLES, TYPE A, 7'-DIAMETER, WITH MEDIAN INLET (604106)	EACH	1	1		
X0325519	DRAIN FOR AGGREGATE BASE COURSE	SQ YD	82	82		
X0712400	TEMPORARY PAVEMENT	SQ YD	2,443	2,443		
X6063600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.24	FOOT	401	401		
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1	1		
XX005938	SOLAR-POWERED FLASHING BEACON ASSEMBLY (COMPLETE)	EACH	8	8		
XX172700	MANHOLES, TYPE A, 8'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1		
XX220000	REMOVE EXISTING LIGHTING SYSTEM	EACH	1		1	
Z0005400	BREAKER-RUN CRUSHED STONE	TON	1,521	607		914
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
Z0014800	CULVERT TO BE CLEANED	FOOT	193	193		
Z0023600	FILLING EXISTING CULVERTS	EACH	5	5		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	4		
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	4		
Z0040315	PILOT CAR	DAY	10	10		
Z0055100	RUMBLE RESURFACING	SQ YD	337	337		
Z0068800	STONE LINED DITCH	SQ YD	867	867		
Z0073500	TEMPORARY SUPPORT SYSTEM	L SUM	1			1
* SPECIALTY ITEMS						
+ NON-PARTICIPATING ITEMS						

PLOT DATE = Thu Mar 22 15:43:42 2007
 FILE NAME = C:\projects\207480\107480.dgn
 USER NAME =

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE DRAWN BY CHECKED BY