

12/20/2006 2:54:26 PM K:\1195800\115_3p\scadd\design\500_3P_01.dgn

SUMMARY OF QUANTITIES				FHWA 80% STATE 20% I000-2A	FHWA 80% STATE 20% Y007	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% X028-2A
CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY	MINOR STRUCTURE	SN 089-2020 (BOX CULVERT *7)	SN 089-2019 (BOX CULVERT *8)
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	34	34			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	127	127			
20100500	TREE REMOVAL, ACRES	ACRE	1.0	1.0			
20101000	TEMPORARY FENCE	FOOT	969	969			
20200100	EARTH EXCAVATION	CU YD	11,010	11,010			
20200200	ROCK EXCAVATION	CU YD	50	50			
20200410	EARTH EXCAVATION (SPECIAL)	CU YD	10	10			
20400800	FURNISHED EXCAVATION	CU YD	4,839	4,839			
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	4,368	4,368			
21101600	TOPSOIL FURNISH AND PLACE, VARIABLE DEPTH	SQ YD	23,855	23,855			
25000100	SEEDING, CLASS 1	ACRE	0.4	0.4			
25000210	SEEDING, CLASS 2A	ACRE	9.6	9.6			
25000310	SEEDING, CLASS 4	ACRE	1.1	1.1			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	999	999			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	999	999			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	999	999			
25000750	MOWING	ACRE	10.0	10.0			
25000775	SELECTIVE MOWING STAKES	EACH	6	6			
25100115	MULCH, METHOD 2	ACRE	11.1	11.1			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	4,400	4,400			
28000300	TEMPORARY DITCH CHECKS	EACH	61	61			
28000400	PERIMETER EROSION BARRIER	FOOT	6,929	6,929			
28000500	INLET AND PIPE PROTECTION	EACH	9	9			
28100105	STONE RIPRAP, CLASS A3	SQ YD	100	100			
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	1,529	1,529			
28200200	FILTER FABRIC	SQ YD	3,077	3,077			
28300470	AGGREGATE DITCH 12"	SQ YD	1,448	1,448			
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	440	440			
35101400	AGGREGATE BASE COURSE, TYPE B	TON	501	501			
35300415	PORTLAND CEMENT CONCRETE BASE COURSE 9 3/4"	SQ YD	999	999			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	81	81			
40600300	AGGREGATE (PRIME COAT)	TON	402	402			
40600525	LEVELING BINDER (HAND METHOD), N50	TON	20	20			
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	7,587	7,587			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	2,833	2,833			
40600990	TEMPORARY RAMP	SQ YD	634	634			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	2,428	2,428			

SUMMARY OF QUANTITIES				FHWA 80% STATE 20% I000-2A	FHWA 80% STATE 20% Y007	FHWA 80% STATE 20% X028-2A	FHWA 80% STATE 20% X028-2A
CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY	MINOR STRUCTURE	SN 089-2020 (BOX CULVERT *7)	SN 089-2019 (BOX CULVERT *8)
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	637	637			
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	11,380	11,380			
40701921	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 12"	SQ YD	440	440			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	1,305	1,305			
42001200	PAVEMENT FABRIC	SQ YD	999	999			
42001300	PROTECTIVE COAT	SQ YD	166	166			
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	60	60			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	291	291			
42400800	DETECTABLE WARNINGS	SQ FT	10	10			
44000100	PAVEMENT REMOVAL	SQ YD	1,199	1,199			
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	6,700	6,700			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	63	63			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	352	352			
44000600	SIDEWALK REMOVAL	SQ FT	462	462			
44002230	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 7 1/2"	SQ YD	5,780	5,780			
44200094	PAVEMENT PATCHING, TYPE II, 8 INCH	SQ YD	619	619			
44200099	PAVEMENT PATCHING, TYPE III, 8 INCH	SQ YD	65	65			
44200101	PAVEMENT PATCHING, TYPE IV, 8 INCH	SQ YD	16	16			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	7,696	7,696			
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	7,048	7,048			
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1			
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1			
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	1			
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1	1			
50100700	REMOVAL OF EXISTING STRUCTURES NO. 5	EACH	1	1			
50100800	REMOVAL OF EXISTING STRUCTURES NO. 6	EACH	1	1			
50100900	REMOVAL OF EXISTING STRUCTURES NO. 7	EACH	1	1			
50101000	REMOVAL OF EXISTING STRUCTURES NO. 8	EACH	1	1			
50101100	REMOVAL OF EXISTING STRUCTURES NO. 9	EACH	1	1			
50102400	CONCRETE REMOVAL	CU YD	4.0	4.0			
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1			
50105200	REMOVE EXISTING CULVERTS	EACH	5	5			
50300225	CONCRETE STRUCTURES	CU YD	1.9		1.9		

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 505 (IL 75)

SUMMARY OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE: 12/20/06

DRAWN BY JMC
CHECKED BY DWB

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
505	110RS-1, 111RS-3	STEPHENSON	174	5
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 64C32				