

PAVEMENT SCHEDULE																		
LOCATION	STATION		STATION	SQ YD	SQ YD	TON	TON	TON	SQ YD	SQ YD	TON	TON	SQ YD	SQ YD	SQ YD	TON	SQ YD	
IL 75																		
1	10138+30	TO	10160+00	0	0	3.62	19	349	316	49	0	523	0	0	0	300	0	
2	10160+00	TO	10190+00	0	0	5.16	26	485	227	54	71	727	0	0	0	403	809	
3	10190+00	TO	10205+00	0	0	2.34	12	229	0	0	0	344	0	0	0	248	0	
4	10205+00	TO	10220+00	0	57	2.47	13	240	0	0	0	359	0	57	0	167	0	
5	10220+00	TO	10235+00	0	0	2.44	13	238	0	0	0	357	0	0	0	178	0	
6	10235+00	TO	10250+00	0	171	2.65	13	239	62	28	82	358	0	171	0	96	931	
7	10250+00	TO	10265+00	0	136	2.50	13	245	0	0	0	367	0	136	0	111	0	
8	10265+00	TO	10280+00	0	0	2.49	13	243	0	0	0	365	0	0	0	245	0	
9	10280+00	TO	10295+00	0	0	2.58	13	242	0	0	41	363	0	0	0	218	428	
10	10295+00	TO	10310+00	0	187	2.40	13	235	103	24	0	352	0	187	0	157	0	
11	10310+00	TO	10325+00	0	0	2.39	13	234	79	19	0	351	0	0	0	248	0	
12	10325+00	TO	10340+00	0	167	2.39	13	234	0	0	0	350	0	167	0	108	0	
13	10340+00	TO	10355+00	0	0	2.44	13	239	0	0	0	358	0	0	0	237	0	
14	10355+00	TO	10370+00	0	281	2.42	13	237	0	0	0	356	0	281	0	120	0	
15	10370+00	TO	10385+00	0	0	2.31	12	226	124	29	0	339	0	0	0	200	0	
16	10385+00	TO	10400+00	0	0	2.60	13	241	105	25	55	361	0	0	0	191	603	
17	10400+00	TO	10430+00	0	0	4.98	26	487	0	0	0	731	0	0	0	511	0	
18	10430+00	TO	10445+00	0	0	2.52	13	242	99	23	0	364	0	0	0	205	0	
19	10445+00	TO	10460+00	0	0	2.55	13	238	154	36	45	356	0	0	0	139	482	
20	10460+00	TO	10490+00	0	0	4.69	25	458	30	7	0	687	0	0	0	241	0	
21	10490+00	TO	10520+00	0	0	5.00	24	440	49	12	194	661	0	0	0	334	2,144	
22	10520+00	TO	10550+00	0	0	4.68	24	455	82	19	6	683	0	0	0	481	56	
23	10550+00	TO	10580+00	0	0	4.87	26	477	0	0	0	716	0	0	0	508	0	
24	10580+00	TO	10600+00	0	0	3.63	17	319	173	14	143	479	0	0	0	200	1,596	
IL-26/CEDARVILLE RD				298	0	0.00	0	0	0	0	0	298	0	166	0	0	0	
IL-75/CEDARVILLE RD				142	0	0.16	1	31	56	0	0	47	142	0	0	27	0	
GOOD NEIGHBOR POLICY ROUTES				0	0	1.45	8	284	1,173	294	0	426	0	0	0	325	0	
TOTAL				440	999	78	402	7,587	2,833	634	637	11,380	440	999	166	* 6,198	7,048	

* ASSUMED 3" AVERAGE DEPTH.

DRIVEWAY AND SIDEROAD SCHEDULE										
LOCATION	STATION		STATION	TON	TON	TON	SQ YD	SQ FT	SQ FT	
IL 75										
1	10138+30	TO	10160+00	102	0.30	161.3	0	0	0	
2	10160+00	TO	10190+00	45	0.34	152.9	0	0	0	
3	10190+00	TO	10205+00	0	0.04	16.0	0	0	0	
4	10205+00	TO	10220+00	42	0.06	37.8	0	0	0	
5	10220+00	TO	10235+00	15	0.17	71.6	0	0	0	
6	10235+00	TO	10250+00	3	0.24	92.8	0	0	0	
7	10250+00	TO	10265+00	16	0.00	0.0	0	0	0	
8	10265+00	TO	10280+00	0	0.02	6.5	0	0	0	
9	10280+00	TO	10295+00	5	0.00	0.0	0	0	0	
10	10295+00	TO	10310+00	0	0.13	50.2	0	0	0	
11	10310+00	TO	10325+00	0	0.06	23.5	0	0	0	
12	10325+00	TO	10340+00	14	0.02	7.3	0	0	0	
13	10340+00	TO	10355+00	0	0.02	7.4	0	0	0	
14	10355+00	TO	10370+00	0	0.00	0.0	0	0	0	
15	10370+00	TO	10385+00	0	0.30	118.1	0	0	0	
16	10385+00	TO	10400+00	0	0.16	62.3	0	0	0	
17	10400+00	TO	10430+00	4	0.00	0.0	0	0	0	
18	10430+00	TO	10445+00	72	0.20	110.5	0	0	0	
19	10445+00	TO	10460+00	15	0.38	156.7	0	0	0	
20	10460+00	TO	10490+00	41	0.14	63.6	0	0	0	
21	10490+00	TO	10520+00	13	0.11	48.2	0	0	0	
22	10520+00	TO	10550+00	41	0.14	65.6	0	0	0	
23	10550+00	TO	10580+00	0	0.04	14.7	0	0	0	
24	10580+00	TO	10600+00	19	0.03	18.1	0	0	0	
IL-26/CEDARVILLE RD				54	0.00	19.9	60	291	10	
IL-75/CEDARVILLE RD				0	0.00	0.0	0	0	0	
GOOD NEIGHBOR POLICY ROUTES				0	0.00	0.0	0	0	0	
TOTAL				501	3	1,305	60	291	10	

CODE NO.	PAY ITEM	QUANTITY	LOCATION
50100300	REMOVAL OF EXISTING STRUCTURES NO.1	1 EACH	10211+00 (AR)
50100400	REMOVAL OF EXISTING STRUCTURES NO.2	1 EACH	10248+73 (AR)
50100500	REMOVAL OF EXISTING STRUCTURES NO.3	1 EACH	10248+73, LT (RR)
50100600	REMOVAL OF EXISTING STRUCTURES NO.4	1 EACH	10263+23 (AR)
50100700	REMOVAL OF EXISTING STRUCTURES NO.5	1 EACH	10306+90 (AR)
50100800	REMOVAL OF EXISTING STRUCTURES NO.6	1 EACH	10332+16 (AR)
50100900	REMOVAL OF EXISTING STRUCTURES NO.7	1 EACH	10332+16, LT (RR)
50101000	REMOVAL OF EXISTING STRUCTURES NO.8	1 EACH	10357+12 (AR)
50101100	REMOVAL OF EXISTING STRUCTURES NO.9	1 EACH	10369+83 (AR)

(AR) = ACROSS-ROAD
(RR) = RAILROAD

AGGREGATE SHOULDERS, TYPE B (48101200)				
6" DEPTH AT AR CULVERT LOCATIONS				
CULVERT #	STATION		STATION	TON
1	10209+00	TO	10213+00	131
2/3	10225+00	TO	10228+50	99
4	10246+00	TO	10253+50	254
5	10260+00	TO	10265+50	180
6	10303+50	TO	10309+00	175
7	10328+50	TO	10337+00	284
8	10354+00	TO	10360+00	205
9	10367+00	TO	10372+00	170
SUB-TOTAL:				1,498
TOTAL:				6,198 + 1,498 = 7,696

CODE #	PAY ITEM	APPLICATION RATES
40600200	BITUMINOUS MATERIALS (PRIME COAT)	0.000286 TON / SY
40600300	AGGREGATE (PRIME COAT)	0.0015 TON / SY
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	112 LB / SY * IN
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	112 LB / SY * IN
40600625	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N50	112 LB / SY * IN
48101200	AGGREGATE SHOULDERS, TYPE B	2.05 TON / CY

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 505 (IL 75)

SCHEDULES OF QUANTITIES

SCALE: DATE: 12/20/06

DRAWN BY JMC
CHECKED BY DWB