

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
505	*	STEPHENSON	174	82A
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
• 110RS-1 & 111RS-3				

LETTERING FOR NAME PLATE

STATION
 BUILT 200 BY
 STATE OF ILLINOIS
 RTE. SEC.
 FA PROJECT
 LOADING HS 20
 STR. NO.

SEE STD. 515001

ALL DIMENSIONS ARE IN MILLIMETERS (INCHES) UNLESS OTHERWISE NOTED.

LETTERING FOR NAME PLATE 89.4

REVISED 10-15-04

TREE REPLACEMENT SCHEDULE

CODE NUMBER	SCIENTIFIC NAME	COMMON NAME	SIZE	UNIT	QUANTITY
A2001714	ACER SACCHARUM	SUGAR MAPLE	1 3/4" CALIPER B&B	EACH	10
A2006714	QUERCUS MACROCARPA	BUR OAK	1 3/4" CALIPER B&B	EACH	10
B2000562	AMELANCHIER CANADENSIS	SHADBLOW SERVICEBERRY	4' HEIGHT, SHRUB FORM, B&B	EACH	20
B2005214	MALUS SUTYZAM	SUGAR TYME CRABAPPLE	1 3/4" CALIPER, TREE FORM, B&B	EACH	19

LAYOUT SHALL BE PERFORMED BY THE DISTRICT LANDSCAPE ARCHITECT.
 MULCH SHALL BE HARDWOOD WOOD CHIPS, 5' WIDTH, 4" THICK WITH WEED BARRIER FABRIC.

ALL DIMENSIONS ARE IN MILLIMETERS (INCHES) UNLESS OTHERWISE NOTED.

TREE REPLACEMENT SCHEDULE 90.4

REVISED 8-10-05