INDEX OF SHEETS

1 COVER SHEET

2 GENERAL NOTES 3 - 4 SUMMARY OF QUANTITIES

5 TYPICAL SECTIONS 6 - 8 SCHEDULE OF QUANTITIES

9-11 SURVEY TIES

12 PROJECT LAYOUT

13 PAVEMENT MARKING DETAILS

14-16 MISCELLANEOUS DETAILS

HIGHWAY STANDARDS

TRAFFIC CONTROL DEVICES
TYPICAL PAVEMENT MARKINGS

001006 DECIMAL OF AN INCH AND OF A FOOT 280001-03 TEMPORARY EROSION CONTROL SYSTEMS 667101 PERMANENT SURVEY MARKERS 701006-02 OFF-ROAD OPERATIONS 2L, 2W, 4.5 m (15') TO 600 mm (24") FROM PAVEMENT EDGE 701011-01 OFF-ROAD MOVING OPERATIONS, 2-L, 2-W, DAY ONLY 701301-02 LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS 701306-01 LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS DAY ONLY, FOR SPEEDS ≥ 45 MPH LANE CLOSURE, 2-L, 2-W, MOVING DAY ONLY OPERATIONS 701311-02

TYPICAL APPLICATIONS, RAISED REFLECTIVE PAVEMENT MARKERS

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

DIVISION OF HIGHWAYS

PROPOSED HIGHWAY PLANS

F.A.P. ROUTE 41 (IL 17)

SECTION (15)RS-3

PROJECT F - 0041 (128)

LIVINGSTON COUNTY

C - 93 - 023 - 04

3P RESURFACING AND MILLING ECL OF DWIGHT TO WEST OF REDDICK

OMISSION SN 053-0150 END IMPROVEMENT STA. 322 + 02.47 TO 324 + 39.61 STA 428+00 **BEGIN IMPROVEMENT** STA -1 + 18.00 OMISSION SN 053-0146 STA. 184 + 54.38 TO 185 + 84.40 IL 47 & IL 17 INTERSECTION STA 0+00 OMISSION SN. 053-0147 SN. 053-2011 STA. 238 + 40 TO 249 + 85 STA. 8 + 82 (BOX CULVERT) OMISSION SN. 053-0151 STA. 407 + 26.03 TO 408 + 41.97

LOCATION MAP

GROSS LENGTH = 42,918.00 FT. = 8.128 MI. NET LENGTH = 41,289.90 FT. = 7.820 MI.

FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES, REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES, IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

J.U.L.I.E.

702001-06

780001-01

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION 1-800-892-0123

DISTRICT 3 NO. (815) 434-6131

PROJECT ENGINEER: JOE KANNEL UNIT CHIEF: MICHELE LINDEMANN TOWNSHIP: DWIGHT & ROUND

CONTRACT NO. 66421

F.A.P. SECTION COUNTY TOTAL SHEETS NO. 41 (15)RS-3 LIVINGSTON 16 1


D-93-022-04



RURAL MINOR ARTERIAL

2005 ADT = 3000

P.V. = 75.0 % S.U. = 5.0 % M.U. = 20.0 %



PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS

* DATE - TIME*