

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301		**	18	5
STA.		TO STA.		
FED. ROAD DIST. NO. 6		ILLINOIS	FED. AID PROJECT	
*113RS-3 & 114RS-2		**GRUNDY & WILL		

MAINLINE

LOCATION	BIT MAT'L PR CT (GAL)	AGG PRIME COAT (TON)	MIX CR,JT &FLGWY (TON)	LEV BIND (HM) N50 (TON)	LEV BIND (MM) N70 (TON)	HMA SURF CSE "D", N70 (TON)	HMA SURF REM 1 1/2" (SQ YD)	HMA SURF VAR DEPTH (SQ YD)	HMA SURF BUTT JT (SQ YD)	AGG WEDGE SHLDRS TYPE B TON	TEMP RAMP (SQ YD)
GRUNDY COUNTY											
8+27 TO 17+56	310	7.75	1.16	1.9		325	3874				14.44
17+56 TO 41+98	564	14.11	2.12	3.5		593	7055				14.44
41+98 TO 77+00	PCC PAVEMENT OMISSION										
77+00 TO 85+82	204	5.10	0.76	1.3		214	2548				28.88
85+82 TO 86+11	RAILROAD OMISSION										
86+11 TO 160+34	1716	42.89	6.43	10.7		1801	21444				14.4
WILL COUNTY											
160+34 TO 190+32	798	19.96	3.09	5.0	414	838	136	216		126	
190+32 TO 191+22	26	0.64	0.1	0.2	15	27			213	4	17.78
TOTALS	3618	90	14	23	429	3798	35057	216	213	130	90

PAVEMENT MARKING

LOCATION	THERMOPLASTIC							TEMPORARY PAINT				RAISED REFL PAVT MARKER EACH	SHORT TERM PVT MK FOOT
	LTRS & SYM	4"		6"		8"		LTRS & SYM	4"	6"	8"		
	WHITE SQ FT	YELLOW FOOT	WHITE FOOT	YELLOW FOOT	WHITE FOOT	YELLOW FOOT	WHITE FOOT	WHITE SQ FT	YELLOW FOOT	YELLOW FOOT	WHITE FOOT		
GRUNDY CO.													
8+27 TO 12+37.5													
TURN LANE	81.3					237		46.8			237	5	326
CENTERLINE		266							266			6	54
MEDIAN		1110							1110			22	222
12+72 TO 17+60													
TURN LANE	54.2	200			136			31.2	200		136	9	252
MEDIAN		1552				158			1552			20	310
17+60 TO 22+83													
CENTERLINE				130						130		7	104
NO PASSING ZONE		523							523				
22+83 TO 41+98													
CENTERLINE				480						480		24	384
77+00 TO 41+98													
CENTERLINE				220						220		11	176
NO PASSING ZONE		675							675				
RAILROAD	122.4						81						
86+11 TO 160+34													
CENTERLINE				1860						1870		93	1484
NO PASSING ZONE		337							337				
RAILROAD	61.2						39						
WILL CO.													
160+34 TO 189+3/4													
CENTERLINE			5750	730								37	584
189+3/4													
MEDIAN		664				12						10	132
EOP			332										
TOTALS	319.1	5327	6082	3420	373	291	120	78	4663	2700	373	244	4028

PLOT DATE = 3/22/2007
 FILE NAME = c:\projects\aed96305\detail.dgn
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = duncmbd

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. DATE
 HORIZ. DATE

DRAWN BY
 CHECKED BY