

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
39	*	LASALLE	16	3

\*50(1,2,3,4,5,6,7,8)PATCHING

# SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: **J000**

RURAL  
100% STATE  
TOTAL  
QUANTITY

CODE NO.	ITEM	UNIT	QUANTITY
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	818
44000100	PAVEMENT REMOVAL	SQ YD	818
42001200	PAVEMENT FABRIC	SQ YD	818
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SQ YD	178
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SQ YD	54
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	825
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	120
44213000	PATCHING REINFORCEMENT	SQ YD	232
44213100	PAVEMENT FABRIC	SQ YD	945
44213200	SAW CUTS	FOOT	6210
67100100	MOBILIZATION	L SUM	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	40
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1
70103710	TRAFFIC CONTROL FOR RAMPS	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	25
*78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1644
*78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	150
*78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	136
*78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	52
Z0017202	DOWEL BARS 1 1/2"	EACH	2156
Z0075310	TIE BARS 3/4"	EACH	20

\*SPECIALTY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
FAI ROUTE 39 (I-39)  
SECTION 50(1,2,3,4,5,6,7,8)PATCHING  
LASALLE COUNTY

Date: February 27, 2007  
c:/projects/cmain08/cm304/details.dgn