

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
687	*	Fulton	37	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* D4 CULVERT EXT/ REPAIR 2007				

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNITS	TOTAL QUANTITY	100% STATE Y007 Fulton Co.
20100500	TREE REMOVAL, ACRES	ACRE	0.77	0.77
20200100	EARTH EXCAVATION	CU YD	2,928	2,928
20400800	FURNISHED EXCAVATION	CU YD	1,157	1,157
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	3,973	3,973
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	90
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	90
* 25001700	SEEDING, CLASS 3 (MODIFIED)	ACRE	1.00	1.00
* 25100115	MULCH, METHOD 2	ACRE	0.50	0.50
* 25101005	HEAVY DUTY EXCELSIOR BLANKET	SQ YD	3,147	3,147
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	300	300
28000300	TEMPORARY DITCH CHECKS	EACH	16	16
28000400	PERIMETER EROSION BARRIER	FOOT	97	97
28000500	INLET AND PIPE PROTECTION	EACH	2	2

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNITS	TOTAL QUANTITY	100% STATE Y007 Fulton Co.
28100107	STONE RIPRAP, CLASS A4	SQ YD	1,071	1,071
28100125	STONE RIPRAP, CLASS B3	SQ YD	58	58
28102630	STONE RIPRAP DITCH CHECKS	EACH	13	13
28200200	FILTER FABRIC	SQ YD	1,071	1,071
48101200	AGGREGATE SHOULDERS TYPE B	TON	20	20
50102400	CONCRETE REMOVAL	CU YD	2.7	2.7
50800105	REINFORCEMENT BARS	POUND	217	217
50901760	PIPE HANDRAIL	FOOT	16	16
54002020	EXPANSION BOLTS 3/4 INCH	EACH	8	8
54202965	PIPE CULVERTS, TYPE 4 RCCP 30"	FOOT	82	82
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1
54248510	CONCRETE COLLAR	CU YD	1	1
54390200	INSERTION CULVERT LINER 28"	FOOT	159	159
60222250	MANHOLES, TYPE A, 5'- DIAMETER, TYPE 37 GRATE	EACH	1	1
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	500	500

\* SPECIALTY ITEM