

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
687	*	Fulton	37	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* D4 CULVERT EXT/ REPAIR 2007				

CODE NO. 20100500

TREE REMOVAL, ACRES	
LOCATION	ACRE
Lt Sta. 590+00 to 593+06	0.60
Rt. Sta. 590+26 to 593+00	0.17
<b>TOTAL = 0.77</b>	

CODE NO.	20200100	20400800	21101615
	EARTH EXCAVATION	FURNISHED EXCAVATION	F & P TOPSOIL, 4"
	CU YD	CU YD	SQ YD
LOCATION			
STA. 588+50 TO 593+50	2,928	1,157	3,973
<b>TOTAL</b>	<b>2,928</b>	<b>1,157</b>	<b>3,973</b>

CODE NO.	28000250	25001700	25100115	25000400	25000500	25000600
	TEMPORARY EROSION CONTROL SEEDING *	SEEDING CLASS 3 (MODIFIED)	MULCH METHOD 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHOROUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT
	POUND	ACRE	ACRE	POUND	POUND	POUND
LOCATION						
Sta. 588+90.81 to Sta. 593+08.82	300	1.00	.50	90	90	90
<b>TOTAL =</b>	<b>300</b>	<b>1.00</b>	<b>.50</b>	<b>90</b>	<b>90</b>	<b>90</b>

\* 3 Applications

CODE NO. 25101005

HEAVY DUTY EXCELSIOR BLANKET	
LOCATION	SQ YD
Rt. Sta. 590+29.27 to Sta. 593+08.82	1,666.52
Lt. Sta. 590+50 to Sta. 592+72.98	1,480.30
<b>TOTAL = 3,147</b>	

CODE NO. 28000300

TEMPORARY DITCH CHECK	
LOCATION	UNIT EACH
Rt. Sta. 589+50 to Sta. 592+43	7
Lt. Sta. 590+50 to Sta. 592+69	9
<b>TOTAL = 16</b>	