

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
687	*	Fulton	37	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* D4 CULVERT EXT/ REPAIR 2007

CODE NO.63100045

TRAFFIC BARRIER TERMINAL, TYPE 2	
LOCATION	UNIT EACH
Lt. Sta. 592+95 to Sta. 593+01	1
TOTAL = 1	

CODE NO.63100167

TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	
LOCATION	UNIT EACH
Lt. Sta. 590+12.5 to Sta. 590+62.5	1
Rt. Sta. 589+25 to Sta. 589+75	1
TOTAL = 2	

CODE NO.63100169

TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	
LOCATION	UNIT EACH
Rt. Sta. 592+37.5 to Sta. 592+87.5	1
TOTAL = 1	

CODE NO.66502300

WOVEN WIRE FENCE REMOVAL	
LOCATION	UNIT FOOT
Lt Sta. 590+00 to Sta. 593+06.71	307.32
Lt. Sta. 590+81.85 to Sta. 590+97.41	33.33
TOTAL = 340.65	

CODE NO.66600105

FURNISHING AND ERECTING RIGHT OF WAY MARKERS	
LOCATION 1	UNIT EACH
Sta. 591+00, 86.25' Lt	1
Sta. 591+75, 160' Lt	1
Sta. 592+25, 160' Lt	1
Sta. 593+05.34, 110' Lt	1
Sta. 590+50, 87.46' Rt	1
Sta. 591+00, 120' Rt	1
Sta. 591+50, 120' Rt	1
Sta. 592+00, 100.93' Rt	1
TOTAL = 8	

CODE NO.67000400

ENGINEER'S FIELD OFFICE, TYPE A	
LOCATION	UNIT CAL MO
JOBSITE	2
TOTAL = 2	

CODE NO.67100100

MOBILIZATION	
LOCATION	UNIT L SUM
JOBSITE	1
TOTAL = 1	

CODE NO.70100450

TRAFFIC CONTROL AND PROTECTION STANDARD 701201	
LOCATION	UNIT L.SUM
Sta. 588+60 to Sta. 593+50	1
TOTAL = 1.0	

CODE NO.78200410

GUARDRAIL MARKER TYPE A	
LOCATION	UNIT EACH
Rt. Sta. 589+25 to Sta. 592+87.5	4
Lt. Sta. 590+12.5 to Sta. 593+01	6
TOTAL = 10	

CODE NO.78201000

TERMINAR MARKER - DIRECT APPLIED	
LOCATION	UNIT EACH
Rt. Sta. 589+25	1
Lt. Sta. 590+12.5	1
Rt. Sta. 592+87.5	1
TOTAL = 3	

CODE NO.X0301512

GUARDRAIL AGGREGATE EROSION CONTROL	
LOCATION	UNIT TON
Rt. Sta. 588+90.81 to Sta. 593+08.83	53.2
Lt. Sta. 589+77.48 to Sta. 593+09.57	40.4
TOTAL = 93.6	