

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|-------------|---------|-----------|--------------|-----------|
| 332 | . | VERMILION | 62 | 6 |

(47Z-3)RS-1 & (52CS,48Z-1)RS-3

SCHEDULE OF QUANTITIES

| TABULATION OF MAINLINE RESURFACING QUANTITIES | | | | | | | | | |
|---|-----------------------------|--------|-----------------------|---------------------|---------------------------------|--------------------------------|--|--|--|
| LOCATION | AVERAGE TOTAL ROADWAY WIDTH | LENGTH | AREA | 44000154 | 40600100 | 40600300 | 40603595 | | |
| | | | | HMA SURFACE REMOVAL | BITUMINOUS MATERIALS PRIME COAT | AGGREGATE MATERIALS PRIME COAT | POLYMERIZED HMA SURFACE CSE MIX "F", N90 | | |
| | | | | 1.25 IN | TON | TON | TON | | |
| | FOOT | FOOT | SQ YD | SQ YD | TON | TON | TON | | |
| GILBERT ST./MAIN ST. | | | 9658.2 | 9658.2 | 965.8 | 19.3 | 869.2 | | |
| STA. 103 + 20 TO 133 + 60 | 54.00 | 3039.9 | 18239.5 | 18239.5 | 1823.9 | 36.5 | 1641.8 | | |
| RAILROAD OMISSION | | | | | | | | | |
| STA. 133 + 69 TO 146 + 50 | 54.00 | 1280.7 | 7684.2 | 7684.2 | 768.4 | 15.4 | 691.6 | | |
| STA. 146 + 50 TO 148 + 25 | 52.50 | 175.0 | 1020.8 | 1020.8 | 102.1 | 2.0 | 91.9 | | |
| GILBERT ST./FAIRCHILD ST. | | | 4271.4 | 4271.4 | 427.1 | 8.5 | 384.4 | | |
| STA. 29 + 32 TO 35 + 00 | 57.00 | 568.0 | 3597.3 | 3597.3 | 359.7 | 7.2 | 323.8 | | |
| STATI 0 + 00 TO 0 + 00 | | | | | | | | | |
| STA. 43 + 44 TO 47 + 09 | 56.00 | 365.3 | 2272.9 | 2272.9 | 227.3 | 4.5 | 204.6 | | |
| FAIRCHILD ST./VERMILION ST. | | | 4714.3 | 4714.3 | 471.4 | 9.4 | 424.3 | | |
| STA. 102 + 54 TO 124 + 63 | 55.00 | 2209.4 | 13502.0 | 13502.0 | 1350.2 | 27.0 | 1215.2 | | |
| STA. 124 + 63 TO 127 + 60 | 55.00 | 296.9 | 1814.4 | 1814.4 | 181.4 | 3.6 | 163.3 | | |
| STA. 127 + 60 TO 129 + 16 | 51.50 | 156.1 | 893.2 | 893.2 | 89.3 | 1.8 | 80.4 | | |
| STA. 129 + 16 TO 174 + 00 | 48.00 | 4483.9 | 23914.1 | 23914.1 | 2391.4 | 47.8 | 2152.3 | | |
| STA. 174 + 00 TO 174 + 98 | 52.00 | 98.0 | 566.2 | 566.2 | 56.6 | 1.1 | 51.0 | | |
| STA. 174 + 98 TO 175 + 25 | 56.00 | 27.0 | 168.0 | 168.0 | 16.8 | 0.3 | 15.1 | | |
| WINTER AVE./VERMILION ST. | | | 3882.1 | 3882.1 | 388.2 | 7.8 | 349.4 | | |
| STA. 180 + 39 TO 183 + 00 | 56.00 | 261.0 | 1624.0 | 1624.0 | 162.4 | 3.2 | 146.2 | | |
| | | | GRAND-TOTALS = | 97,822.5 | 9,782.3 | 195.6 | 8,804 | | |
| | | | USE | 97823.0 | 9783.0 | 196.0 | 8805.0 | | |

| TABULATION OF INCIDENTAL RESURFACING QUANTITIES | | | | |
|---|-----------------------------|---------------------------------|--------------------------------|--------------------------|
| LOCATION | 44000196 | 40800010 | 40800030 | 40800050 |
| | HMA SURFACE REMOVAL SPECIAL | BITUMINOUS MATERIALS PRIME COAT | AGGREGATE MATERIALS PRIME COAT | INCIDENTAL HMA SURFACING |
| | SQ YD | GALLONS | TON | TON |
| | | | | |
| ENGLISH ST. (EAST) | 250.50 | 25.05 | 0.50 | 21.04 |
| ENGLISH ST. (WEST) | 179.30 | 17.93 | 0.36 | 15.06 |
| VORHEES ST. (EAST) | 406.59 | 40.66 | 0.81 | 34.15 |
| VORHEES ST. (WEST) | 353.64 | 35.36 | 0.71 | 29.71 |
| WINTER AVE. (WEST) | 381.00 | 38.10 | 0.76 | 32.00 |
| | GRAND-TOTALS = | 1,571.0 | 157.1 | 132.0 |
| | USE | 1,571.0 | 157.0 | 132.0 |

| 40600900 TEMPORARY RAMPS | |
|-----------------------------|--------------|
| LOCATION | SQ YD |
| S. GILBERT ST. | 45.4 |
| E. MAIN | 32.2 |
| W. MAIN | 31.1 |
| W. FAIRCHILD | 30.6 |
| N. GILBERT | 28.9 |
| S. VERMILION | 32.8 |
| E. FAIRCHILD | 31.7 |
| E. WINTER | 72.9 |
| W. WINTER | 71.6 |
| TOTAL = | 377.2 |
| USE = | 378.0 |