

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
725	(10-72VB)BRD	CHAMPAIGN	15	4

SUMMARY OF QUANTITIES

LOCATION OF WORK:
FAP 725 (I-72 / CHURCH STREET)
SN 010-0037 OVER ICRR

CHAMPAIGN COUNTY
URBAN
ROADWAY / STRUCTURE
IMPROVEMENTS
FAP 725
STA. 2012N+05.51
STA. 2014N+57.73
100% STATE
SFTY-2A

CONSTRUCTION TYPE CODE:

<u>CODE NO</u>	<u>ITEM</u>	<u>UNIT</u>	<u>TOTAL QUANTITY</u>	<u>QUANTITY</u>
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	92.0	92.0
40600300	AGGREGATE (PRIME COAT)	TON	2.0	2.0
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	90.0	90.0
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	918.0	918.0
50157300	PROTECTIVE SHIELD	SQ YD	604.0	604.0
67100100	MOBILIZATION	L SUM	1.0	1.0
70100325	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423	EACH	1.0	1.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	946.0	946.0
70400100	TEMPORARY CONCRETE BARRIER	FOOT	500.0	500.0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	500.0	500.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3,192.0	3,192.0
78300100	PAVEMENT MARKING REMOVAL	SQ FT	874.0	874.0
X0325205	MONODIRECTIONAL REFLECTORS TYPE C	EACH	28.0	28.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14.0	14.0
* X7200201	WIDTH RESTRICTION SIGNING	L SUM	1.0	1.0
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	48.0	48.0
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	140.0	140.0
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	89.0	89.0
* Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1.0	1.0
* Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1.0	1.0
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0	1.0
* SPECIALTY ITEMS				