

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	LOGAN	111	9
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

FAP ROUTE 320 AT FAU ROUTE 77066  
 \*\* (103, 22), N, TS

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 LOCATION OF WORK: IL 10/121 (WOODLAWN ROAD) AT OLD U.S. 66 (LINCOLN PARKWAY)

F  
 80% Fed.  
 20% State

F  
 80% Fed.  
 20% State

HS  
 90% FED.  
 10% STATE

⚠

CODE NO.	ITEM	UNIT	URBAN			
			TOTAL	1000-1A	1000-1A	Y031-1F
*81021570	CONDUIT, AUGURED 3" DIA., PVC	FOOT	174			174
*81021590	CONDUIT, AUGURED 4" DIA., PVC	FOOT	157			157
*81400100	HANDHOLE	EACH	3			3
*81400300	DOUBLE HANDHOLE	EACH	2			2
*81900200	TRENCH BACKFILL FOR ELECTRICAL WORK	FOOT	4,373.5			4,373.5
*81603025	UNIT DUCT, 600 V, 2-1C NO. 4, 1/C NO. 4 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	1,110			1,110
*81603035	UNIT DUCT, 600 V, 2-1C NO. 6, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	3,898			3,898
*82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	14			14
*82104250	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, PHOT-CELL CONTROL, 250 WATT	EACH	4			4
*82500605	LIGHTING CONTOLLER PHOTOCELL RELAY	EACH	1			1
*83034400	LIGHT POLE STEEL, 45' MH, TENON MOUNT	EACH	14			14
*83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	92			92
* 83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	14			14
*84200500	REMOVAL OF EXISTING LIGHTING UNIT-SALVAGE	EACH	9			9
*84200805	POLE FOUNDATION REMOVED, METAL	EACH	9			9

\* SPECIALTY ITEMS

PLOT DATE : 3/20/2007  
 FILE NAME : c:\projects\76533284\ah\taunemr.pdg  
 PLOT SCALE : 85/8821 / IN.  
 USER NAME : taugh11r1

REVISIONS	
NAME	DATE
TMJ	03-07

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SUMMARY OF QUANTITIES  
 FAP ROUTE 320 (IL 10/121) AT  
 FAU ROUTE 77066 (OLD US 66)  
 LOGAN COUNTY

SCALE: VERT.  
 HORIZ.  
 DATE 03-21-06

DRAWN BY TMJ  
 CHECKED BY VTY

⚠ Rev. 6-5-07