

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	LOGAN	111	21
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- * FAP ROUTE 320 AT FAU ROUTE 77066
- ** (103, 22)1, N, TS

INCIDENTAL BITUMINOUS SURFACING	
LOCATION	QUANTITY (SQ.YD.)
BIT. ENTRANCE, STA 6+00.00 LT	34.1
BIT. ENTRANCE, STA 6+00.00 RT	41.4
TOTAL	75.5

PORTLAND CEMENT CONCRETE BASE COURSE 9"	
LOCATION	QUANTITY (SQ. YD.)
STA 134+58.00 TO STA 137+38.00 RT	344.2
STA 138+30.00 TO STA 141+51.00 LT	380.6
STA 1759+00.00 TO STA 1761+81.00 RT	325.8
STA 0+42.00 TO STA 0+91.00 LT	71.7
STA 2+22.00 TO STA 4+06.00 LT	187.4
NORTH MEDIAN NOSE	6.8
SOUTH MEDIAN NOSE	7.0
WEST MEDIAN NOSE	7.2
EAST MEDIAN	86.4
TOTAL	1,417.1

PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 9"	
LOCATION	QUANTITY (SQ. YD.)
STA 133+80.00 TO STA 134+58.00 RT	26.2
STA 137+38.00 TO STA 137+46.00 RT	18.5
STA 138+91.00 TO STA 139+77.00 RT	23.7
STA 138+16.00 TO STA 138+30.00 LT	31.0
STA 141+51.00 TO STA 143+21.00 LT	41.8
STA 1758+50.00 TO STA 1759+00.00 RT	18.6
STA 1761+81.00 TO STA 1761+91.45 RT	30.4
STA 0+91.00 TO STA 1+17.00 LT	7.9
STA 1+46.00 TO STA 2+22.00 LT	21.2
STA 4+06.00 TO STA 5+14.00 LT	37.5
TOTAL	256.8

PORTLAND CEMENT CONCRETE DRIVEWAY, 8 INCH	
LOCATION	QUANTITY (SQ. YD.)
STA 134+38.34 RT	89.2
STA 135+38.02 RT	77.1
STA 141+37.35 RT	57.1
TOTAL	223.4

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	
LOCATION	QUANTITY (FOOT)
STA 135+92.94 LT TO STA 1761+19.99 RT	211.0
STA 133+79.68 RT TO STA 1+31.46 RT	428.0
STA 1+25.04 LT TO STA 139+76.8 RT	192.0
STA 1761+22.62 LT TO STA 142+67.17 LT	467.0
TOTAL	1298.0

COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	
LOCATION	QUANTITY (FOOT)
N.E. ISLAND	58.0
S.E. ISLAND	67.0
N.W. ISLAND	62.0
S.W. ISLAND	58.0
SOUTH MEDIAN NOSE	33.0
WEST MEDIAN NOSE	35.0
NORTH MEDIAN NOSE	23.0
TOTAL	336.0

SIDEWALK REMOVAL	
LOCATION	QUANTITY (SQ.FT.)
STA 141+79.57 TO STA 142+57.57 LT	312
TOTAL	312

PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	
LOCATION	QUANTITY (SQ.FT.)
STA 141+79.57 TO STA 142+57.57 LT	390
SIDEWALK RAMPS (NE & NW ISLANDS)	50
TOTAL	440

AGGREGATE FOR TEMPORARY ACCESS	
LOCATION	QUANTITY (TON)
ENTRANCE AT STA 134+38.34 RT	40.6
ENTRANCE AT STA 135+38.02 RT	35.1
ENTRANCE AT STA 141+37.35 RT	26
TOTAL	101.7

PLOT DATE : 3/28/2007
 FILE NAME : c:\projects\653384\shsched\shsdr
 PLOT SCALE : 1/8"=1'-0"
 USER NAME : laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAP ROUTE 320 (IL 10/121) AT
 FAU ROUTE 77066 (OLD US 66)
 LOGAN COUNTY
 SCALE: VERT. DRAWN BY TMJ
 HORIZ. CHECKED BY VTY
 DATE 03-22-06