CONTRACT NO. 72B07

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	*	SANGAMON	14	2
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* D-6 PAVEMENT PATCHING 2007

1. ANY REFERENCE TO THE STANDARDS THROUGHOUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.

2. EXISTING PAVEMENT DAMAGED DUE TO THE CONTRACTOR'S OPERATIONS, NOT OTHERWISE NECESSARY TO REPLACE, SHALL BE REPLACED AT THE EXPENSE OF THE CONTRACTOR

3. NO EXCAVATION ANTICIPATED ON THIS PROJECT WHICH WOULD AFFECT UTILITIES. SHOULD ANY EXCAVATION DEVIATING FROM THAT ANTICIPATED BE REQUIRED, J.U.L.I.E. WILL BE NOTIFIED A MINIMUM OF 48 HOURS IN ADVANCE - (800) 892-0123.

4. IN ADDITION TO FIELD SURVEYS AND AERIAL SURVEYS, PLAN DIMENSIONS AND DETAILS RELATIVE TO THE EXISTING FACILITIES HAVE BEEN TAKEN FROM EXISTING PLANS AND ARE SUBJECT TO CONSTRUCTION VARIATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY SUCH DIMENSIONS AND DETAILS IN THE FIELD. SUCH VARIATIONS SHALL NOT BE A CAUSE FOR ADDITIONAL COMPENSATION DUE TO A CHANGE IN THE SCOPE OF THE WORK. HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE BID PRICE FOR THE WORK.

5. ACTUAL SIZE AND LOCATIONS OF PATCHES WILL BE DETERMINED IN THE FIELD BY THE RESIDENT ENGINEER.

LIST OF STANDARDS

000001 - 04
001001 - 01
001006
442001 - 03
701101 - 01
701106 - 01
701411 - 03
701421 - 01
701422 - 01
701701 - 04
702001 - 06

INDEX OF SHEETS

1 COVER SHEET
2. GENERAL NOTES
3 SUMMARY OF QUANTITIES
4.-12. PATCHING SCHEDULE
13. TYPICAL SECTION
14. PLAN VIEW

DISTRICT SIX

EXAMINED March 23 20 07
Louis J. Harris
OPERATIONS ENGINEER

EXAMINED Mar 20 20 07
W R
PROGRAM IMPLEMENTATION ENGINEER

EXAMINED Mar 23 20 07
W R
PROGRAM DEVELOPMENT ENGINEER

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

GENERAL NOTES & SIGNATURES

FAP 662 (IL 4/VETERANS PKWY)
SECTION D-6 PAVEMENT PATCHING
SANGAMON COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = 3/23/2007
FILE NAME = c:\projects\d65340\sh\sgamnotes.dgn
PLOT SCALE = 108.4337 ' / IN.
USER NAME = eadsmusaj