CONTRACT: 72B20 SHEET 6 OF 7

PAVEMENT MARKING SCHEDULE				
STATION	TYPE	PAINT PVT MK LINE 5"		
		WHITE	YELLOW	
LT & RT 1863+46.8 TO 1905+86.8	EDGE LINE	8,448 FT		
RT 1863+46.8 TO 1868+86.8	NO PASS		540 FT	
LT 1863+46.8 TO 1868+86.8	SKIP DASH		130 FT	
1868+86.6 TO 1875+92 . 8	SKIP DASH		170 FT	
LT 1875+92.8 TO 1882+92.8	NO PASS		700 FT	
RT 1875+92.8 TO 1882+92.8	SKIP DASH		180 FT	
1882+92.8 TO 1905+86.8	SKIP DASH		570 FT	
LT & RT 1957+13.4 TO 1995+52.2	EDGE LINE	7,392 FT		
1957+13.4 TO 1973+62.2	SKIP DASH		380 FT	
RT 1973+62.2 TO 1983+82.2	NO PASS		1,020 FT	
LT 1973+62.2 TO 1983+82.2	SKIP DASH		260 FT	
LT & RT 1983+82.2 TO 1995+52.2	NO PASS		2,340 FT	
TOTALS		15,840 FT	6,290 FT	

STA. EQ. - 1872+35.5bk=1872+51.5ah STA. EQ. - 1966+64.9bk=1968+07.7ah

NOTES:

STATIONS ARE APPROXIMATE.

MIXTURE REQUIREMENTS		
THE FOLLOWING MIXTURE REQUIREMENTS		
ARE APPLICABLE FOR THIS PROJECT		
MIXTURE USE(S):	H.M.A S.C., MIX C, N50	
AC/PG	PG 64-22	
DESIGN AIR VOIDS:	4.0% @ N DESIGN = 50	
MIXTURE COMP:	IL 9.5 OR 12.5	
FRICTION AGG:	MIX "C"	

SCHEDULES
FAP 317 (US 24)
SECTION (1,2,3&4)RS-8
ADAMS COUNTY