STATE OF ILLINOIS

**DEPARTMENT OF TRANSPORTATION** 

**DIVISION OF HIGHWAYS** 

**PROPOSED** HIGHWAY PLANS


> **FAI ROUTE 64 SECTION 82-(1,2,3,4)I-1** PROJECT: HSIP-064-1(120)005 HIGH TENSION CABLE MEDIAN BARRIER ST. CLAIR COUNTY C-98-046-06


STA. 77 + 46 LAT: 38.62722 LONG: -90.13793 STA. 89 + 00 -STA. 105 + 00 STA. 280 + 00 LAT: 38.61891 LONG: -90.06901

> GRGSS LENGTH = 20,254 FT = 3.84 MILES OMISSION LENGTH = 1,600 FT = 0.303 MILES NET LENGTH = 18,654 FT = 3.53 MILES

RTE. SECTION COUNTY SHEETS
64 82-(1,2,3,4)I-1 ST. CLAIR 42 COUNTY TOTAL SHEET SHEETS NO.

D-98-058-06





PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS


### **HIGHWAY STANDARDS**

FOR INDEX OF SHEETS, SEE SHEET NO. 2

000001-04 701101-01 701400-02 701406-04 701426-02 702001-06

MICROFILMED **REEL NUMBER** AWARDED RESIDENT ENGINEER AS BUILT CHANGES WERE MADE

ON THE FOLLOWING SHEETS



ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION 1-800-892-0123

**CONTRACT NO. 76A18** 

SECTION \$2-(1,2,3,4)1-1 FAI ROUTE 64

DESIGN DESIGNATION

618-346-3179

CHERYL KEPLAR

ENGINEER! PATTI LEBEAU

**PROJECT** 

LEADER:

SQUAD

ST. CLAIR COUNTY

#### GENERAL NOTES

- 1. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
- 2. ILLINOIS STATE LAW REQUIRES A 48 HOUR NOTICE TO BE GIVEN TO UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. (PHONE: 800-892-0123) OR FOR NON MEMBERS. THE UTILITY COMPANIES DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
- · AMEREN IP
- AMEREN UE
- . BUCKEYE PIPE LINE COMPANY
- · CENTERPOINT ENERGY
- ILLINOIS AMERICAN WATER COMPANY . MCLEOD USA TELECOMMUNICATION, INC.
- . MEDIACOM LLC CENTRAL
- . AT&T ILLINOIS
- . CITY OF EAST ST. LOUIS

MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY . NON J.U.L.I.E. MEMBERS MUST BE CONTACTED INDIVIDUALLY.

- 3. ALL EXCAVATION ADJACENT TO THE EDGE OF SHOULDER SHALL BE PROTECTED WITH EXTENDED LEG BARRICADES AND STEADY BURN LIGHTS.
- 4. WHEN NO WORK IS BEING PERFORMED, THE FLAGGERS WILL NOT BE REQUIRED. IF FLAGGERS ARE NOT PRESENT, THE FLAGGER SIGNS SHALL BE REMOVED OR COVERED.
- 5. FLAGMEN SHALL BE PRESENT DURING ALL CLOSURE HOURS. INCLUDING LUNCH HOUR, AND NO ADDITIONAL COMPENSATION WILL BE APPLIED.
- 6. STANDARD 701101 SHALL BE USED FOR SHOULDER CLOSING WITH A SHOULDER CLOSED SIGN. THE COST SHALL BE INCLUDED IN THE TRAFFIC CONTROL PAY ITEMS.
- 7. NO OVERNIGHT LANE CLOSURES WILL BE ALLOWED.
- 8. ALL TRAFFIC CONTROL DEVICES SHALL BE SKID MOUNTED.
- 9. 'ROAD CONSTRUCTION AHEAD' SIGNS SHALL BE PLACED AT THE BEGINNING OF THE PROJECT AND ALL ENTRANCE RAMPS; COST TO BE INCLUDED WITH THE TRAFFIC CONTROL PAY ITEMS. ALL CONSTRUCTION SIGNS SHALL BE FLUORESCENT ORANGE AND 48"X48".
- 10. TOPOGRAPHIC SURVEY WAS PERFORMED FOR THE MEDIAN AREA ONLY. ALL OTHER ITEMS SHOWN WERE CREATED FROM OLD PLANS.
- 11. BEGINNING AND END STATIONS AS SHOWN IN THE PLANS FOR HTC AND MOW STRIP ARE APPROXIMATE. THE R. E. WILL DETERMINE THE EXACT LOCATION.
- 12. A QUANTITY FOR CLASS 2A SEEDING AND MULCH METHOD 1. (3.5 ACRES) HAS BEEN INCLUDED IN THE PLANS TO BE APPLIED TO ALL DISTURBED AREAS AS FINAL SEEDING. APPROPRIATE FERTILIZER NUTRIENTS PER SECTION 250 OF STANDARD SPECIFICATIONS SHALL BE APPLIED. FERTILIZER NUTRIENTS WILL NOT BE PAID FOR SEPARATELY. BUT WILL BE INCLUDED IN THE COST OF SEEDING CLASS 2A.
- 13. THE MINIMUM DEPTH OF THE LINE POST FOUNDATIONS SHALL BE 30".
- 14. THE FOLLOWING MIXTURE REQUIREMENTS APPLY TO THIS PROJECT.

MIXTURE USE	SHOULDERS
AC/PG	PG 58-22
RAP % (MAX)	30%
DESIGN AIR VOIDS	2.0% @ NDES=30
MIX COMPOSITION	
(GRADATION MIXTURE)	
FRICTION AGG	BAM

- 15. ANY FURNISHED EXCAVATION REQUIRED TO MEET THE 4:1 SLOPE REQUIREMENTS FOR THE MOW STRIP WILL BE PAID FOR PER SECTION 109.04 OF THE STANDARD SPECIFICATIONS.
- 16. THE LIMITS OF THE MOW STRIP SHALL BE THE SAME AS THE LIMITS OF THE HTC INCLUDING TERMINAL SECTIONS.
- 17. REMOVED GUARDRAIL SHALL BECOME THE PROPERTY OF THE CONTRACTOR.
- 18. DELINEATOR REMOVAL WILL NOT BE PAID FOR SEPARATELY BUT WILL BE INCLUDED IN THE COST FOR HOT-MIX ASPHALT SHOULDER, 4". REMOVED DELINEATORS SHALL BECOME PROPERTY OF THE CONTRACTOR.
- 19. IN ADDITION TO THE PORTABLE CHANGEABLE MESSAGE SIGNS INCLUDED IN THE TRAFFIC CONTROL STANDARDS, 4 PORTABLE CHANGEABLE MESSAGE SIGNS ARE INCLUDED AND SHALL BE PAID FOR PER SECTION TOL IN THE STANDARD SPECIFICATIONS. THEIR LOCATIONS TO BE DETERMINED BY THE ENGINEER. NO ADDITIONAL PAYMENT WILL BE ALLOWED FOR ANY RELOCATION OF THESE SIGNS.
- 20. REFLECTORS FOR HTC SHALL BE PROVIDED AND INSTALLED PER MANUFACTURER'S SPECIFICATIONS FOR THE TYPE OF HTC BARRIER USED. COST SHALL BE INCLUDED IN HIGH TENSION CABLE MEDIAN BARRIER. MAXIMUM SPACING SHALL BE 50' OR AS DIRECTED BY THE ENGINEER.
- 21. OPEN AUGER HOLES SHALL BE PROTECTED WITH BARRICADES WITH STEADY BURN LIGHTS AT 50' CENTERS AS DIRECTED BY THE ENGINEER. COST TO BE INCLUDED WITH TRAFFIC CONTROL PAY ITEMS.
- 22. HTC SYSTEM SHALL BE CHOSEN FROM THE DEPARTMENT'S APPROVED LIST TO BE USED WHERE MEDIAN SLOPES ARE STEEPER THAN 1:6 AND AS STEEP AS 1:4.
- 23. POST SPACING SHALL BE REDUCED IN FRONT OF MEDIAN HAZARDS AND FOR A DISTANCE OF 100' BEFORE AND 100' AFTER THE MEDIAN HAZARD AS SHOWN IN THE PLANS. THE POST SPACING SHALL BE REDUCED IN ORDER THAT A DEFLECTION OF <= T' IS PROVIDED ACCORDING TO MANUFACTURER'S RECOMMENDATIONS AND AS SUPPORTED BY NCHRP 350 TESTING. COST FOR PROVIDING REDUCED POST SPACING WILL NOT BE PAID FOR SEPARATELY, BUT WILL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR HIGH TENSION CABLE MEDIAN BARRIER.

23. ALL WORK REQUIRED TO PLACE THE HOT MIX ASPHALT SHOULDER (MOW STRIP) INCLUDING, BUT NOT LIMITED TO SAW CUTTING AND THE REMOVAL OF EXISTING HOT MIX-ASPHALT SHOULDER, WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE COST FOR HOT-MIX ASPHALT SHOULDERS 4".

- 24. THE CONTRACTOR SHALL HAVE ALL LANES OF TRAFFIC OPEN DURING PEAK HOURS IN EACH DIRECTION. THE CONTRACTOR WILL NOT BE ALLOWED TO CONDUCT ANY TYPE OF OPERATION IN THE OPEN LANES OR ANY TYPE OF OPERATION THAT WOULD IMPEDE THE FLOW OF TRAFFIC DURING PEAK HOURS. PEAK HOURS ARE DEFINED AS 6:00 AM TO 9:00 AM FOR THE WESTBOUND TRAFFIC AND 3:00 PM TO 6:00 PM FOR THE EASTBOUND TRAFFIC.
- 25. AN ADDITIONAL QUANTITY FOR MULCH METHOD 1, (3.5 ACRES), HAS BEEN INCLUDED IN THE PLANS TO BE APPLIED TO ALL DISTURBED AREAS AS AN EROSION CONTROL MEASURE, AT THE DIRECTION OF THE ENGINEER. MULCH USED FOR EROSION CONTROL SHALL CONFORM TO SECTION 251 OF THE STANDARD SPECIFICATIONS.
- 26. THE PROPOSED SPBGR AND TRAFFIC BARRIER TERMINALS SHOWN IN THE PLANS SHALL COMPLY WITH THE DETAILS IN THE PLANS IN ORDER TO MATCH THE EXISTING GUARDRAIL SYSTEM.

ADT

15th ST. - ST. CLAIR AVE, RAMP

2005 ADT = 62.600 (ACTUAL) 2007 ADT = 63,900 (ESTIMATED) 2027 ADT = 78,000 (ESTIMATED)

SU = 2.7% MU = 10.5%

ST. CLAIR AVE. RAMP - BAUGH AVE.

2007 ADT = 66.200 (FSTIMATED)2027 ADT = 80,200 (ESTIMATED)

SU = 3.0X

BAUGH AVE. TO 25th ST.

2005 ADT = 68.500 (ACTUAL) 2007 ADT = 69,900 (ESTIMATED) 2027 ADT = 85,300 (ESTIMATED)

MIL = 10.17

25th ST - IL RTE 11

2005 ADT = 65.700 (ACTUAL) 2007 ADT = 67,000 (ESTIMATED) 2027 ADT = 81,800 (ESTIMATED) SU = 3.0%

MU = 10.5%

IL RTE 111 - I-255

2005 ADT = 56.600 (ACTUAL) 2007 ADT = 57,700 (ESTIMATED) 2027 ADT = 70,400 (ESTIMATED)

MU = 8.7%

INDEX OF SHEETS

1. COVER SHEET

2. GENERAL NOTES, INDEX OF SHEETS, COMMITMENTS, STANDARDS AND ADT

STA.

SECTION

64 82-(1,2,3,4)I-1 ST. CLAIR 42 2

FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

TO STA.

CONTRACT NO. 76A18 COUNTY TOTAL SHEETS

SUMMARY OF QUANTITIES

4.-5. TYPICAL SECTIONS

SCHEDULES

7.-20. PLAN SHEETS 21. HTC DETAILS

22.-23. STORM WATER PREVENTION POLLUTION PLAN

24.-37. EROSION CONTROL PLAN

38.-42. GUARDRAIL DETAILS

COMMITMENTS:

ILLINOIS DEPARTMENT OF TRANSPORTATION GENERAL NOTES, INDEX OF SHEETS, COMMITMENTS AND ADT FAI ROUTE 64 SECTION 82-(1,2,3,4)I-1 ST. CLAIR COUNTY SCALE: VERT. HORIZ. DRAWN BY

DATE NAME SCALE ENCE

DATE

CHECKED BY

CONTRACT NO. 76A18

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SUMMARY OF QUANTITIES


			CON	ITRA	CT NO.	76A18
F.A.I. RTE.	SECTION		COUNT	Y	TOTAL SHEETS	SHEET NO.
64	82-(1,2,3,4)	[-1	ST. C	LAIR	42	3
STA.		TO	STA.			
EED DO	AD DICT NO	TI I THOTS	EED	ATD	PPO IECT	


			301	MINIAL		<b>UU</b>
SUMMARY OF QUANTITIES			URBAN	CONS 90% FED	TRUCTION TYPE C	ODE
		T	TOTAL	10% STATE SFTY-4A		
CODE NO	ITEM	UNIT	QUANTITIES	SF11-HA		
20200100	EARTH EXCAVATION	CU YD	629	629		
25000210	SEEDING, CLASS 2A	ACRE	3.5	3.5		
25100105	MULCH, METHOD 1	ACRE	7	7		
48203013	HOT-MIX ASPHALT SHOULDERS, 4"	SQ YD	5657	5657		
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	2437.5	2437.5		
63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	2	2		
63200310	GUARDRAIL REMOVAL	F00T	828.5	828.5		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL, MO	2	2		
67100100	MOBILIZATION	L SUM	1	1		
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	10	10		
78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16		
80300100	LOCATING UNDERGROUND CABLE	FOOT	50	50		
X0325589	HIGH TENSION CABLE MEDIAN BARRIER	FOOT	13368	13368		
X0325590	HIGH TENSION CABLE MEDIAN BARRIER TERMINAL	EACH	14	14		

· · · · · · · · · · · · · · · · · · ·	SUMMARY OF QUANTITIES			CONS	TRUCTION TYPE (	CODE
CODE NO	SUMMART OF QUANTITIES	UNIT	TOTAL QUANTITIES			
CODE NO	11EM	OWIT	GOWNITIES			
	٧					
,						
	·					
					· · · · · · · · · · · · · · · · · · ·	
	***					
			:			
	·					
				5		[
	Rev.	<u> </u>	<u> </u>	L		1

PLOT DATE. = SDATES FILE NAME = SFILELS PLOT SCALE = SCALES REFERENCE = SREFS

SPECIALTY ITEMS





#### HIGH TENSION CABLE MEDIAN BARRIER

				HTC BARRIER	HTC BARRIER
					TERMINAL
RT/LT/CL	STATION	ТО	STATION	FOOT	EACH
CL	106+60		107+10		1
CL	107+10		118+00	1090	
CL	118+00		119+50	150	
CL .	119+50		120+00		1
RT	144+92		145+42		1
RT	145+42		148+00	258	
RT	148+00		150+85	285	
RT	150+85		151+35		1
LT	150+68		151+18	-	1
LT	151+18		157+33	615	
LT	157+33		157+83		1
RT	158+94		159+44		1
RT	159+44		163+00	356	
RT	163+00		178+00	1500	
RT	178+00		193+00	1500	
RT	193+00		201+16	816	
RT	201+16		201+66		1
LT	201+04		201+54		1
LT	201+54		208+00	646	
LT	208+00		223+00	1500	
LT	223+00		238+00	1500	
LT -	238+00		244+60	660	
LT	244+60		245+10		1
RT	248+50		249+00		11
RT	249+00		253+00	400	
RT	253+00		260+70	770	-
RT	260+70		261+20		1
RT	265+78		266+28		1
RT	266+28		268+00	172	
RT	268+00		279+50	1150	
RT	279+50		280+00		1
			TOTAL	13368	14

#### HOT MIX ASPHALT SHOULDER, 4"

RT/LT	STATION	TO	STATION	LENGTH	WIDTH	SQ YE
RT	144+92		148+00	308	4	137
RT	148+00		151+35	335	4	149
LT	150+68		157+83	715	4	318
RT	158+94		163+00	406	4	. 180
RT	163+00		178+00	1500	4	667
RT	178+00		193+00	1500	4	667
RT	193+00		201+66	866	4	385
LT	201+04		208+00	696	4	309
LT	208+00		223+00	1500	4	667
LT	223+00		238+00	1500	4	667
LT	238+00		245+10	710	4	316
RT	248+50		253+00	450	4	200
RT	253+00		261+20	820	4	364
RT	265+00		268+00	300	4	133
RT	268+00		280+00	1200	4	533
<del></del>				TOTAL		5692

## EARTHWORK SCHEDULE


LOCATION	EARTH EXCAVATION	EARTH EXCAVATION ADJ FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR
	CUBIC YARD	(25%) CUBIC YARD	CUBIC YARD	SHORTAGE (-) CUBIC YARD
144+92 +o 280+00	629	472	0	472
106+57 to 120+00	0	0	150	-150
TOTAL	629	472	150	322


APPROXIMATELY 150 CY OF FURNISHED EXCAVATION WILL BE REQUIRED BETWEEN STATION 106+57
AND STATION 120+00 IN ORDER TO RE-GRADE THE MEDIAN SLOPES TO 8:1. THE EARTH
EXCAVATION GENERATED BY THE PLACEMENT OF THE HOT MIX ASPHALT SHOULDER (MOW STRIP)
SHALL BE USED. THE EXCESS EARTH EXCAVATION SHALL BE DISPOSED OF BY CONTRACTOR
PER SECTION 202 OF THE STANDARD SPECIFICATIONS.

#### GUARDRAIL SCHEDULE


			<u> </u>				
	1				STEEL PLATE	TRAFFIC BARRIER	
			1	GUARDRAIL	BEAM GUARDRAIL	TERMINAL	GUARDRAIL MARKERS
RT/LT	STATION	TO	STATION	REMOVAL	TYPE A	TYPE 5	TYPE A
		<u> </u>		FOOT	FOOT .	EACH	EACH
RT	77+34		77+46	12.5			
RT	83+77		84+27	50			
LT	78+78		79+28	50			
LT	125+10	1	125+60	50			
LT	129+58		129+70.5	12.5			
RT	126+22		126+72	50			
RT	195+30		197+69	239			-1
LT	210+48		213+75	327			
RT	77+40		83+77		637.5		4
LT	78+78		87+25		850		4
LT	125+09		129+70.5		462.5		4
RT	121+97	1	126+72		475		4
LT	87+25		87+38			1	
RT	121+84		121+97			1	
			1				
			TOTAL	701	0.405		
			TOTAL	791	2425	2	16


REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION					
NAME	DATE	ILLINOIS	DELANTMENT OF TRANSPORTATION				
			SCHEDULES				
		] SCHEDULES					
			FAI ROUTE 64				
		SECTION 82-(1,2,3,4)I-1 ST. CLAIR COUNTY					
			SI CLAIR COUNTI				
		VERT.					
		SCALE: HORIZ.	DRAWN BY				
		DATE	CHECKED BY				







| CONTRACT NO. 76A18 | F.A.I. | SECTION | COUNTY | TOTAL SHEET NO. 76A18 | SHEET NO. 76A18 | ST. CLAIR | 42 | 9 | STA. TO STA. | TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT STA. 107+10 TO STA. 118+00 HIGH TENSION CABLE MEDIAN BARRIER - 1090 FT TS \* 50' DUE TO MEDIAN RE-GRADING, MEDIAN INLET AND UNDERDRAIN OUTLETS MAY REQUIRE ADJUSTMENT (METHOD SUBJECT TO APPROVAL BY ENGINEER). THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT WILL BE INCLUDED IN THE CONTRACT UNIT PRICE FOR EARTH EXCAVATION. \* HIGH TENSION CABLE MEDIAN BARRIER TERMINAL - 1 EACH ILLINOIS DEPARTMENT OF TRANSPORTATION BM: ELEV. 432.92 STA. 110+72 CHISELED 'X' ON NORTH SIDE OF CONC. LIGHT POLE FOUNDATION PLAN VIEW FAI RTE 64 SECTION 82-(1,2,3,4)I-1 ST. CLAIR COUNTY SCALE: VERT. DRAWN BY DATE CHECKED BY









STA. 163+00 TO STA. 178+00 HIGH TENSION CABLE MEDIAN BARRIER ~ 1500 FT ILLINOIS DEPARTMENT OF TRANSPORTATION PLAN VIEW BM: ELEV. 419,94 STA, 176+00 CHISELED X'ON NORTH SIDE OF CONC. LIGHT POLE FOUNDATION FAI RTE 64 SECTION 82-(1,2,3,4)I-1 ST. CLAIR COUNTY PLOT DATE = #DATE# FILE NAME = #FILEL# PLOT SCALE = #SCALE# REFERENCE = #REF# SCALE: VERT. DRAWN BY








PC STATION 196+67.57 SET I.P. WITH CAP

## HIGH TENSION CABLE MEDIAN BARRIER TERMINAL - 1 EACH



BM: ELEV. 419.42 STA. 205+05 CHISELED 'X' ON NORTH SIDE OF CONC. LIGHT POLE FOUNDATION

KEAT2TOM2					
NAME	DATE				
	T				

ILLINOIS DEPARTMENT OF TRANSPORTATION PLAN VIEW


FAI RTE 64 SECTION 82-(1,2,3,4)I-1 ST. CLAIR COUNTY


SCALE: VERT. DATE

DRAWN BY CHECKED BY

PLOT DATE = #DATE# FILE NAME = #FILEL# PLOT SCALE = #SCALE# REFERENCE = #REF#

| CONTRACT NO. 76418 |
F.A.I.	SECTION	COUNTY	SHEETS	NO.
64	82-(1,2,3,4)	ST. CLAIR	42	16
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID	PROJECT	





PT STATION 208+78.66 SET I.P. WITH CAP

BM: FLEV. 421.39 STA. 215+30 CHISELED 'X' ON NE BOLT OF LIGHT POLE BASE PLATE

L	REVISIONS			
	NAME	DATE		
			ŀ	
	+			

ILLINOIS DEPARTMENT OF TRANSPORTATION PLAN VIEW

FAI RTE 64 SECTION 82-(1,2,3,4)I-1 ST. CLAIR COUNTY

SCALE: VERT.

CHECKED BY


PLOT DATE = #DATE# FILE NAME = #FILEL# PLOT SCALE = #SCALE# REFERENCE = #REF#

SET MAG NAIL IN EOS FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT SET MAG NAIL IN EOS PC STATION 232+22.48 SET I.P. WITH CAP STA, 223+00 TO STA, 238+00 HIGH TENSION CABLE MEDIAN BARRIER - 1500 FT ILLINOIS DEPARTMENT OF TRANSPORTATION BM: ELEV. 421.74 STA. 228+50 CHISELED 'X' ON WEST SIDE OF CONC. LIGHT POLE FOUNDATION PLAN VIEW FAI RTE 64 SECTION 82-(1,2,3,4)I-1 ST. CLAIR COUNTY SCALE: VERT. CHECKED BY

CONTRACT NO. 76A18
COUNTY TOTAL SHEET NO.
ST. CLAIR 42 18 SECTION COUNTY F.A.I. SECTION COUNTY
64 82-(1,2,3,4)I-1 ST. CLAIR TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT SET MAG NAIL IN EOS PT STATION 249+19,48 SET I.P. WITH CAP EXIST. CURVE 7
PI STA. = 240+77.24


\$\Delta = 16\circ 58' 12'' (RT)
0 = 1\circ 00' 00''
R = 5,729.58'
T = 854.76'
L = 1,697.00'
E = 63.41'
e = I-64 OVER ALTON & SOUTHERN RR e = \_\_\_\_\_ T.R. = \_\_\_\_\_ S.E. RUN = \_\_\_\_\_ P.C. STA. = 232+22.48 P.T. STA. = 249+19.48 \* HIGH TENSION CABLE MEDIAN BARRIER TERMINAL - 1 EACH STA. 249+00 TO STA. 253+00 HIGH TENSION CABLE MEDIAN BARRIER - 400 FT -STA. 238+00 TO STA. 244+60 HIGH TENSION CABLE MEDIAN BARRIER - 660 FT \* HIGH TENSION CABLE MEDIAN BARRIER TERMINAL - 1 EACH ILLINOIS DEPARTMENT OF TRANSPORTATION PLAN VIEW FAI RTE 64 SECTION 82-(1,2,3,4)I-1 ST. CLAIR COUNTY SCALE: VERT. CHECKED BY

PLOT DATE = #DATE# FILE NAME = #FILEL# PLOT SCALE = #SCALE# REFERENCE = #REFF#




CONTRACT NO. 76A18 RTE. SECTION COUNTY TOTAL SHEET NO. 64 82-(1,2,3,4)I-1 ST. CLAIR TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT END PROJECT STA. 280+00 J 270+00 i i \* HIGH TENSION CABLE MEDIAN BARRIER TERMINAL - 1 EACH STA. 268+00 TO STA. 279+50 HIGH TENSION CABLE MEDIAN BARRIER - 1150 FT ILLINOIS DEPARTMENT OF TRANSPORTATION PLAN VIEW FAI RTE 64 SECTION 82-(1,2,3,4)I-1 ST. CLAIR COUNTY PLOT DATE = #DATE# FILE NAME = #FILEL# PLOT SCALE = #SCALE# REFERENCE = #REF# SCALE: VERT. HORIZ. DATE DRAWN BY CHECKED BY


COUNTY TOTAL SHEET NO. F.A.I. SECTION 64 82-(1,2,3,4)I-1 ST. CLAIR 42 21 TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT




#### HTC LAYOUT & PLAN NOTATION FOR LIMITED DEFLECTION LOCATION




HTC LAYOUT FOR TERMINATION IN FRONT OF FLARED GUARDRAIL




HTC LAYOUT FOR TERMINATION BEHIND TANGENT GUARDRAIL




#### HTC LAYOUT ADJACENT TO GUARDRAIL



HTC LAYOUT AT MEDIAN CROSSOVERS



HTC LAYOUT FOR MEDIAN HAZARD PROTECTION



HTC LAYOUT FOR PLACEMENT ON OPPOSITE SIDES

\* FOR PURPOSES OF HTC LAYOUT SHOWN IN PLANS, 44' FOR LON POINT WAS USED. ACTUAL LON POINT WILL VARY DEPENDING ON HTC SYSTEM USED.

PAY LENGTH FOR HTC MEDIAN BARRIER TERMINAL IS 50' REGARDLESS OF LON POINT.

SCALE: VERT.

ILLINOIS DEPARTMENT OF TRANSPORTATION HTC DETAILS

> FAI ROUTE 64 SECTION 82-(1,2,3,4)I-1 ST. CLAIR COUNTY

> > CHECKED BY

#### DESCRIPTION OF STABILIZATION PRACTICES DURING CONSTRUCTION:

- DURING CONSTRUCTION, AREAS OUTSIDE THE CONSTRUCTION LIMITS AS OUTLINED PREVIOUSLY HEREIN SHALL BE PROTECTED. THE CONTRACTOR SHALL NOT USE THIS AREA FOR STAGING (EXCEPT AS DESCRIBED ON THE PLANS AND DIRECTED BY THE ENGINEER), PARKING OF VEHICLES OR CONSTRUCTION EQUIPMENT, STORAGE OF MATERIALS, OR OTHER CONSTRUCTION RELATED ACTIVITIES.
- (a.) WITHIN THE CONSTRUCTION LIMITS, AREAS WHICH MAY BE SUSCEPTIBLE TO EROSION AS DETERMINED BY THE ENGINEER SHALL REMAIN UNDISTURBED UNTIL FULL SCALE CONSTRUCTION IS UNDERWAY TO PREVENT UNNECESSARY SOIL EROSION.
- (b.) EARTH STOCKPILES SHALL BE TEMPORARILY SEEDED IF THEY ARE TO REMAIN UNUSED FOR MORE THAN FOURTEEN DAYS.
- (c.) AS CONSTRUCTION PROCEEDS. THE CONTRACTOR SHALL INSTITUTE THE FOLLOWING AS DIRECTED BY THE ENGINEER:
- I. PLACE TEMPORARY EROSION CONTROL FACILITIES AT LOCATIONS SHOWN ON THE PLANS
- II. TEMPORARILY SEED ERODABLE BARE EARTH ON A WEEKLY BASIS TO MINIMIZE THE AMOUNT OF ERODABLE SURFACE
- TILL CONSTRUCT ROADSIDE DITCHES AND PROVIDE TEMPORARY EROSION CONTROL SYSTEMS.
- IV. TEMPORARILY DIVERT WATER AROUND PROPOSED CULVERT LOCATIONS.
- V. BUILD NECESSARY EMBANKMENT AT CULVERT LOCATIONS AND THEN EXCAVATE AND PLACE CULVERT.
- VI. CONTINUE BUILDING UP THE EMBANKMENT TO THE PROPOSED GRADE WHILE AT THE SAME TIME, PLACING PERMANENT CONTROL SUCH AS RIPRAP DITCH LINING AND CONDUCTING FINAL SHAPING TO THE SLOPES.
- (d.) EXCAVATED AREAS AND EMBANKMENT SHALL BE PERMANENTLY SEEDED IMMEDIATELY AFTER FINAL GRADING. IF NOT. THEY SHALL BE TEMPORARILY SEEDED IF NO CONSTRUCTION ACTIVITY IN THE AREA IS PLANNED FOR 7 DAYS.
- (e.) CONSTRUCTION EQUIPMENT SHALL BE STORED AND FUELED ONLY AT DESIGNATED LOCATIONS. ALL NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OF OTHER POLLUTANT IN ACCORDANCE WITH EPA WATER QUALITY REGULATIONS. LEAKING EQUIPMENT OR SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR REMOVED FROM THE SITE.
- (f.) THE RESIDENT ENGINEER SHALL INSPECT THE PROJECT DAILY DURING CONSTRUCTION ACTIVITIES. INSPECTION SHALL ALSO BE DONE WEEKLY AND AFTER RAINS OF 1/2 INCH OR GREATER OR EQUIVALENT SNOWFALL AND DURING THE WINTER SHUTDOWN PERIOD. THE PROJECT SHALL ADDITIONALLY BE INSPECTED BY THE CONSTRUCTION FIELD ENGINEER ON A BI-WEEKLY BASIS TO DETERMINE THAT EROSION CONTROL EFFORTS ARE IN PLACE AND EFFECTIVE AND IF OTHER
- (g) SEDIMENT COLLECTED DURING CONSTRUCTION OF THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF ON THE SITE ON A REGULAR BASIS AS DIRECTED BY THE ENGINEER. THE COST OF THIS MAINTENANCE SHALL BE INCLUDED IN THE UNIT BID PRICE FOR EARTH EXCAVATION.
- (h) THE TEMPORARY EROSION CONTROL SYSTEMS SHALL BE REMOVED AS DIRECTED BY THE ENGINEER AFTER USE IS NO LONGER NEEDED OR NO LONGER FUNCTIONING. THE COST OF THIS REMOVAL SHALL BE INCLUDED IN THE UNIT BID PRICE FOR TEMPORARY EROSION CONTROL SYSTEM.

#### DESCRIPTION OF STRUCTURAL PRACTICES AFTER FINAL GRADING:

- TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION
  CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS SEEDED AND ESTABLISHED.
- ONCE PERMANENT EROSION CONTROL SYSTEMS AS PROPOSED IN THE PLANS ARE FUNCTIONAL AND ESTABLISHED, TEMPORARY ITEMS SHALL BE REMOVED, CLEANED UP, AND DISTURBED TURF RESEEDED.

#### MAINTENANCE AFTER CONSTRUCTION:

1. CONSTRUCTION IS COMPLETE AFTER ACCEPTANCE BY I.D.O.T. FINAL INSPECTION. MAINTENANCE UP TO THIS DATE WILL BE BY THE CONTRACTOR.

#### MISCELLANEOUS:

1. A QUANTITY FOR MULCH METHOD 1, BASED ON AN ESTIMATED 8' WIDE AREA (3.5 ACRES), HAS BEEN INCLUDED IN THE PLANS TO BE APPLIED TO ALL DISTURBED AREAS AS AN EROSION CONTROL MEASURE AT THE DIRECTION OF THE ENGINEER. MULCH USED FOR EROSION CONTROL WILL BE PAID FOR SEPARATELY AND SHALL CONFORM TO SECTION 251 OF THE STANDARD SPECIFICATIONS.

ANY DISTURBANCE BEYOND THE 8' WIDTH , MEASURED FROM THE EDGE OF EXISTING SHOULDER, SHALL BE MULCHED PER SECTION 251 AND SHALL BE AT THE CONTRACTOR'S EXPENSE.

LEGEND

TEMPORARY DITCH CHECK- ROLLED EXCELSIOR, SILT WEDGES/PANELS

302 TEMPORARY DITCH CHECK- AGGREGATE

EROSION CONTROL BLANKET

PERIMETER EROSION BARRIER- SILT FILTER FENCE OR OTHER AS APPROVED BY THE ENGINEER

INLET AND PIPE PROTECTION- STRAW BALES, FILTER FABRIC, AGGREGATES

 $\bigoplus$ 

MULCH

ILLINOIS DEPARTMENT OF TRANSPORTATION STORM WATER POLLUTION PREVENTION PLAN FAI ROUTE 64 SECTION 82-(1,2,3,4)I-1 ST. CLAIR COUNTY SCALE: VERT. DATE

#### STORM WATER POLLUTION PREVENTION PLAN

THE FOLLOWING PLAN IS ESTABLISHED AND INCORPORATED IN THE PROJECT TO DIRECT THE CONTRACTOR IN THE PLACEMENT OF TEMPORARY EROSION CONTROL SYSTEMS AND TO PROVIDE A STORM SEWER WATER POLLUTION PREVENTION PLAN FOR COMPLIANCE UNDER NPDES.

THE PURPOSE OF THIS PLAN IS TO MINIMIZE EROSION WITHIN THE CONSTRUCTION SITE AND TO LIMIT SEDIMENTS FROM LEAVING THE CONSTRUCTION SITE BY UTILIZING PROPER TEMPORARY EROSION CONTROL SYSTEMS AND PROVIDING GROUND COVER WITHIN A REASONABLE AMOUNT OF TIME.

CERTAIN EROSION CONTROL FACILITIES SHALL BE INSTALLED BY THE CONTRACTOR AT THE BEGINNING OF CONSTRUCTION. OTHER ITEMS SHALL BE INSTALLED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER ON A CASE BY CASE SITUATION DEPENDING ON THE CONTRACTOR'S SEQUENCE OF ACTIVITIES, TIME OF YEAR, AND EXPECTED WEATHER CONDITIONS.

THE CONTRACTOR SHALL INSTALL PERMANENT EROSION CONTROL SYSTEMS AND SEEDING WITHIN A TIME FRAME SPECIFIED HEREIN AND AS DIRECTED BY THE ENGINEER, THEREFORE MINIMIZING THE AMOUNT OF AREA SUSCEPTIBLE TO EROSION AND REDUCING THE AMOUNT OF TEMPORARY SEEDING. THE ENGINEER WILL DETERMINE IF ANY TEMPORARY EROSION CONTROL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED AND IF ANY ADDITIONAL TEMPORARY EROSION CONTROL SYSTEMS, WHICH ARE NOT INCLUDED IN THIS PLAN, SHALL BE ADDED. THE CONTRACTOR SHALL PERFORM ALL WORK AS DIRECTED BY THE ENGINEER AND AS SHOWN IN STANDARD 280001 OF THE PLANS.

#### SITE DESCRIPTION

DESCRIPTION OF CONSTRUCTION ACTIVITY:

- 1. THE PROJECT CONSISTS OF INSTALLING HIGH TENSION CABLE MEDIAN BARRIER.
- CONSTRUCTION INCLUDES PLACEMENT OF A HOT-MIX ASPHALT SHOUDER, HIGH TENSION CABLE MEDIAN BARRIER, GUARDRAIL REMOVAL AND INSTALLATION OF NEW STEEL PLATE BEAM GUARDRAIL.

## DESCRIPTION OF INTENDED SEQUENCE FOR MAJOR CONSTRUCTION ACTIVITIES WHICH WILL DISTURB SOILS FOR MAJOR PORTIONS OF THE CONSTRUCTION SITE:

- EXCAVATION FOR HOT-MIX ASPHALT SHOULDER INSTALLATION AND INSTALLATION OF HIGH TENSION CABLE MEDIAN BARRIER.
- GUARDRAIL REMOVAL.
- 3. INSTALLATION OF STEEL PLATE BEAM GUARDRAIL.

#### AREA OF CONSTRUCTION SITE:

THE TOTAL AREA OF THE CONSTRUCTION SITE IS ESTIMATED TO BE 3.5 ACRES OF WHICH 3.5 ACRES WILL BE DISTURBED BY EXCAVATION, GRADING, AND OTHER ACTIVITIES.

OTHER REPORTS, STUDIES AND PLANS WHICH AID IN THE DEVELOPMENT OF THE STORM WATER POLLUTION PREVENTION PLAN AS REFERENCED DOCUMENTS:

- INFORMATION OF THE SOILS AND TERRAIN WITHIN THE SITE WAS OBTAINED FROM TOPOGRAPHIC SURVEYS AND SOIL BORINGS THAT WERE UTILIZED FOR THE DEVELOPMENT OF THE PROPOSED TEMPORARY EROSION CONTROL SYSTEMS.
- PROJECT PLAN DOCUMENTS, STANDARD SPECIFICATIONS, AND PLAN DRAWINGS INDICATING DRAINAGE
  PATTERNS AND APPROXIMATE SLOPES ANTICIPITATED AFTER GRADING ACTIVITIES WERE UTILIZED FOR THE PROPOSED
  PLACEMENT OF THE TEMPORARY EROSION CONTROL SYSTEMS.

DRAINAGE TRIBUTARIES AND SENSITIVE AREAS RECEIVING RUNOFF FROM THIS CONSTRUCTION SITE:

- HARDING DITCH
- 2. TRIBUTARIES TO HARDING DITCH.

CONTROLS • EROSION CONTROLS AND SEDIMENT CONTROL

DESCRIPTION OF STABILIZATION PRACTICES AT THE BEGINNING OF CONSTRUCTION:

- THE DRAWINGS, SPECIFICATIONS AND SPECIAL PROVISIONS WILL ENSURE THAT EXISTING VEGETATION IS PRESERVED WHERE ATTAINABLE AND DISTURBED PORTIONS OF THE SITE WILL BE STABILIZED. STABILIZATION PRACTICES INCLUDE: TEMPORARY SEEDING, PERMANENT SEEDING, MULCHING, PROTECTION OF TREES, PRESERVATION OF MATURE VEGETATION, AND OTHER APPROPRIATE MEASURES AS DIRECTED BY THE ENGINEER. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN 7 DAYS AFTER THE CONSTRUCTION ACTIVITY IN THAT PORTION OF THE SITE HAS TEMPORARILY OR PERMANENTLY CEASED.
- (g.) AREAS OF EXISTING VEGETATION (WOOD AND GRASSLANDS) OUTSIDE THE PROPOSED CONSTRUCTION LIMITS SHALL BE IDENTIFIED BY THE ENGINEER FOR PRESERVING AND SHALL BE PROTECTED FROM CONSTRUCTION ACTIVITIES.
- (b.) DEAD, DISEASED, OR UNSUITABLE VEGETATION WITHIN THE SITE SHALL BE REMOVED AS DIRECTED BY THE ENGINEER, ALONG WITH REQUIRED TREE REMOVAL.
- (c.) AS SOON AS REASONABLE ACCESS IS AVAILABLE TO ALL LOCATIONS WHERE WATER DRAINS AWAY FROM THE PROJECT, TEMPORARY DITCH CHECKS, INLET AND PIPE PROTECTION, AND PERIMETER EROSION BARRIER SHALL BE INSTALLED AS CALLED OUT IN THIS PLAN AND DIRECTED BY THE ENGINEER.
- (d.) BARE AND SPARSELY VEGETATED GROUND IN HIGH ERODABLE AREAS AS DETERMINED BY THE ENGINEER SHALL BE TEMPORARILY SEEDED AT THE BEGINNING OF CONSTRUCTION WHERE NO CONSTRUCTION ACTIVITIES ARE EXPECTED WITHIN SEVEN DAYS.
- (e.) IMMEDIATELY AFTER TREE REMOVAL IS COMPLETED, AREAS WHICH ARE HIGHLY ERODABLE AS DETERMINED BY THE ENGINEER, SHALL BE TEMPORARILY SEEDED WHEN NO CONSTRUCTION ACTIVITIES ARE EXPECTED WITHIN SEVEN DAYS.
- (f.) AT LOCATIONS WHERE A SIGNIFICANT AMOUNT OF WATER DRAINS INTO THE CONSTRUCTION ZONE FROM OUTSIDE AREAS (ADJACENT LANDOWNERS), TEMPORARY DITCH CHECKS WILL BE UTILIZED TO LOCALLY DIVERT WATER, REDUCE FLOW RATES, AND COLLECT OUTSIDE SILATION INSIDE THE RIGHT-OF-WAY LINE.
- ESTABLISHMENT OF THESE TEMPORARY EROSION CONTROL MEASURES WILL HAVE ADDITIONAL BENEFITS TO THE PROJECT.
  DESTRABLE GRASS SEED WILL BECOME ESTABLISHED IN THESE AREAS AND WILL SPREAD SEEDS ONTO THE CONSTRUCTION
  SITE UNTIL PERMANENT SEEDING/MOWING AND OVERSEEDING CAN BE COMPLETED.

THIS PLAN HAS BEEN PREPARED TO COMPLY WITH THE PROVISIONS OF THE NPDES PERMIT NUMBER ILRIO, ISSUED BY THE ILLINOIS ENVIRONMENTAL PROTECTION AGENCY FOR STORM WATER DISCHARGES FROM CONSTRUCTION SITE ACTIVITIES.

I CERTIFY UNDER PENALTY OF LAW THAT THIS DOCUMENT AND ALL ATTACHMENTS WERE PREPARED UNDER MY DIRECTION OR SUPERVISION IN ACCORDANCE WITH A SYSTEM DESIGNED TO ASSURE THAT QUALIFIED PERSONNEL PROPERLY GATHERED AND EVALUATED THE INFORMATION SUBMITTED. BASED ON MY INQUIRY OF THE PERSON WHO MANAGE THE SYSTEM, OR THOSE PERSONS DIRECTLY RESPONSIBLE FOR CATHERING THE INFORMATION, THE INFORMATION SUBMITTED IS, TO THE BEST OF MY KNOWLEDGE AND BELIEF, TRUE, ACCURATE AND COMPLETE. I AM AWARE THAT THERE ARE SIGNIFICANT PENALTIES FOR SUBMITTING FALSE INFORMATION, INCLUDING THE POSSIBILITY OF FINE AND IMPRISONMENT FOR KNOWING VIOLATIONS.

Man C Jamis
DEPUTY DIRECTOR OF HIGHWAYS
REGION FIVE ENGINEER

DATE

REVISIONS
NAME
DATE

SCA
DAT


ILLINOIS DEPARTMENT OF TRANSPORTATION STORM WATER POLLUTION PREVENTION PLAN


FAI ROUTE 64
SECTION 82-(1,2,3,4)I-1
ST. CLAIR COUNTY
DRAWN BY

DATE = #DA NAME = #FIL SCALE = #SC RENCE = #RE


SCALE: VERT. HORIZ.


CHECKED BY







| CONTRACT NO. 76A18 | F.A.I. | SECTION | COUNTY | TOTAL | SHEETS | NO. 76A18 | STA. | TO STA. | FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT ILLINOIS DEPARTMENT OF TRANSPORTATION EROSION CONTROL PLAN FAI RTE 64 SECTION 82-(1,2,3,4)I-1 ST. CLAIR COUNTY SCALE: VERT. DRAWN BY









ILLINOIS DEPARTMENT OF TRANSPORTATION EROSION CONTROL PLAN PLOT DATE = #DATE# FILE NAME = #FILEL# PLOT SCALE = #SCALE# REFERENCE = #REF# FAI RTE 64 SECTION 82-(1,2,3,4)I-1 ST. CLAIR COUNTY SCALE: VERT. DRAWN BY CHECKED BY





FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT IL RTE 111 OVER I-64 ILLINOIS DEPARTMENT OF TRANSPORTATION EROSION CONTROL PLAN MULCH PLOT DATE = #DATE# FILE NAME = #FLEL# PLOT SCALE = #SCALE# REFERNCE = #REF# FAI RTE 64 SECTION 82-(1,2,3,4)I-1 ST. CLAIR COUNTY SCALE: VERT. HORIZ. DATE DRAWN BY


| CONTRACT NO. 76A18 | F.A.I. | SECTION | COUNTY | SHEETS | NO. | SHEET | SHEET | NO. | SHEET | SHEET | NO. | SHEET | SHEE TO STA. FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT ILLINOIS DEPARTMENT OF TRANSPORTATION EROSION CONTROL PLAN MULCH FAI RTE 64 SECTION 82-(1,2,3,4)I-1 ST. CLAIR COUNTY SCALE: VERT. HORIZ. DRAWN BY CHECKED BY





| COUNTY | TOTAL | SHEET | NO. |
| COUNTY | SHEETS | NO. |
| ST. CLAIR | 42 | 36 | | CONTRAC | COUNTY | S | 64 | 82-(1,2,3,4)1-1 | ST. CLAIR | STA. | TO STA. | FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT EXIST. CURVE 8
PI STA. = 262+18.06

\$\Delta = 17^\circ 31'\circ 55''\ (LT)
D = 1^\circ 29'\circ 53''\
R = 3,825.00'\tau
T = 589.82'\tau
L = 1,170.42'\tau
E = 45.21' e = \_\_\_\_ T.R. = \_\_\_\_ S.E. RUN = \_\_\_ P.C. STA. = 256+28.24 P.T. STA. = 267+98.66 ILLINOIS DEPARTMENT OF TRANSPORTATION EROSION CONTROL PLAN PLOT DATE = \$DATE\$
FILE NAME = \$FILEL\$
PLOT SCALE = \$SCALE\$
REFERENCE = \$REF\$ FAI RTE 64 SECTION 82-(1,2,3,4)I-1 ST. CLAIR COUNTY SCALE: VERT.


CONTRACT NO. 76A18
COUNTY TOTAL SHEET NO. ILLINOIS DEPARTMENT OF TRANSPORTATION EROSION CONTROL PLAN FAI RTE 64
SECTION 82-(1,2,3,4)I-1
ST. CLAIR COUNTY SCALE: VERT. DRAWN BY







WOOD POST CONSTRUCTION








PLATE A






POST OR SPLICE BOLT & NUT


ILLINOIS DEPARTMENT OF TRANSPORTATION

STEEL PLATE BEAM GUARDRAIL

FAI ROUTE 64 SECTION 82-(1,2,3,4)I-1 ST. CLAIR COUNTY



CONTRACT NO. 76A18



#### Note:

If it is necessary for D to be more than 300 (12) and less than 3.0 m (10'-0'') type M-5 (M-2) curb and gutter (Std. 606001) shall be used in front of and in advance of the guardrail.


### PLAN

203(8) min. (Steel post) 250(10) min. (Wood post)

Optional round hole

## GUARDRAIL PLACED BEHIND CURB


 $(D = 0 \text{ desirable } \pm 0.300 \text{ (12) maximum)}$ 



ELEVATION

# FOOTING FOR POST WHEN IMPERVIOUS MATERIAL IS ENCOUNTERED

V	W	L	-
	yv	Steel Post	Wood Post
0 - 460 (0 - 18)	<b>610</b> (24)	530 (21)	<b>580</b> (23)
>460 - 825 (>18 - 41.5)	. <b>305</b> (12)	203 (8)	<b>250</b> (10)
>825 - 1.13 m (>41.5 - 53.5)	<b>305 - 0</b> (12 - 0)	203 (8)	<b>250</b> (10)



WOOD BLOCK-OUT AND STEEL POST DETAILS

## CABLE ASSEMBLY

(18,100 kg (40,000 lbs.) min. breaking strength) Tighten to taut tension.

ILLINOIS DEPARTMENT OF TRANSPORTATION

STEEL PLATE BEAM GUARDRAIL

FAI ROUTE 64 SECTION 82-(1,2,3,4)I-1 ST, CLAIR COUNTY

(Sheet 4 of 4)

